



JOHN PHILLIPS
CONSTRUCTION
CCB# 120868

Mykie's Bar & Lounge
Patio Cover Proposal
155 Liberty St. NE
Salem, OR 97301

Scope of Work:

- Construct an approximately 32' x 18' covered porch per plans.
The construction will consist of glu-lam beams approximately 6' on center with 2" x 6" fir stringers between at 24" on center. The structure will hang from existing angle iron with 1/2" threaded rod at 36" on center as to not attach to the existing brick wall.
- Install (4) Architectural Specialties 2' x 4' skylights as shown on plans.
- Install corrugated metal roofing on framing members and flash skylights.
- Install 1" x 8" horizontal fir siding with 1" spacing on 4" x 4" posts per plans.
- Install black "Hog Wire" fencing above fir siding to close off area to the bottom of the roof per plans.
- Clean and remove all construction debris from job site when project is complete.

Total cost: \$24,500.00	Accepted By:
	Date: