



PROJECT DESCRIPTION

THIS PROJECT WILL ADDRESS SECURITY AND SAFETY ISSUES WITH THE EXISTING PARKING STRUCTURE. STAIR TOWERS ON THE FOUR CORNERS WILL BE DEMOLISHED AND REPLACED WITH OPEN STAIRS FEATURING NEW SIGNAGE. CANOPIES WILL BE ADDED TO THE THIRD FLOOR PERIMETER PARKING STALLS ON THE WEST, SOUTH, AND EAST SIDES. ON THE EXTERIOR COLUMNS, VERTICAL FINS AND PERFORATED METAL SCREENS WILL BE ADDED TO THE EXTERIOR CONCRETE FACES TO PROVIDE A REFRESHED LIGHTING ARRAY FOR THE PARKADE.

SITE INFORMATION:

LOT AREA	131,261 SF
ZONE	CENTRAL BUSINESS DISTRICT
USES	PARKING
LOT WIDTH	348'-8"
LOT DEPTH	331'-8"

SP DRAWING INDEX

Sheet Number	Sheet Name
GENERAL	
SP-00	COVER SHEET
CIVIL	
C0.0	COVER SHEET, VICINITY & LOCATION MAPS, DRAWING INDEX
C0.1	TOPOGRAPHIC SURVEY
C1.0	EXISTING CONDITIONS & EROSION CONTROL PLAN
C1.1	POST-DEVELOPED EROSION CONTROL PLAN
C1.2	EPSC (EROSION CONTROL & SEDIMENT PROTECTION) NOTES
C1.3	EPSC NOTES
C1.4	EPSC DETAILS
C2.0	GRADING PLAN
C3.0	SURFACING PLAN
C5.0	CIVIL NOTES
ARCHITECTURAL	
SP-01	FIRST FLOOR AND SITE PLAN
SP-02	SECOND FLOOR PLAN
SP-03	THIRD FLOOR AND ROOF PLAN
SP-04	NORTH EXTERIOR ELEVATION
SP-05	EAST EXTERIOR ELEVATION
SP-06	SOUTH EXTERIOR ELEVATION
SP-07	WEST EXTERIOR ELEVATION
SP-08	ENLARGED ELEVATIONS
SP-09	ELEVATION DETAILS
SP-10	RENDERINGS

ZONING/LOCATION MAP



PROJECT/LOCATION:

MARION PARKADE  
445 MARION ST NE, SALEM OR 97301

TITLE: COVER SHEET

SP-00

DATE: 10/09/24



DRAWINGS FOR:

MARION PARKADE IMPROVEMENTS  
538 LIBERTY ST NE,  
SALEM, OR 97303


FOR:

CB TWO ARCHITECTS  
500 LIBERTY ST. SE SUITE 100  
SALEM, OR 97301

DRAWING INDEX


DWG	TITLE
C0.0	COVER SHEET, VICINITY & LOCATION MAPS, DRAWING INDEX
C0.1	TOPOGRAPHIC SURVEY
C1.0	EXISTING CONDITIONS & EROSION CONTROL PLAN
C1.1	POST-DEVELOPED EROSION CONTROL PLAN
C1.2	EPSC (EROSION CONTROL & SEDIMENT PROTECTION) NOTES
C1.3	EPSC NOTES
C1.4	EPSC DETAILS
C2.0	GRADING PLAN
C3.0	SURFACING PLAN
C4.0	CONSTRUCTION NOTES
C5.0	CIVIL DETAILS

PROJECT  
LOCATION



VICINITY MAP

PROJECT  
LOCATION



LOCATION MAP



Know what's below.  
Call before you dig.

BENCHMARK UTILIZED:  
C.O.S. #1021  
ELEV: 150.93' NGVD 29

MARK IS A 3" BRASS DISK IN CONCRETE SIDEWALK AT THE  
NORTHWEST CORNER OF THE INTERSECTION OF  
MARION ST. NE AND COMMERCIAL ST. NE.

ABBREVIATIONS			
ASPH	ASPHALT	IRR	IRRIGATION
AD	AREA DRAIN	IE	INVERT ELEVATION
ASSY	ASSEMBLY	JB	JUNCTION BOX
BLDG, BLD	BUILDING	LP	LIGHT POLE
BW	BOTTOM OF WALL	M	METER, MAIN
CATV	CABLE TELEVISION	MB	MAILBOX
CB	CATCH BASIN	MH	MANHOLE
CO	CLEAN-OUT	OH	OVER-HEAD
CONC	CONCRETE	P/L, R	PROPERTY LINE
CL	CENTERLINE	PVC	POLYVINYL CHLORIDE
DIP	DUCTILE IRON PIPE	PWR	POWER
EG	EDGE OF GRAVEL	R, RAD	RADIUS
EOP, EP	EDGE OF PAVEMENT	ROW, R/W	RIGHT-OF-WAY
ELEV	ELEVATION	SS	SANITARY SEWER
EX, EXIST.	EXISTING	SD	STORM DRAIN
FDC	FIRE DEPT. CONNECTOR	SVC	SERVICE
FT	FEET	SWK, S/W	SIDEWALK
FF	FINISH FLOOR	TC	TOP OF CURB
FG	FINISH GRADE	TEL	TELEPHONE
FH	FIRE HYDRANT	TR	TRANSFORMER
FI	FIELD INLET	TS	TRAFFIC SIGNAL
FM	FORCE MAIN	TW	TOP OF WALL
GM	GAS METER	TYP	TYPICAL
GP	GATE POST	UG, U/G	UNDER GROUND
GS	GROUND SHOT	UTIL	UTILITY
GV	GAS VALVE	VLT	VAULT
HC	HANDICAP	W/W	WITH
HDPE	HIGH-DENSITY POLYETHYLENE	WM	WATER METER
HYD	HYDRANT	WLM	WETLANDS MARKER
IR	IRON ROD	YPC	YELLOW PLASTIC CAP
IP	IRON PIPE		

SYMBOLS			
AD	AREA DRAIN	/	SIGN POST
CB or	CATCH BASIN	PEDO	PEDESTAL
COO	CLEANOUT	MB	MAIL BOX
FX	FIRE HYDRANT	IV	IRRIGATION VALVE
GV	GAS VALVE	☆	LIGHT POLE
WV	WATER VALVE	TP	UTILITY/POWER POLES
GPW	GAS/POWER/WATER METER	TP	TEST PIT
DSO	DOWN SPOUT	●	MONUMENT FOUND
①	MANHOLE TELEPHONE		
②	MANHOLE STORM DRAIN		
③	MANHOLE SANITARY SEWER		
④	TREES - *TREENAME* DIAMETER (INCHES)/DRIP RADIUS (FEET)		
	NOTE: DIAMETER MEASURED AT BREAST HEIGHT		

LINE TYPES	
CATV LINE	— CATV — CATV — CATV — CATV — CATV — CATV — CATV — CATV —
COMMUNICATION LINE	— COM — COM — COM — COM — COM — COM — COM — COM —
EASEMENT LINE	— EAS — EAS — EAS — EAS — EAS — EAS — EAS — EAS —
FENCE LINE	— FEN — FEN — FEN — FEN — FEN — FEN — FEN — FEN —
FIBER OPTIC LINE	— FOC — FOC — FOC — FOC — FOC — FOC — FOC — FOC —
GAS LINE	— GAS — GAS — GAS — GAS — GAS — GAS — GAS — GAS —
EDGE OF GRAVEL LINE	— OH — OH — OH — OH — OH — OH — OH — OH —
OVERHEAD LINE	— OH — OH — OH — OH — OH — OH — OH — OH —
PHONE LINE	— PH — PH — PH — PH — PH — PH — PH — PH —
POWER LINE	— ELEC — ELEC — ELEC — ELEC — ELEC — ELEC — ELEC — ELEC —
SANITARY SEWER LINE	— SS — SS — SS — SS — SS — SS — SS — SS —
STORM DRAIN LINE	— SD — SD — SD — SD — SD — SD — SD — SD —
WATER LINE	— W — W — W — W — W — W — W — W —

C B T W O  
A R C H I  
T E C T S LLC

www.cbtwoarch.com



NOT FOR CONSTRUCTION  
WE JOB #3536.0000.0

WE  
WESTTECH ENGINEERING, INC.  
CONSULTING ENGINEERS AND PLANNERS  
3841 Fairview Industrial Dr. S.E., Suite 100, Salem, OR 97302  
Phone: (503) 585-2474 Fax: (503) 585-3886  
E-mail: westtech@westtech-eng.com



MARION PARKADE  
538 LIBERTY ST NE, SALEM, OR 97303


Issue:	75% CD'S	
Date:	10/1/2024	
Rev:	Description:	Date:

COVER SHEET,  
VICINITY &  
LOCATION  
MAPS, DRAWING  
INDEX

C0.0



TOPOGRAPHIC SURVEY



ABBREVIATIONS	
ASPH	ASPHALT
AD	AREA DRAIN
ASSY	ASSEMBLY
BLDG, BLD	BUILDING
BW	BOTTOM OF WALL
CATV	CABLE TELEVISION
CB	CATCH BASIN
CO	CLEAN-OUT
CONC	CONCRETE
CL	CENTERLINE
DIP	DUCTILE IRON PIPE
EG	EDGE OF GRAVEL
EOP, EP	EDGE OF PAVEMENT
ELEV	ELEVATION
EX, EXIST	EXISTING
FDC	FIRE DEPT. CONNECTOR
FT	FEET
FF	FINISH FLOOR
FG	FINISH GRADE
FH	FIRE HYDRANT
FI	FIELD INLET
FM	FORCE MAIN
GRAV	GRAVEL
GM	GAS METER
GP	GATE POST
GS	GROUND SHOT
GV	GAS VALVE
HC	HANDICAP
HDPE	HIGH-DENSITY POLYETHYLENE
HYD	HYDRANT
IR	IRON ROD
IP	IRON PIPE
IRR	IRRIGATION
IE	INVERT ELEVATION
JB	JUNCTION BOX
LP	LIGHT POLE
M	METER, MAIN
MB	MAILBOX
MH	MANHOLE
OH	OVER-HEAD
P/L	PROPERTY LINE
PP	POWER POLE
PVC	POLYVINYL CHLORIDE
PWR	POWER
R, RAD	RADIUS
ROW, R/W	RIGHT-OF-WAY
SS	SANITARY SEWER
SD	STORM DRAIN
SVC	SERVICE
SWK, S/W	SIDEWALK
TC	TOP OF CURB
TEL	TELEPHONE
TR	TRANSFORMER
TS	TRAFFIC SIGNAL
TW	TOP OF WALL
TYP	TYPICAL
UG, U/G	UNDER GROUND
UTIL	UTILITY
VALT	VAULT
W	WITH
WM	WATER METER
WLM	WETLANDS MARKER
YPC	YELLOW PLASTIC CAP

SYMBOLS	
AD	AREA DRAIN
CB or	CATCH BASIN
CO	CLEANOUT
FH	FIRE HYDRANT
GV	GAS VALVE
W	WATER VALVE
GPW	GAS/POWER/WATER METER
DSO	DOWN SPOUT
MH	MANHOLE TELEPHONE
MSD	MANHOLE STORM DRAIN
MSW	MANHOLE SANITARY SEWER
TS	TRAFFIC SIGNAL
VALT	VAULT
W	WITH
WM	WATER METER
WLM	WETLANDS MARKER
YPC	YELLOW PLASTIC CAP
TS	TRAFFIC SIGNAL
VALT	VAULT
W	WITH
WM	WATER METER
WLM	WETLANDS MARKER
YPC	YELLOW PLASTIC CAP

LINE TYPES	
CATV LINE	CATV
COMMUNICATION LINE	COM
EASEMENT LINE	EASEMENT
FENCE LINE	FENCE
FIBER OPTIC LINE	FIBER OPTIC
GAS LINE	GAS
EDGE OF GRAVEL LINE	EG
OVERHEAD LINE	OH
PHONE LINE	PH
POWER LINE	ELEC
SANITARY SEWER LINE	SS
STORM DRAIN LINE	SD
WATER LINE	W

BENCHMARK UTILIZED:  
C.O.S. #1021  
ELEV: 150.93' NGVD 29

MARK IS A 3" BRASS DISK IN CONCRETE SIDEWALK AT THE NORTHWEST CORNER OF THE INTERSECTION OF MARION ST. NE AND COMMERCIAL ST. NE.

DISCLAIMER: UTILITIES DEPICTED ARE BASED ON EVIDENCE FOUND IN THE FIELD, MUNICIPALITY AND/OR OTHER GOVERNMENT ENTITY AS-BUILT PLANS, CONTRACTOR PLANS AND OTHER DOCUMENTS OF RECORD. BARKER SURVEYING ASSUMES NO RESPONSIBILITY FOR UTILITIES THAT ARE NO LONGER IN USE, INSTALLED AFTER THE DATE OF ACTUAL SURVEY, NOT IDENTIFIED OR NOT LOCATED. THIS INCLUDES UTILITIES UPON PUBLIC OR PRIVATE PROPERTY.

SPECIFIC UTILITY POSITIONS INDICATED ON THE GROUND SURFACE PROVIDED BY LOCATION SERVICES MAY VARY DUE TO UNDERGROUND DETECTION CAPABILITIES.






REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*Gregory L. Wilson*  
O R E G O N  
JULY 19, 1994  
GREGORY L. WILSON  
2087  
EXPIRES: 6/30/2026

SURVEY FOR	CB TWO ARCHITECTS
LOCATION:	MARION PARKADE -- 538 LIBERTY ST NE
SE 1/4 SECTION 22 T7S, R3W, W.M.	CITY OF SALEM MARION COUNTY, OREGON
SCALE: 1"=20'	BARKER SURVEYING 3657 KASHMIR WAY SE SALEM, OREGON 97317 PHONE (503) 588-8800 FAX (503) 363-2469 EMAIL: GREG@BARKERWILSON.COM
DATE: 08/19/2024	SHEET 1 OF 1
DRAWN BY: S.C.P.	JOB NUMBER: 42700



10/9/2024 9:09:20 AM  
R:\Dwg\CB2 ARCHITECT\Marion County Parade\Civil\Pos\PD-EPC Demo Plan.dwg (C1.0 tab)



EROSION CONTROL LEGEND

SILT SACK.

BIO BAGS.

SILT FENCE.

DEMOLITION LEGEND

SAWCUT.


CONTRACTOR TO REMOVE.

CONTRACTOR TO PROTECT

Issue:		75% CD'S
Date:		10/1/2024
Rev:	Description:	Date:

EXISTING  
CONDITION &  
EROSION  
CONTROL PLAN











10/9/2024 9:09:35 AM  
R:\Dwg\CB2 ARCHITECT\Marion County Parkade\Civil\Pos\PD-EPSC Notes & Dtl.dwg, (C 13 tab)

CITY OF SALEM PUBLIC WORKS DESIGN STANDARDS:

Division 007 Appendix A–EPSC Plan Standard Notes

(a) PRE–CONSTRUCTION

(1). Prior to any land disturbing activities, the boundaries of the clearing and grading limits, vegetated buffers, and any sensitive areas shown on this plan shall be clearly delineated in the field. Unless otherwise approved, no disturbance is permitted beyond the clearing limits. The Contractor must maintain the delineation for the duration of the project. Note: vegetated corridors to be delineated with orange construction fence or approved equal.

(2). BMPs that must be installed prior to land disturbing activities are construction entrance, perimeter sediment control, and inlet protection.

(3). Hold a preconstruction conference to review the EPSCP and with the City's Project Manager and Inspector.

(b) CONSTRUCTION

(1). All sediment is required to stay on site. Sediment amounts greater than 1/2–cubic foot which leave the site must be cleaned up within 24 hours and placed back on the site and stabilized or properly disposed. Vacuuming or dry sweeping must be used to clean up released sediment and it must not be swept or washed into storm sewers, drainage ways, or water bodies. The cause of the sediment release must be found and prevented from causing a recurrence of the discharge within thesame 24 hours. Any in–stream clean up of sediment shall be performed according to the DSL required time frame.

(2). Construction, maintenance, replacement, and upgrading of erosion prevention and sediment control facilities is the sole responsibility of the Contractor until all construction is completed, approved, and permanent erosion control (i.e., vegetation/landscaping) is established on all disturbed areas.

(3). All recommended erosion prevention and sediment control procedures are dependent on construction methods, staging, site conditions, weather, and scheduling. During the construction period, erosion control facilities shall be revised, upgraded, replaced, or added, to comply with SRC and State and Federal regulatory requirements.

(4). The Contractor is solely responsible for protection of all adjacent property and downstream facilities from erosion and siltation during project construction. Any damage resulting from such erosion and siltation shall be corrected at the sole expense of the Contractor.

(5). When saturated soil is present, water–tight trucks must be used to transport saturated soils from the construction site. Soil may be drained on site at a designated location, using appropriate BMPs. Soil must be drained sufficiently to drip less than one gallon per hour prior to leaving the site.

(6). All materials spilled, dropped, or washed into storm drains must be removed immediately, and the Contractor shall provide protection of downstream inlets and catch basins to ensure sediment–laden water does not enter the storm drain system.

(7). All discharge of sediment–laden water must be treated with an appropriate BMP to remove sediment from discharge waters and to comply with SRC and State and Federal Regulatory Permits.

(8). In areas subject to wind erosion, appropriate BMPs must be used which may include the application of fine water spraying, plastic sheeting, mulching, or other approved measures.

(9). The EPSC measures and BMPs shown on this plan are the minimum requirements for anticipated site conditions. During the construction period, these measures shall be upgraded as needed to maintain compliance with all regulations.

(10). The contractor shall provide onsite water or other appropriate BMPs to prevent dust and wind erosion of fine grain soils.

(11). Disturbed areas must be stabilized after 14 days of inactivity, or immediately if rain is forecasted. See Subsection 7A.1(d)–Wet Weather Period.

(12). During the wet weather work period or when rain is forecasted, all active and inactive soil stock piles must be covered with appropriate plastic sheeting. Plastic sheeting must cover the entire stock pile and be sufficiently anchored.

(c) POLLUTANTS, SOLID WASTE AND HAZARDOUS MATERIALS MANAGEMENT

(1). Any use of toxic or other hazardous materials must include proper storage, application, and disposal.

(2). The contractor is solely responsible to properly manage pollutants, hazardous wastes, used oils, contaminated soils, concrete waste, sanitary waste, liquid waste, or other toxic substances discovered or generated during construction to prevent leakage, spills or release of pollutants to the environment and surface waters.

(3). Contractor shall develop a project specific written spill prevention and response procedures that includes employee training on spill prevention and proper disposal procedures; regular maintenance schedule for vehicles and machinery, and material delivery and storage controls, signage, material use, and use of covered storage areas for waste and supplies. The plan shall comply with SRC and Federal and State requirements, and shall be available on site at all times.

(d) WET WEATHER PERIOD (OCTOBER 15 THROUGH APRIL 30)

(1). Construction activities must avoid or minimize the duration of disturbed areas.

(2). Temporary stabilization of the site including covering of bare soils with approved BMPs, must be installed at the end of the shift before a holiday or weekend, or at the end of each workday if rainfall is forecast in the next 24 hours.

(3). Temporary stabilization or covering of soil stockpiles and protection of stockpiles located away from construction activity must occur at the end of each workday.

(e) MAINTENANCE

(1). Erosion control measures shall be maintained in such a manner as to ensure that erosion is prevented and sediment–laden water does not enter a drainage system, roadway, or violate applicable water quality standards.

(2). Sediment shall not be washed or swept into storm sewers, drainage ways, or water bodies.

(3). Sediment must be removed from behind all sediment control measures when it has reached a height of 1/3 the barrier height, and prior to the control measures removal.

(4). Removal of trapped sediment in a sediment basin or sediment trap or catch basins must occur when the sediment retention capacity has been reduced by 50 percent; is not functioning properly and/or at the completion of project.

(5). Cleaning of all structures, inlet protection BMPs, and sump pumps must be completed regularly and as required to ensure structures and inlets function properly and flow freely.

(6). Construction site exits shall be maintained in a condition that will prevent tracking or flow of mud onto the ROW or approved access point. The entrance may require periodic top dressing as conditions demand, and repair and/or cleanout of any structures used to trap sediment. Wheel washing shall be required to prevent sediment and material tracking on road surfaces if passive BMPs are not effective.

(f) INSPECTION

(1). The EPSCP must be kept onsite at all times. All measures shown on the plan must be installed properly to ensure compliance with SRC and State and Regulatory permits, and that sediment does not enter a surface water system, roadway, or other properties.

(2). Written EPSC inspection logs shall be maintained onsite and available to City inspectors upon request.

(3). All BMPs shall be inspected at least every week. When a rainfall event exceeds 1/2–inch in a 24–hour period, daily inspection of the erosion controls, sediment controls, and discharge outfalls must be conducted and documented. Inspections shall be done by a representative of the permit registrant who is knowledgeable and experienced in the principles, practices, installation, and maintenance of erosion and sediment controls.

(g) INACTIVE CONSTRUCTION PERIODS AND POST–CONSTRUCTION

(1). Should work cease in any area for 14 days, the inactive area must be stabilized with appropriate soil stabilization BMPs. If all construction activity ceases the entire site must be temporarily stabilized using vegetation, heavy mulch layer, temporary seeding, or other method.

(2). All temporary erosion prevention and sediment control facilities shall be removed by the contractor within 30 days after permanent landscaping/vegetation is established and the threat of erosion and sediment transport has been mitigated.

(3). Temporary grass cover measures must be fully established by October 15 or other cover measures (i.e., erosion control blankets with anchors, one–inch of straw mulch, six mil HDPE plastic sheet, etc.) shall be in place over all disturbed soil areas until April 30. To establish an adequate grass stand for controlling erosion by October 15, it is recommended that seeding and mulching occur by September 1.

(4). Permanent erosion control vegetation on all embankments and disturbed areas shall be re–established as soon as construction is completed.

(h) SPECIFICATIONS

(1). Soil preparation. Topsoil should be prepared according to the landscape plans, if available, or recommendations of the grass seed supplier. Slopes shall be textured before seeding by rack walking (i.e., driving a crawling tractor up and down the slopes to leave a pattern of cleat imprints parallel to slope contours) or other method to provide stable areas for seeds to rest.

(2). Seeding. Erosion control grass seed mix shall be as follows: Dwarf grass mix (low height, low maintenance) consisting of dwarf perennial ryegrass (80 percent by weight), creeping red fescue (20 percent by weight). Application rate shall be 100 pounds per acre minimum.

(3). Grass seed shall be fertilized at a rate of ten pounds per 1,000 square feet with 16–16–16 slow release type fertilizer. Disturbed areas within 50 feet of water bodies and wetlands must use a non–phosphorous fertilizer.

(4). The application rate of fertilizers used to reestablish vegetation shall follow manufacturer's recommendations. Nutrient releases from fertilizers to surface waters shall be minimized. Time release fertilizers shall be used. Care shall be made in the application of fertilizers within any waterway riparian zone to prevent leaching into the waterway.

(5). When used, hydromulch shall be applied with grass seed at a rate of 2,000 pounds per acre between April 30 and June 10, or between September 1 and October 1. On slopes steeper than ten percent, hydroseed and mulch shall be applied with a bonding agent (tackifier). Application rate and methodology shall be in accordance with seed supplier recommendations.

(6). When used in lieu of hydromulch, dry, loose, weed–free straw used as mulch shall be applied at a rate of 4,000 pounds per acre (double the hydromulch application requirement). Anchor straw by working in by hand or with equipment (rollers, cleat trackers, etc.). Mulch shall be spread uniformly immediately following seeding.

(7). When conditions are not favorable to germination and establishment of the grass seed, the Contractor shall irrigate the seeded and mulched areas as required to establish the grass cover.

(8). Sediment fences shall be constructed of continuous filter fabric to avoid use of joints. When joints are necessary, filter cloth shall be spliced together only at a support post, with a minimum six–inch overlap, and both ends securely fastened to a post.


(9). The standard strength filter fabric shall be fastened securely to stitched loops installed on the upslope side of the posts, and six inches of the fabric shall be extended into the trench. The fabric shall not extend more than 30 inches above the original ground surface. Filter fabric shall not be stapled to existing trees.

(10). Bio–filter bags shall be clean 100 percent wood product waste. Bags shall be 18–inch x 18–inch x 30–inch, weigh approximately 45 pounds, and be contained in a bag made of 1/2–inch plastic mesh.

(11). Minimum wet weather slope protection. For 3H:1V or steeper slopes use Bon Terra Type C2 or North American Green Type C125 erosion control blankets. Use a minimum of two inches straw mulch or North American Green Type S150 for slopes flatter than 3H:1V and greater than 6H:1V. Slopes flatter than 6H:1V use one inch straw mulch, hydroseed with hydromulch and tackifier. Slope protection shall be placed on all disturbed areas immediately after completion of each section of construction activity, until the erosion control seeding has been established. As an option during temporary or seasonal work stoppages, a six–mil HDPE plastic sheet may be placed on exposed slopes. The plastic sheet shall be provided with an anchor trench at the top and bottom of the slope, and shall be sandbagged on the slopes as required to prevent damage or displacement by wind.

C B T W O  
A R C H I  
T E C T S LLC

www.cbtwoarch.com



RENEWED: 6/30/2026  
NOT FOR CONSTRUCTION  
WE JOB #3536.0000.0

**WE** WESTTECH ENGINEERING, INC.  
CONSULTING ENGINEERS AND PLANNERS  
3841 Fairview Industrial Dr. S.E., Suite 100, Salem, OR 97302  
Phone: (503) 585–2474 Fax: (503) 585–3886  
E-mail: westech@westtech-eng.com






MARION PARKADE  
538 LIBERTY ST NE, SALEM, OR 97303

Issue:	75% CD'S	
Date:	10/1/2024	
Rev:	Description:	Date:

EPSC NOTES

C1.3






Issue:	75% CD'S
Date:	10/1/2024
Rev:	Description: Date:





RENEWALS: 6/30/2026  
T FOR CONSTRUCTION  
JOB #3536.0000.0




MARION PARKADE

[illegible][illegible]

## GRADING PLAN

## C2.0







RENEWS: 6/30/2026

T FOR CONSTRUCTIC

JOB #3536.0000.



Y OF Salem

MARION PARKADE

---


538 LIBERTY ST NE, SALEM, OR 97303

[illegible]

	75% C
	10/1/20
Description:	Date


## SURFACING PLANS

## C3.0



### SURFACING LEGEND

4" THICK PCC (4000 PSI)  
OVER 2" OF COMPACTED  
1"-0 OVER APPROVED  
SUBGRADE.




U N I O N   S T .   N . E .


LIBERTY ST. N.E.


HIGH ST. N.E.

M A R I O N   S T .   N . E .






KEYNOTES		GENERAL NOTES	
①	SLOPE 1.5% TYPICAL (2.0% MAXIMUM)	<ul style="list-style-type: none"> <li>SIDEWALK WIDTH SHALL BE 5' UNLESS OTHERWISE SHOWN ON PLANS.</li> <li>FINISH SIDEWALK WITH LIGHT TRAVERSE BROOMING. ALL EDGES SHALL BE TOOL ROUNDED AND SHINED (3") AFTER BROOMING.</li> <li>SET SIDEWALK 1FT FROM PROPERTY LINE UNLESS OTHERWISE SHOWN ON PLANS.</li> </ul>	
②	4" MIN. THICK P.C.C. COMMERCIAL GRADE CONCRETE.		
③	2" MIN. COMPACTED CRUSHED AGGREGATE.		
④	CONSTRUCT CONTRACTION JOINTS AT 15' FT MAX SPACING.		
ALL NEW DRAWING CHANGES _____ _____ _____		<b>CITY OF SALEM</b> <b>DEPARTMENT OF PUBLIC WORKS</b>  STANDARD PLAN <b>PROPERTY LINE SIDEWALK</b>	
APPROVED	 CITY ENGINEER	12/27/19	DRAWN BY JAK 10/2019 CHECKED BY DEW 10/2019
		<b>NO. 306B</b>	



NOT FOR CONSTRUCTION  
WE JOB #3536.0000.0



MARION PARKADE  
538 LIBERTY ST NE, SALEM, OR 97303

[illegible]

CIVIL DETAILS

C5.0




SITE COVERAGE:


TYPE	AREA	%
EXISTING BUILDING	124,862 SF	95 %
RENOVATED STAIR TOWER	2,956 SF	2 %
EXISTING HARDSCAPE	3,434 SF	3 %
TOTAL SITE AREA	131,261 SF	100 %
NO MAXIMUM LOT COVERAGE PER CENTRAL BUSINESS DISTRICT		

FIRST FLOOR AREA:

TYPE	AREA	%
PARKING	124,862 SF	95%
VERTICAL CIRCULATION STAIRS, ELEVATORS, SHAFTS, ETC	2,956 SF	3%
TOTAL SITE AREA	131,261 SF	
NO MAXIMUM LOT COVERAGE PER CENTRAL BUSINESS DISTRICT		




2 R.O.W. ENCROACHMENT PLAN  
SCALE: 1/16" = 1'-0"




1 SITE AND FIRST FLOOR PLAN  
SCALE: 1" = 50'-0"





FINS AND PERFORATED SCREENS




SECOND FLOOR PLAN

SCALE: 1" = 50'-0"








PARKING CANOPY  
DECORATIVE FINS  
DIAGONAL SHADES

ROOF DECK CANOPY




THIRD FLOOR AND ROOF PLAN

SCALE: 1" = 50'-0"








## 1 NORTH ELEVATION - EXISTING

SCALE: 1" = 30'-0"



## 2 NORTH ELEVATION - PROPOSED

SCALE: 1" = 30'-0"



A  
MATERIAL:  
CONCRETE

COLOR:  
MATCH EXISTING



B  
MATERIAL:  
EXISTING BRICK

COLOR:  
MATCH EXISTING




C  
MATERIAL:  
METAL ELEMENTS

COLOR:  
SW "7069" IRON  
ORE



D  
MATERIAL:  
PAINT EXISTING  
BRICK


COLOR:  
SW "7666"  
FLEUR DE SEL




E  
MATERIAL:  
DECORATIVE  
FINS & SCREENS

COLOR:  
SW "7066" GRAY  
MATTERS





1 EAST ELEVATION - EXISTING  
SCALE: 1" = 30'-0"



2 EAST ELEVATION - PROPOSED  
SCALE: 1" = 30'-0"




A  
MATERIAL:  
CONCRETE  
  
COLOR:  
MATCH EXISTING




B  
MATERIAL:  
EXISTING BRICK  
  
COLOR:  
MATCH EXISTING



C  
MATERIAL:  
METAL ELEMENTS  
  
COLOR:  
SW "7069" IRON  
ORE




D  
MATERIAL:  
PAINT EXISTING  
BRICK  
  
COLOR:  
SW "7666"  
FLEUR DE SEL




E  
MATERIAL:  
DECORATIVE  
FINS & SCREENS  
  
COLOR:  
SW "7066" GRAY  
MATTERS





1 SOUTH ELEVATION - EXISTING  
SCALE: 1" = 30'-0"



2 SOUTH ELEVATION - PROPOSED  
SCALE: 1" = 30'-0"




A  
MATERIAL:  
CONCRETE  
  
COLOR:  
MATCH EXISTING




B  
MATERIAL:  
EXISTING BRICK  
  
COLOR:  
MATCH EXISTING



C  
MATERIAL:  
METAL ELEMENTS  
  
COLOR:  
SW "7069" IRON  
ORE




D  
MATERIAL:  
PAINT EXISTING  
BRICK  
  
COLOR:  
SW "7666"  
FLEUR DE SEL




E  
MATERIAL:  
DECORATIVE  
FINS & SCREENS  
  
COLOR:  
SW "7066" GRAY  
MATTERS





1 WEST ELEVATION - EXISTING  
SCALE: 1" = 30'-0"



2 WEST ELEVATION - PROPOSED  
SCALE: 1" = 30'-0"




A  
MATERIAL:  
CONCRETE  
  
COLOR:  
MATCH EXISTING




B  
MATERIAL:  
EXISTING BRICK  
  
COLOR:  
MATCH EXISTING



C  
MATERIAL:  
METAL ELEMENTS  
  
COLOR:  
SW "7069" IRON  
ORE




D  
MATERIAL:  
PAINT EXISTING  
BRICK  
  
COLOR:  
SW "7666"  
FLEUR DE SEL




E  
MATERIAL:  
DECORATIVE  
FINS & SCREENS  
  
COLOR:  
SW "7066" GRAY  
MATTERS






3 SECTION  
SCALE: 1/8" = 1'-0"




2 ELEVATION - STRUCTURAL BAY  
SCALE: 1/8" = 1'-0"








1 ELEVATION - STAIR  
SCALE: 1/8" = 1'-0"






SE CORNER - EAST ELEVATION

SCALE: 1/8" = 1'-0"

-  MATERIAL:  
CONCRETE  
COLOR:  
TBD
-  MATERIAL:  
PAINT EXISTING BRICK  
COLOR:  
SW "7666" FLEUR DE SEL
-  MATERIAL:  
EXISTING BRICK  
COLOR:  
TBD
-  MATERIAL:  
DECORATIVE FINS & SCREENS  
COLOR:  
SW "7066" GRAY MATTERS
-  MATERIAL:  
METAL ELEMENTS  
COLOR:  
SW "7069" IRON ORE



SE CORNER - SOUTH ELEVATION

SCALE: 1/8" = 1'-0"





MARION ST FACADE AT NIGHT



SOUTHWEST STAIR TOWER AT MARION AND LIBERTY