PROPOSED TREE LEGEND

- HEDGE MAPLE (ACER CAMPESTRE 'METRO GOLD')
- RISING FIRE AMERICAN HORNGEAM (CARPINUS CAROLINIANA 'RISING FIRE')
- CORNELIANCHERRY DOGWOOD (CORNUS MAS 'SAFFRON SENTINEL')

ALL TREES TO BE 6' STANDARD, 1-1/2" TO 2" CALIPER

CONTRACTOR SHALL COMPLY WITH CITY STREET DESIGN STANDARDS (SECTION 6.29 & TABLE 6-31) FOR SEPARATION BETWEEN UTILITIES/INFRASTRUCTURE AND STREET TREES

UTILITY/INFRASTRUCTURE	DISTANCE (FT)
CURB, SIDEWALK	2
ACCESS WALKWAYS, FIRE HYDRANTS, ROOF DRAINS IN THE CURB, CATCH BASINS, MANHOLES, WATER METERS, WATER SERIVCES, GAS & ELECTRIC SERVICES, UTILITY BOXES & VAULTS, MOUNTED PEDESTAL, STORMWATER PLANTERS	6
ALLEYS, DRIVEWAYS, TRAFFIC SIGNS & SIGNALS (ON APPROACH), STREET LIGHT ON UTILITY POLE, AND WATER, WASTEWATER & STORMWATER LINES (1)	10
(1) THIS REQUIREMENT ONLY APPLIES WHERE THESE UTILITIES ARE PERPENDICULAR TO THE PLANTING STRIP	
TABLE 6-31. MINIMUM HORIZONTAL DISTANCES FROM NEW OR EXISTING UTILITIES OR INFRASTRUCTURE	

EXISTING TREE LEGEND

- = EXISTING TREE WHICH MAY BE REMOVED
- = EXISTING TREE TO REMAIN
- = EXISTING OAK TREE 24"+ TO REMAIN*
- = EXISTING OAK TREE 24"+ WHICH MAY BE REMOVED

* PRIOR TO ANY CONSTRUCTION WITHIN THE CRITICAL ROOT ZONE, CONTRACTOR TO SECURE STREET TREE PERMIT.

TREES SHOWN TO BE REMOVED OR SAVED APPLY ONLY TO THOSE WITHIN THE No. 6 PROJECT AREA UNLESS OTHERWISE INDICATED.

EXISTING TREES WITHIN THE No. 6 PROJECT AREA

	REMAIN	REMOVE	TOTAL
WHITE OAK 24"+	1	0	1
OTHER TREES	0	0	0
TOTAL TREES IN THE No. 6 PROJECT AREA			1

[EXISTING TREES WITHIN OVERALL SITE]

	REMAIN	REMOVE	TOTAL
WHITE OAK 24"+	50	9	59
OTHER TREES	63	177	240
TOTAL TREES WITHIN SITE			299

MULTI/TECH
ENGINEERING SERVICES, INC.
1155 13th ST. S.E. SALEM, OR. 97302
PH. (503) 363-9227 FAX (503) 364-1260
www.mtengineering.net office@mtengineering.net

TREE CONSERVATION & STREET TREE PLAN

EAST PARK ESTATES P.U.D. No. 6

NO CHANGES, MODIFICATIONS OR REPRODUCTIONS TO BE MADE TO THESE DRAWINGS WITHOUT WRITTEN AUTHORIZATION FROM THE DESIGN ENGINEER.

DIMENSIONS & NOTES TAKE PRECEDENCE OVER GRAPHICAL REPRESENTATION.

7369b 702-TREE

Design: M.D.G.
Drawn: D.G.G.
Checked: J.J.G.
Date: APR. 2023
Scale: AS SHOWN
As-Built: ---

REGISTERED PROFESSIONAL ENGINEER
OREGON
JAN. 19, 1978
MARK D. GRENZ

EXPIRES: 06-30-2025

JOB # 7369

702