

## ***Appendix 7***

### ***Draft Geotechnical Report***

---



# Improvements to the Aquifer Storage & Recovery Facility

## Geotechnical Engineering Report

**Report Status: Draft**  
**Revision No. 0**



June 2020

*This page intentionally left blank.*

## Table of Contents

<b>1.0</b>	<b>Introduction.....</b>	<b>1</b>
1.1	General .....	1
1.2	Project Description .....	1
1.3	Purpose and Scope of Work .....	2
<b>2.0</b>	<b>Geotechnical Exploration .....</b>	<b>3</b>
2.1	Exploratory Borings.....	3
2.2	Soil Classification & Sampling .....	3
2.3	Laboratory Testing .....	3
2.3.1	One-Dimensional Expansion, Shrinkage, and Uplift Pressure Tests .....	4
<b>3.0</b>	<b>Site Conditions .....</b>	<b>5</b>
3.1	Surface Conditions.....	5
3.2	Site Geology .....	5
3.3	Subsurface Conditions.....	6
3.3.1	Residual Soil of Columbia River Basalt Group .....	6
3.4	Groundwater .....	6
<b>4.0</b>	<b>Seismic and Geologic Hazard Evaluation.....</b>	<b>7</b>
4.1	Regional Seismicity.....	7
4.1.1	Crustal Sources.....	7
4.1.2	Cascadia Subduction Zone Seismic Sources .....	8
4.2	Site Classification.....	9
4.3	Seismic Design Parameters.....	9
4.4	Seismic Sources and Hazard Deaggregation.....	10
4.5	Liquefaction.....	10
4.6	Lateral Spreading.....	11
4.7	Fault Rupture .....	11
4.8	Slope Stability .....	12
4.9	Flood Hazard .....	12
4.10	Other Hazards.....	12
<b>5.0</b>	<b>Conclusions and Key Geotechnical Considerations.....</b>	<b>13</b>
5.1	Shrink-Swell Potential of Subgrade Soils .....	13
5.2	Construction Disturbance on Moisture-Sensitive Soils .....	14

<b>6.0</b>	<b>Design Recommendations .....</b>	<b>14</b>
6.1	Water Treatment Facility, ASR Well Houses, & Below-Grade Structures.....	14
6.1.1	Subgrade Preparation .....	15
6.1.2	Minimum Footing Width and Embedment.....	15
6.1.3	Footing Bearing Pressure & Settlement.....	15
6.1.4	Interior Floor Slabs.....	16
6.1.5	Lateral Earth Pressures .....	16
6.1.6	Lateral Resistance .....	17
6.1.7	Buoyancy .....	17
6.1.8	Drainage Considerations .....	18
6.2	Pipelines.....	18
6.2.1	Pipeline Subgrade Support .....	18
6.2.2	Soil Design Parameters .....	19
6.2.3	Pipeline Buoyancy and Flotation.....	19
6.3	Infiltration Facilities .....	19
<b>7.0</b>	<b>Construction Recommendations.....</b>	<b>20</b>
7.1	Site Preparation .....	20
7.1.1	Demolition .....	20
7.1.2	Site Stripping.....	20
7.1.3	Existing Utilities & Below-Grade Structures.....	20
7.1.4	Erosion Control .....	21
7.1.5	Subgrade Preparation .....	21
7.2	Pipeline Trench Excavation .....	21
7.3	Fill Materials and Compaction Criteria.....	21
7.3.1	On-Site Materials .....	21
7.3.2	Structural Fill .....	22
7.3.3	Embedded Walls and Below-Grade Structure Backfill.....	22
7.3.4	Pipe Bedding and Pipe Zone Backfill.....	22
7.3.5	CLSM Backfill.....	23
7.3.6	Foundation Stabilization.....	23
7.3.7	Geotextiles .....	23
7.3.8	Trench Backfill.....	23
7.4	Temporary Excavations .....	24
7.5	Groundwater Control.....	24
7.6	Wet Weather Earthwork.....	25

<b>8.0</b>	<b>Closure .....</b>	<b>26</b>
<b>9.0</b>	<b>References .....</b>	<b>27</b>

## List of Tables

Table 2-1: Results Summary of Shrink-Swell & Expansion Pressure (ASTM D3877) Tests .....	4
Table 4-1. Known Faults Within 20 km of the Project Site.....	8
Table 4-2. 2019 OSSC MCE Spectral Acceleration Parameters for Site Class D.....	9
Table 4-3: Deaggregation Results for 2,475-year Mean Source Event (MCE), PGA Period .....	10
Table 6-1. Recommended Lateral Earth Pressures .....	17
Table 6-2. Pipeline Geotechnical Design Parameters .....	19

## List of Figures

Figure 1	Vicinity Map
Figure 2	Exploration Plan
Figure 3	Lateral Earth Pressures

## Appendices

Appendix A	Boring Logs
Appendix B	Laboratory Test Results

## Distribution

To: Lael Alderman, P.E.  
Murraysmith

From: Jeff Quinn, P.E.  
McMillen Jacobs Associates

Prepared By: Jeff Quinn, P.E.  
McMillen Jacobs Associates

Reviewed By: Wolfe Lang, P.E., G.E.  
McMillen Jacobs Associates

## Revision Log

Revision No.	Date	Revision Description
0	June 2, 2020	Draft submitted for Murraysmith review

## 1.0 Introduction

### 1.1 General

McMillen Jacobs Associates (McMillen Jacobs) has been retained by Murraysmith to provide geotechnical engineering services for the Improvements to the Aquifer Storage & Recovery Facility Project (Project). The Project is in Woodmansee Park in Salem, Oregon, and the City of Salem (City) is the project Owner. This Geotechnical Engineering Report (GER) summarizes the geotechnical analyses and recommendations for the Project. The Project location is shown on the attached Figure 1, Vicinity Map.

### 1.2 Project Description

The City stores drinking water for backup use at the Aquifer Storage and Recovery (ASR) facility located in Woodmansee Park in Salem, Oregon. The ASR facility receives water diverted from the North Santiam River (the City's primary water source) during the winter, treats the water to drinking water quality, and injects it into a confined aquifer at a depth of about 300 feet below ground, within an interflow zone of the Columbia River Basalt unit. The ASR facility currently consists of five ASR wells (four of which are operational) located in four existing well houses across Woodmansee Park, as well as appurtenant conveyance piping.

As part of the City's commitment to provide safe drinking water, several improvements are proposed for the ASR Facility. Our project understanding is based on our communications with, and drawings provided by, Murraysmith. The proposed improvements to the ASR Facility include the following:

- A new water treatment facility (WTF) located on the east side of the park, approximately 50 feet north of the existing ASR Well No. 4 pumphouse. The new 50-foot by 54-foot WTF will have a finished floor elevation of 379 feet. To facilitate the construction of the new WTF, cuts up to about 3 feet deep will likely be required. We anticipate the new WTF structure will be lightly loaded and founded on either a conventional perimeter footing with slab-on-grade foundation system or on a mat foundation.
- The new WTF will be situated in the middle of an approximately 180-foot by 110-foot area that will be regraded/flattened and paved with asphalt. In addition, the existing, 15-foot wide, City-owned easement and gravel access road from Sunnyside Road SE will be widened to 30 feet and paved with asphalt; providing access to the new WTF.
- Three new ASR wells (Nos. 8 through 10), each enclosed in an approximately 900 square-foot pumphouse. We anticipate the pumphouses will be lightly loaded and founded on mat foundations.
- We understand that a stormwater infiltration facility will be constructed within the northwest corner of the above-referenced paved area, to offset the increased stormwater volume of the impermeable area resulting from the WTF property development. The stormwater infiltration facility design will be completed by others.

- Approximately 3,050 feet piping is proposed as part of this Project. At this time, no information has been provided regarding the piping materials, sizes, or invert depths.

### **1.3 Purpose and Scope of Work**

The purpose of our work is to evaluate the subsurface conditions and to provide geotechnical engineering design and construction recommendations for subsequent use by the design team in support of the Project. Specifically, the scope of our work included the following:

- Subsurface investigation at the Project site including four drilled borings advanced to approximate depths of up to 50 feet below ground surface (bgs);
- Laboratory testing on soil samples obtained from the drilled borings, including moisture content, Atterberg Limits, particle size analysis, and shrink-swell / expansion pressure;
- Characterization of subsurface conditions at the proposed WTF, the ASR well locations, and new pipelines based on geotechnical explorations and laboratory testing;
- Geotechnical engineering assessments and design recommendations for structure and pipeline subgrade properties and settlement potential;
- Shallow foundation design recommendations for the proposed WTF and the pumphouses for the new ASR wells;
- Seismic hazard evaluation results and seismic geotechnical recommendations for the design of new structures;
- Bedding and backfill recommendations for the replacement pipeline and backfill compaction criteria;
- Recommendations for lateral earth pressures on embedded structures (e.g., manholes and vaults);
- Recommendations for structural fill, bedding, backfill, and compaction criteria for foundations, pipelines, and buried structures;
- Recommendations for subgrade stabilization, if required;
- Preparation of this Geotechnical Engineering Report.

## 2.0 Geotechnical Exploration

### 2.1 Exploratory Borings

The geotechnical exploration for the Project was completed on April 6 and 7, 2020, and included four exploratory borings (B-1 through B-4). Western States Soil Conservation, Inc. of Hubbard, Oregon, completed the borings using a track-mounted CME-55 drill rig. The borings were advanced to depths ranging from 20 feet to 50 feet bgs, using hollow-stem auger and mud-rotary drilling techniques.

The exportations were completed under the supervision of a McMillen Jacobs geologist who maintained continuous observation, collected soil, and maintained a full-depth descriptive log of the soil materials penetrated in each borehole.

### 2.2 Soil Classification & Sampling

The soil samples collected in the borings were classified in accordance with the Visual-Manual Procedure (ASTM D2488). Sample depths, stratigraphy, groundwater observations, and soil engineering characteristics were also noted. The stratigraphic contacts, indicated on the exploration logs in Appendix A, represent the approximate boundaries between soil types; actual transitions between soil units might be more gradational than shown.

Disturbed soil samples were collected at selected intervals using a standard 2-inch diameter split-barrel sampler and automatic safety hammer system. In each test, the sampler was advanced 18 inches by dropping a 140-pound hammer 30-inches for each strike in accordance with ASTM D1586. The number of hammer-blows for each 6 inches of penetration was recorded. The standard penetration resistance (designated as the “N-value”) of the soil is calculated as the sum of the number of blows required for the final 12 inches of sampler penetration. SPT N-values of 50 or more blows per 6 inches or less of penetration is defined as “refusal.” The N-value is an indication of the relative density of granular soils and the relative consistency of cohesive soils. The drill rig was equipped with an automatic hammer to obtain Standard Penetration Test (SPT) samples. Western States provided an automatic hammer calibration Report of SPT Hammer Energies (GeoDesign, 2018), showing that the drill rig used for our site investigation (Rig #2, CME-55) has an energy transfer ratio of 81.2 (correction factor = 1.353). N-values reported on our boring logs are, however, uncorrected field-recorded values (i.e., no corrections have been applied).

### 2.3 Laboratory Testing

Soil samples were delivered to the McMillen Jacobs Portland office for further examination and storage. Each of the samples was re-examined and compared to the field boring log description to confirm the field classifications and maintain consistency. Representative samples were then selected for the following laboratory testing:

- Water (Moisture) Content of Soil and Rock by Mass (ASTM D2216);
- Amount of Material Finer than a No. 200 Sieve (i.e., ‘Fines Content’) (ASTM D1140);

- Standard Test Methods for Liquid Limit, Plastic Limit, and Plasticity Index of Soils (ASTM D4318); and
- Standard Test Methods for One-Dimensional Expansion, Shrinkage, and Uplift Pressure of Soil-Lime Mixtures (ASTM D3877), with an explanation provided below.

Moisture contents, Atterberg limits, and Percent fines are indicated on the boring logs in Appendix A. Individual laboratory test reports are included in Appendix B.

### 2.3.1 One-Dimensional Expansion, Shrinkage, and Uplift Pressure Tests

Three, one-dimensional expansion, shrinkage, and uplift pressure tests (referred to hereafter as shrink-swell / expansion pressure tests) were performed on remolded composite SPT samples. The expansion pressure test is the first step, in which the sample is placed in a consolidometer and inundated. As the sample tries to expand, the vertical pressure is increased just enough to keep the sample from expanding. This process is continued until the applied vertical load maintains a constant-volume condition of the soil sample. The vertical pressure to maintain this condition is the uplift or expansion pressure.

After the uplift pressure phase of the test, the expansion-shrinkage phase of the test is performed. The sample is removed from the consolidometer, weighed, and allowed to air-dry for typically three days. Then, the sample dimensions and weight are measured and put in an oven. After oven-dried, the sample dimensions and weight are measured again. The volume change vs. moisture content is then plotted; an increase in volume corresponds to expansion and a decrease in volume corresponds to shrinkage. A summary of these test results is presented in Table 2-1.

**Table 2-1: Results Summary of Shrink-Swell & Expansion Pressure (ASTM D3877) Tests**

Sample Designation	Sample Depth (feet)	In-Situ Moisture Content (%)	Expansion Pressure Phase		Shrink-Swell Phase	
			Expansion Pressure (psf)	Change in Height (%) (positive=swell), (negative=shrink)	Volume Change <sup>3</sup> (%)	Range of Moisture Contents <sup>4</sup> (%)
Boring B-1, Sample S-1/S-2	2.5 to 6.5	33.1	7,381 <sup>1</sup>	1.32	-5.1	32.7 to 0.0
Boring B-1, Sample S-3/S-4	7.5 to 11.5	59.3	N/A <sup>2</sup>	-0.3% at 100 psf load	-26.1	59.9 to 0.0
Boring B-4, Sample S-1/S-2	2.5 to 6.5	39.9	N/A <sup>2</sup>	-0.4% at 100 psf load	-16.6	40.2 to 0.0

Notes:

1. Expansion pressure based on inundating soil from air-dried condition.
2. Expansion pressure based on inundating soil from in-situ/field moisture content.
3. Volume change measured in one dimension (e.g., height of sample), from saturated to oven-dry. Negative values indicate shrinkage.
4. Higher moisture content value represents saturated condition and 0 percent moisture represents oven-dry conditions.

## **3.0 Site Conditions**

### **3.1 Surface Conditions**

The Project site is in Woodmansee Park, approximately 30-acre City park located on the west side of Sunnyside Road SE and about ½ mile north of Kuebler Boulevard. The Project site is bordered by Sunnyside Road SE to the east, residential developments to the north and south, and the north-flowing Pringle Creek to the west. Existing features within Woodmansee Park include two tennis courts, a basketball court, restroom facilities, an access road, three parking areas, a soccer/sports field, a covered picnic area, and a frisbee golf course. The southern portion of the park is generally grass-surfaced and includes the tennis courts, basketball court and the soccer/sports field, while the northern and western areas of the park are generally more vegetated with coniferous and deciduous trees. Pringle Creek flows along the western boundary of the park. In general, topography within the park slopes gently downhill to the north, with an overall vertical relief of about 15 to 20 feet. To the west of Pringle Creek, the topography rises to the west, with an overall vertical relief of about 10 feet, and flattens out at the neighboring Judson Middle School property.

### **3.2 Site Geology**

The Project site is situated in Salem Heights, the name given to the rolling upland area of indefinite extent near the southern City of Salem limits and is included in the northeastern part of the more extensive Salem Hills area (Foxworthy, 1970). The approximately 60-square-mile Salem Hills area rises to the south from the City of Salem, from an elevation of approximately 200 feet to slightly more than 1,100 feet at Prospect Hill, located about 4 miles southwest of the Project site.

The oldest rock unit in the Project site area is the Eocene-Oligocene sedimentary bedrock, typically consisting of sandstone, siltstone, and mudstone, with lesser amounts of conglomerate and interspersed localized volcanic rocks (Wang and Leonard, 1996). The middle Miocene (about 17 to 6 million years before the present time) Columbia River Basalt Group (CRBG) overlies the sedimentary bedrock, and typically consists of weathered and fresh basaltic lava flows with interflow zones characterized by vesicular flow-top breccia, ash, and baked soils (Wang and Leonard, 1996). The maximum CRBG thickness ranges from about 400 to 600 feet, generally thickest in the Salem Hills and thins to the north towards Salem. Well logs drilled in Woodmansee Park as part of the original City of Salem ASR study indicated a CRBG thickness of about 270 feet (Foxworthy, 1970).

The upper region of the basalt has been deeply weathered to laterite and saprolite soils; red-brown clayey soils, collectively referred to in this report as residual soil. The residual soils extend to depths on the order of 200 feet in the Salem Hills and generally thin out to the north towards Salem; typically, several tens of feet thick in the Salem Heights and Salem Hills areas. The previously-referenced ASR study encountered residual soils to depths of up to 65 feet (Foxworthy, 1970) at the Project site.

Overlying the bedrock units are Quaternary lower terrace deposits of alluvial bottomlands; land that is typically adjacent to a river or creek (e.g., Pringle Creek in this case) and subject to overflow during floods. These deposits primarily consist of low to medium plasticity, clayey soils with minor amounts of sand and typically extend to depths of about 4 to 12 feet along bottomlands of interior drainages (Bela, 1981).

### **3.3 Subsurface Conditions**

Subsurface conditions were generally consistent between the four borings advanced as part of our geotechnical exploration. Except for an upper 1-foot topsoil zone, we encountered residual soil to the maximum depths explored, up to 50 feet bgs. We did not encounter Quaternary alluvium (i.e., lower terrace deposits) that is shown on geologic mapping; likely because this unit is locally present in the vicinity of Pringle Creek and our explorations were at least 300 feet from Pringle Creek. The residual soil unit has been defined by its geologic origin, stratigraphic position, engineering properties, and its distribution in the subsurface. Variations in subsurface conditions may exist between the locations of the borings. Contacts between the various soil types within the residual soil unit are approximate and may be more gradational than shown on the boring logs in Appendix A.

#### **3.3.1 Residual Soil of Columbia River Basalt Group**

Residual soil of the Columbia River Basalt (CRB) group was encountered below topsoil in each of the borings, at an approximate depth of 1 foot bgs, and extended to the maximum depth explored of approximately 50 feet bgs. The residual soil is a product of deep, in-place weathering of the CRB.

The residual soil is typically red-brown with frequent varicolored mottled zones, ranging from red to yellow to black. The overall structure of the residual soil is typically heterogeneous, with a clayey, silty matrix containing frequent angular gravel clasts of predominately weathered to decomposed basalt, with the parent rock fabric being apparent.

Forty-two SPT N-values were recorded in the residual soil, ranging from 2 to 53 blows per foot (bpf) and averaging 17 bpf; indicating soft to hard consistencies. Seven Atterberg Limits tests indicated liquid limits (LL) ranging from 48 to 112 and plasticity indices (PI) ranging from 24 to 51; resulting in lean clay (CL), fat clay (CH), and elastic silt (MH) soil classifications. Thirty-six moisture contents test ranged from 32 to 83 percent and generally increased with depth.

In the upper 7 to 12 feet, soil moisture content typically ranges from 32 to 40 percent, and increases from 53 to 83 percent below these depths. Soils in the upper 7 to 12 feet typically exhibit transitional-type behavior, plotting around the CL-CH-MH transition zone on the PI versus LL graph. An exception to this trend was observed in boring B-2, in which non-plastic silt with sand (ML) and moisture content above 50 percent was observed in the upper 16 feet.

### **3.4 Groundwater**

The borings were advanced using mud rotary drilling methods, thereby precluding the observation of groundwater conditions during drilling. However, in boring B-4 (at the proposed WTF), the borehole was flushed clean and allowed to stay open for about two hours, allowing for the groundwater level to stabilize to the extent possible. Using an electronic groundwater level indicator, we measured a groundwater level of 5.6 feet bgs at this location.

We researched available well logs located within Section 10, Township 8 South, Range 3 West, Willamette Meridian on the Oregon Water Resources Department (OWRD) website. Our research resulted in five well logs drilled in Woodmansee Park as part of the City of Salem ASR study. Our review

indicated groundwater levels at the site ranged from about 8 feet to 135 feet bgs. It should be noted that groundwater levels reported on the OWRD logs often reflect the purpose of the well, so water well logs may only report deeper, confined groundwater, while geotechnical or environmental borings will often report any groundwater encountered, including shallow, unconfined groundwater. Therefore, the levels reported on the OWRD well logs referenced above are considered generally indicative of local water levels and may not reflect actual groundwater levels at the project site. However, well logs for ASR wells No. 4 and ASR No. 6 indicated groundwater was first encountered at depths of 10 feet and 8 feet bgs, which is consistent with our findings.

Groundwater levels may vary with precipitation, the time of year, site utilization, and/or other factors. Generally, groundwater highs occur near the end of the wet season in late spring or early summer and groundwater lows occur near the end of the dry season in the early fall. We believe that that water levels encountered during the current investigation are close to the seasonal maximum.

## **4.0 Seismic and Geologic Hazard Evaluation**

We performed a seismic hazards evaluation in general accordance with the 2019 Oregon Structure Specialty Code (OSSC, 2019) and ASCE's Minimum Design Loads for Buildings and Other Structures, 2016 Edition (ASCE/SEI 7-16). The OSSC requires evaluating the seismic hazards for the Maximum Credible Earthquake (MCE) having a 2-percent probability of exceedance in a 50-year period (2,475-year return period).

### **4.1 Regional Seismicity**

The Pacific Northwest is a seismically active region that has three principle seismic sources: (1) the Cascadia Subduction Zone (CSZ) megathrust, which represents the interface between the subducting Juan de Fuca plate and the overriding North American plate; (2) faults located within the Juan de Fuca plate (referred to as CSZ intraplate or intraslab sources); and (3) crustal faults principally within the North American plate (Wong and Silva, 1998). Faulting and seismicity associated with Cascade volcanoes are also potential sources of seismicity, though they generally do not impact sites in the Willamette Valley.

#### **4.1.1 Crustal Sources**

Crustal sources typically occur at depths ranging from approximately 14 to 40 kilometers bgs (Geomatrix Consultants, 1995). A search was performed on the U.S. Geological Survey (USGS) website (USGS, 2020) to identify known crustal seismic sources within 20 kilometers (about 12.5 miles) of the project alignment. These faults are presented in Table 4-1.

**Table 4-1. Known Faults Within 20 km of the Project Site**

USGS Fault ID.	Fault Name	Char. Mag	Type of Fault	USGS Fault Class <sup>1</sup>	Approx. Earthquake Depth (km)	Distance (km) & Direction from Site	Notes
719	Salem-Eola Hills Homocline	6.00	Homocline (Normal)	A	15 to 40 km	6.3 km West	3
871	Turner and Mill Creek faults	6.59	Normal	A	15 to 40 km	9 km South	2
872	Waldo Hills fault	6.00	Normal	A	15 to 40 km	4.5 km Southwest	3

Notes:

- USGS Fault Classes from USGS Earthquake Hazards Program, 2014 National Seismic Hazard Maps
  - Class A: Fault with convincing evidence of Quaternary activity (ACTIVE)
  - Class B: Fault that requires further study in order to confidently define their potential as possible sources of earthquake-induced ground motion (POTENTIALLY ACTIVE)
- Characteristic earthquake magnitude from USGS Earthquake Hazards Program, 2014 National Seismic Hazard Maps – Fault Parameters.
- Characteristic earthquake magnitude from Section 1803.3.2.1 of the 2019 OSSC - Design Earthquake.

#### 4.1.2 Cascadia Subduction Zone Seismic Sources

The Cascadia Subduction Zone (CSZ) is an approximate 1,000-kilometer-long zone of active tectonic convergence where oceanic crust of the Juan de Fuca Plate is subducting beneath the North American continental plate at a rate of about 3 to 4 centimeters per year (DeMets, et al., 1990). The fault trace is located off the coast of southern British Columbia, Washington, Oregon, and northern California; approximately 325 kilometers west of the site.

There are two primary seismicity sources associated with the CSZ: 1. relatively shallow earthquakes that occur on the interface between the Juan de Fuca and North American plates (i.e., Subduction Zone earthquakes) and 2. deep earthquakes that occur along faults within the subducting Juan de Fuca plate (i.e., intraplate earthquakes). These two types of earthquakes are discussed in the following sections.

##### 4.1.2.1 Subduction Zone Earthquakes

Large subduction zone (megathrust) earthquakes occur within the upper approximate 30 kilometers of the contact between the two plates (Pacific Northwest Seismic Network (PNSN), 2020). As the Juan de Fuca Plate subducts beneath the North American Plate through this zone, the plates are locked together by friction (PNSN, 2020). Stress slowly builds as the plates converge until the frictional resistance is exceeded, and the plates rapidly slip past each other resulting in a megathrust earthquake. The USGS estimates megathrust earthquakes on the CSZ may have magnitudes up to M9.2. Geologic evidence indicates a recurrence interval for major subduction zone earthquakes of 250 to 650 years, with the last major event occurring in 1700 (Atwater, B.F., 1992).

##### 4.1.2.2 Intraplate Earthquakes

Below depths of approximately 30 kilometers, the plate interface does not appear to be locked by friction, and the plates slowly slide past each other. The curvature of the subducted plate increases as the

advancing edge moves east, creating extensional forces within the plate. Normal faulting occurs in response to these extensional forces. This region of maximum curvature and faulting of the subducting plate is where large intraplate earthquakes are expected and is located at approximate depths ranging from 30 to 60 kilometers (Geomatrix Consultants, 1993, 1995 and Kirby, S.H. et al., 2002). Intraplate earthquakes within the Juan de Fuca plate generally have magnitudes less than M7.5 (Cascadia Region Earthquake Workshop, 2008). The 2001 M6.8 Nisqually earthquake near Olympia, Washington, occurred within this seismogenic zone at a depth of 52 kilometers.

## 4.2 Site Classification

We assigned a seismic site class for the Project site following code-based procedures in ASCE/SEI 7-16, Chapter 20 (2016). Site class is used to categorize common subsurface conditions into broad classes to which ground motion attenuation and amplification effects are assigned. Site classification is based on the weighted average of the shear wave velocity or Standard Penetration Test (SPT) blow counts (N-value) in the upper 100 feet of subsurface profile. Based on the SPT N-values from our recent geotechnical exploration, a Site Class D is appropriate for design purposes.

## 4.3 Seismic Design Parameters

The 2019 OSSC requires that spectral response accelerations be developed based on ASCE 7-16. We developed spectral response accelerations using the online ASCE 7 Hazard Tool, which references ground motion procedures in accordance with ASCE 7-16 and is based on the USGS 2014 National Seismic Hazard Mapping Project (NSHMP) developed for the Maximum Considered Earthquake (MCE) (Peterson et. al., 2008). The MCE consists of ground motions (accelerations) with a 2-percent probability of exceedance in 50 years (return period of 2,475 years). The mean earthquake magnitude and the mean site-to-source distance for the zero-second period of vibration (e.g., PGA) are 8.34 and 68.75 km, respectively, for the MCE. The recommended spectral acceleration parameters for use in structural design are provided in Table 4-2.

**Table 4-2. 2019 OSSC MCE Spectral Acceleration Parameters for Site Class D**

Parameter	0.2-Second Period	1-Second Period
Mapped $MCE_R$ (Rock site)	$S_S = 0.821g$	$S_1 = 0.415g$
Site Coefficients	$F_a = 1.172$	$F_v = 1.885$
Site-Adjusted $MCE_R$	$S_{MS} = 0.962g$	$S_{M1} = 0.782g$
Design $MCE_R$	$S_{DS} = 0.641g$	$S_{D1} = 0.523g$
Mapped $MCE_G$ PGA (Rock Site)	0.382g	
Site Coefficient $F_{PGA}$	1.218	
Site-adjusted $MCE_G$ PGA	0.466g	
Site-Adjusted Peak Ground Velocity (PGV) (cm/sec)	74	

It is important to note that Section 11.4.8 of ASCE 7-16 requires a site-specific ground motion hazard analysis be performed on structures on Site Class D sites with a 1-second spectral response acceleration parameter ( $S_1$ ) greater than 0.2g. However, exception No. 2 in Section 11.4.8 states that a site-specific ground motion hazard analysis is not required if the structure's fundamental period of vibration  $T$  is less than  $1.5T_s$ . When this condition is met, the seismic response coefficient  $C_s$  shall be calculated using equation 12.8-2 in ASCE 7-16. The following provides a summary of these parameters:

- We anticipate the pumphouse and WTF buildings will be single-story, reinforced concrete structures; therefore, we anticipate  $T$  will be less than or equal to 0.5 second;
- $T_s$  equals the design 0.2-second spectral response parameter  $S_{DS}$  divided by the design 1-second spectral response parameter  $S_{D1}$ . Using this equation and the  $S_{DS}$  and  $S_{D1}$  values in Table 4-2,  $T_s$  equals 1.226 and  $1.5T_s$  equals 1.839; and
- $T$  is less than  $1.5T_s$  and therefore, a site-specific ground motion hazard analysis is not required, and the seismic response coefficient  $C_s$  shall be calculated using equation 12.8-2 in ASCE 7-16.

#### 4.4 Seismic Sources and Hazard Deaggregation

The probabilistic seismic hazard assessment (PSHA) produces a mean source event (e.g., the MCE) that generates the spectral accelerations reported in Table 4-2. The deaggregation data identify the earthquake sources, magnitudes, and site-to-source distances that contribute to the mean source event. Table 4-3 summarizes the results of the mean source event hazard deaggregation for the zero-second period of vibration (e.g., PGA).

**Table 4-3: Deaggregation Results for 2,475-year Mean Source Event (MCE), PGA Period**

Source	Moment Magnitude, $M_w^1$	Site-to-Source Distance <sup>2</sup> (km)	% Contribution to Hazard
CSZ Interface	8.95	78.61	73.37
CSZ Intraslab	6.98	59.84	16.49
Crustal Faults <sup>3</sup>	6.19 to 6.6	11.77 to 13.92	10.14

Notes:

1.  $M_w$  values represent the mean value from each type of earthquake source.
2. Site-to-Source distances represent the mean value from each type of earthquake source.
3. Crustal faults source includes gridded seismic sources that represent earthquakes that do not occur on known, mapped faults.

#### 4.5 Liquefaction

Liquefaction is a phenomenon whereby saturated cohesionless soils, generally sands and silts, undergo significant loss of strength and stiffness when they are subjected to vibration or large cyclic ground motions produced by earthquakes. During earthquake shaking (e.g., undrained conditions), loads are

transferred from the soil skeleton to the pore-water with consequent reduction in the soil shear strength. The shear strength of a cohesionless soil is directly proportional to the effective stress; equal to the difference between the overburden pressure and the pore water pressure. The susceptibility of sands, gravels, and sand-gravel mixtures to liquefaction is typically assessed based on in-situ penetration resistance tests (e.g., SPT, CPT, etc.).

For fine-grained soils, however, susceptibility to liquefaction can be characterized into three categories (Boulanger and Idriss, 2014):

1. **Sand-like behavior:** Fine-grained soils with a plasticity index less than 7 are considered to exhibit classical soil liquefaction behaviors like clean sand.
2. **Clay-like behavior:** Fine-grained soils with a plasticity index greater than 12 are not considered to be liquefiable; however, cyclic softening and strain accumulation from seismic shaking should be considered.
3. **Transitional behavior:** Fine-grained soils with a plasticity index between 7 and 12 should be considered as “transitional” soils, and their seismic behaviors are expected to include cyclic softening, strength loss, and post liquefaction settlement.

As discussed in Section 3.3, we encountered residual soils from the ground surface to the maximum depths explored in each of our exploratory borings, about 50 feet bgs. Based on the results of our visual-manual soil classification, the residual soils exhibited clay-like behavior. Seven Atterberg Limits tests were completed on representative soils encountered during our geotechnical exploration, with plasticity indices ranging from 24 to 51; well within the clay-like behavior category. Therefore, we conclude the risk of liquefaction is negligible for the Project. This judgement is further supported by the liquefaction susceptibility map, which indicates “No Susceptibility” hazard level for the Project site (Wang and Leonard, 1996).

## 4.6 Lateral Spreading

Lateral spreading is a liquefaction-related phenomenon that results in ground displacement during an earthquake and occurs in sloping ground or flat ground with free face. Surface rupture due to lateral spreading can occur on sites underlain by liquefiable soils that are located immediately adjacent to slopes steeper than about 3 degrees (20H:1V), and/or adjacent to a free face, such as a stream bank or the shore of an open body of water. During lateral spreading, the materials overlying the liquefied soils are subject to lateral movement downslope or toward the free face. Due to the lack of liquefiable soils at the Project site, we conclude that the risk of lateral spreading is negligible for the Project.

## 4.7 Fault Rupture

There are no known active faults that are mapped on or immediately adjacent to the Project site. The nearest fault considered to be active is the Waldo Hills fault located 4.5 km southwest of the Project site. Therefore, we conclude the risk of surface rupture due to faulting is negligible.

#### **4.8 Slope Stability**

Due to the relatively flat to gently sloping topography on and surrounding the Project site, we conclude that the risk of slope instability, for both static and seismic conditions, is negligible. This conclusion is supported by our review of available online landslide susceptibility mapping on the Oregon Department of Geology and Mineral Industries (DOGAMI) Statewide Geohazards Viewer (HazVu), which indicates a “Low – Landsliding Unlikely” hazard level at the Project site (Oregon DOGAMI, 2020).

#### **4.9 Flood Hazard**

The Oregon DOGAMI HazVu mapping utilizes FEMA Flood Insurance Rate Maps (FIRM) to assess flood hazard. HazVu mapping indicates the project alignment is outside of any mapped flood hazards (DOGAMI, 2020).

#### **4.10 Other Hazards**

Other geologic and seismic hazards, including debris flows, and tsunamis/seiches are not considered hazards to the Project.

## 5.0 Conclusions and Key Geotechnical Considerations

Based on the results of our field explorations and analyses, the site can be developed as described in Section 1.2 of this report, provided the recommendations presented in this report are incorporated into the design and development. The primary geotechnical considerations for the Project are as follows:

- The presence of potentially shrinking-swelling, high plasticity soils (e.g., elastic silt and fat clay) at or near the anticipated foundation depths of the WTF and pumphouse buildings; and
- The presence of fine-grained silty residual soils which are sensitive to construction disturbance and moisture changes.

These considerations are discussed in further detail in the following sections.

### 5.1 Shrink-Swell Potential of Subgrade Soils

Three, shrink-swell / expansion pressure tests were performed within the residual soil unit. The test methods are discussed in Section 2.3.1, with the results summarized in Table 2-1. Detailed shrink-swell / expansion pressure test results are included in Appendix B.

Boring B-1 sample S-3/S-4 and boring B-4 sample S-1/S-2 did not exhibit expansive behavior; rather, they consolidated slightly (e.g., less than ½ percent) under a 100-psf load. The boring B-1 S-1/S-2 sample indicated an expansion pressure of about 7,400 psf. However, this expansion pressure is based on inundating the soil sample from an air-dried condition and is not representative of anticipated conditions expected during the service life of the proposed structures. Incidentally, this test demonstrates that foundation and structural distress could occur if the foundation subgrade soils are allowed to dry excessively during construction. As indicated in Table 2-1, the in-situ moisture content of each soil sample was negligibly less than saturated. Soil expansion corresponds to the volume increase due to the soil's absorption of water. A saturated or nearly-saturated soil cannot absorb additional water, or only a negligible amount of water. Therefore, at their in-situ saturated or nearly-saturated moisture conditions, the foundation subgrade soils are not susceptible to appreciable expansion if subjected to additional wetting.

As indicated by the shrink-swell / expansion pressure test results, each of the soil samples exhibited shrinkage ranging from 5.1 to 26.1 percent. The shrinkage occurred with a loss in moisture content, from saturated to oven-dry conditions, and corresponds to the decrease in soil sample height, expressed as a percentage.

The primary concern related to expansive and shrinkage potential of the foundation subgrade soils is the fluctuation of moisture content. The shrink-swell / expansion pressure tests demonstrate these soils are subject to significant changes in volume with changes in moisture content; swelling with an increase in moisture content and shrinking with a decrease in moisture content. Foundations and floor slabs founded directly on these soils may be subject to cyclic shrink-swell movements that can result in differential movements and structural distress. Therefore, to mitigate the shrink-swell potential of the foundation subgrade soils, we recommend the following:

- Extend the shallow foundations to a depth at which seasonal moisture content fluctuation is minimal, about 2.5 feet below adjacent site grades;
- Concrete slabs-on-grade should be supported on a minimum 6-inch thick layer of structural fill over properly prepared subgrade;
- Exposed foundation subgrade soils should be covered immediately with either structural fill or a geotextile fabric to minimize moisture loss;
- Exposed foundation subgrade soils should be saturated prior to casting concrete;
- Install perimeter drains around footings to drain the collected water in the backfill above footing level;
- Provide positive surface drainage away from all points around the building, with hardscaping extending a minimum of 5 feet from the building perimeter;
- Prevent the root systems of nearby large trees from approaching the foundations; and
- Eliminate landscaping around the perimeter of the structures to prevent water infiltration into the foundation subgrade.

## **5.2 Construction Disturbance on Moisture-Sensitive Soils**

The fine-grained residual soils are highly susceptible to disturbance and damage due to construction traffic during wet weather construction. If earthwork is undertaken without proper precautions, when the exposed soils are wet of optimum moisture content by more than a few percentage points, then significant damage to the subgrade could occur, making trafficability of these soils difficult. If construction occurs during wet weather, McMillen Jacobs recommends measures be implemented to protect the fine-grained subgrade in areas of heavy construction traffic, as provided in Section 7.6.

It is important to note that these conditions may be initiated regardless of the time of year; even during the dry summer months. When initially exposed, these soils can appear to be competent and at their near-optimum moisture content. However, once disturbed by construction equipment and traffic, the residual soil / decomposed rock structure can be crushed, thereby releasing water trapped inside and rendering a once-competent material to a wet and sticky mass. Once the soil is rendered to this condition, it can be extremely difficult to compact, as well as for construction equipment to travel upon. If these conditions prevail during the dry summer months, we recommend implementing measures provided in Section 7.6 to facilitate earthwork activities.

## **6.0 Design Recommendations**

### **6.1 Water Treatment Facility, ASR Well Houses, & Below-Grade Structures**

We understand the new WTF will be a 50-foot by 54-foot, single-story building with a finished floor elevation of 379 feet, which will likely require cuts up to about 3 feet deep. We understand the new WTF structure will be lightly loaded and founded on a perimeter footing with slab-on-grade foundation system. The new WTF will be situated in the middle of an approximately 180-foot by 110-foot area that will be regraded/flattened and paved with asphalt.

Three new ASR wellhouses for ASR well Nos. 8 through 10 will each be approximately 900 square-foot single-story structures. We anticipate the pumphouses will be lightly loaded and founded on either a conventional perimeter footing with slab-on-grade foundation system or on a mat foundation with thickened edges.

In addition to the above-referenced at-grade structures, we anticipate there will be several ancillary below-grade structures, including buried vaults/manholes and pump stations. We anticipate the below grade structures will consist of either precast or cast-in-place reinforced concrete construction.

Foundation recommendations for both the at-grade and below-grade structures are provided in the following sections.

### **6.1.1 Subgrade Preparation**

Satisfactory subgrade support for shallow foundations (for WTF and new ASR wellhouses) can be obtained from the native, medium stiff to stiff residual soil, or new structural fill that is properly placed and compacted on these soils during construction. As discussed in Section 5.1, the foundation subgrade soils are susceptible to shrink-swell behavior. To mitigate this behavior, we recommend overexcavating to a minimum depth of 2.5 feet below the adjacent finished grade elevation.

Once the overexcavations are complete, McMillen Jacobs should be contacted to observe subgrade conditions. The exposed foundation subgrade soils should not be exposed to period of wetting or drying but should be covered with geotextile fabric as soon as possible. The geotextile fabric should be in conformance with Section 7.3.7.

Overexcavations should be brought back to grade with imported structural fill in conformance with Section 7.3.2. The maximum particle size of overexcavation backfill should be limited to 1½ inches. All granular pads for footings should be constructed a minimum of 6 inches wider on each side of the footing for every vertical foot of overexcavation. To minimize the disturbance of the fine-grained subgrade, we recommend the use of lightweight excavation equipment with smooth-edged digging buckets. In addition, we recommend only static compaction with a small roller be used for the granular footing pads.

### **6.1.2 Minimum Footing Width and Embedment**

Minimum footing widths should be in conformance with the 2019 OSSC. We recommend individual spread footings have a minimum width of 24 inches and continuous wall footings have a minimum width of 18 inches. All footings should be founded at least 18 inches below the lowest, permanent adjacent grade to develop lateral capacity and for frost protection.

### **6.1.3 Footing Bearing Pressure & Settlement**

Footings founded as recommended above may be proportioned for an allowable soil bearing pressure of 2,000 pounds per square foot (psf), based on a factor of safety (FOS) of 3. This bearing pressure is a net bearing pressure (i.e., footing weight and overlying backfill are neglected), applies to the total of dead and long-term live loads, and may be increased by one-third when considering seismic or wind loads.

For foundations founded as recommended above, total settlement of foundations is anticipated to be less than 1 inch. We expect that differential static settlements across the foundation elements will be on the order of one-half of the total settlement.

#### **6.1.4 Interior Floor Slabs**

##### **6.1.4.1 Subgrade Preparation**

Satisfactory subgrade support for shallow foundations can be obtained from the native, medium stiff to better residual soil, or new structural fill that is properly placed and compacted on these soils during construction. If soft, loose, or otherwise unsuitable materials are encountered, they should be overexcavated as recommended by McMillen Jacobs during construction. Interior floor slabs should be founded upon a minimum 6-inch thick layer of structural fill that should be placed in one lift and compacted to at least 90 percent of the maximum dry density as determined by ASTM D1557.

##### **6.1.4.2 Interior Floor Slab Design Parameters**

A modulus of subgrade reaction value of 100 pounds per cubic inch (pci) may be used for slab-on-grade design. This subgrade modulus value represents the anticipated value, which would be obtained in a standard in situ plate test with a 1-foot square plate. Use of this subgrade modulus for design should include appropriate modifications based on dimensions as necessary.

##### **6.1.4.3 Subgrade Moisture Considerations**

Liquid moisture and moisture vapor should be anticipated at the subgrade surface. The recommended crushed rock base is anticipated to provide protection against liquid moisture. Where moisture vapor emission through the slab must be minimized (e.g., impervious floor coverings, storage of moisture sensitive materials and or equipment directly on the slab surface, etc.), a vapor retarding membrane or vapor barrier below the slab should be considered. Factors such as cost, special considerations for construction, floor coverings, and end use suggest that the decision regarding a vapor retarding membrane or vapor barrier be made by the designer and owner.

If a vapor retarder or vapor barrier is placed below the slab, its location should be based on current American Concrete Institute (ACI) guidelines, ACI 302 Guide for Concrete Floor and Slab Construction. In some cases, this indicates placement of concrete directly on the vapor retarder or barrier. It should be noted that the placement of concrete directly on impervious membranes increases the risk of plastic shrinkage cracking and slab curling in the concrete. Construction practices to reduce or eliminate such risk, as described in ACI 302, should be employed during concrete placement.

#### **6.1.5 Lateral Earth Pressures**

Backfill material placed behind the below-grade structures should consist of free-draining crushed aggregate, as described in Section 7.3.3. The following table summarizes our recommended lateral earth pressure values, expressed as the equivalent fluid pressures.

**Table 6-1. Recommended Lateral Earth Pressures**

Design Condition	Groundwater Condition <sup>1</sup>	Static At-rest Pressure (psf)	Static & Live Load Surcharge Pressure (psf)	Additional Seismic Pressure (psf)	Hydrostatic Pressure (psf)
At-Rest Earth Pressure	Above Groundwater	$50(H-H_w)$	$0.40q$	$34H$	--
	Below Groundwater	$50(H-H_w) + 27H_w$	$0.40q$	$34H$	$62.4H_w$
Active Earth Pressure	Above Groundwater	$32(H-H_w)$	$0.26q$	$17H$	--
	Below Groundwater	$32(H-H_w) + 18H_w$	$0.26q$	$17H$	$62.4H_w$

Notes:

1. We recommend a groundwater level of 5 feet bgs for the calculation of hydrostatic pressure.

H is the total height of the buried wall and  $H_w$  is the submerged portion of the buried wall (i.e., from the bottom of the buried wall up to the groundwater level). The above recommendations are valid only for imported, free-draining crushed aggregate and finished backfill slopes of flatter than 4H:1V (horizontal:vertical). The above earth pressures can be assumed to act horizontally on the embedded walls. The equivalent fluid earth pressures and seismic earth pressures increase with depth in a hydrostatic, triangular pressure distribution with the resultant force acting at approximately 0.3H above the base of the wall. The pressure distribution of the surcharge loads is a constant value of lateral pressure resulting from the vertical, surface surcharge loads (q) with the resultant lateral surcharge force acting approximately at a height above the base of the wall equal to one-half the total wall height. The distribution and resultant of the backfill, groundwater, and seismic earth pressure are shown in Figure 3.

### 6.1.6 Lateral Resistance

Lateral resistance for the below- and at-grade structure foundations can be provided by frictional resistance between the subgrade and the bottom of the foundations and by passive resistance around the footings. For the base frictional resistance, we recommend using an ultimate friction coefficient of 0.55 for cast-in-place concrete on prepared subgrade or structural fill. A coefficient of 0.45 may be used for pre-cast concrete foundations (i.e., vaults and manholes). Typically, a FOS of 1.5 is used to convert to allowable friction coefficients.

Lateral resistance can also be provided by passive resistance of the foundations. We recommend using an ultimate equivalent fluid pressure of 375 pounds per cubic foot (pcf) in the design of foundations. This resistance should be applied across the face of the foundation element. To develop full passive resistance, slight movement may first need to occur. Because of this, we recommend (1) neglecting using passive resistance in the upper 12 inches of the foundation element and (2) applying a FOS of 3 to the ultimate value (e.g., use a recommended passive earth pressure of 125 pcf).

### 6.1.7 Buoyancy

As of the date of issuance of this report, we have not been provided information regarding below-grade structures. Once this information is provided, we will update the subsequent version of this report and

revise the preliminary recommendations herein, if warranted. Buoyancy concerns are generally during periods of seasonal high groundwater levels and when partially or entirely empty. To evaluate buoyancy potential, we recommend assuming a groundwater level at the surface at the Project site.

Below-grade structures should be designed to resist buoyant uplift and lateral hydrostatic forces. Buoyant uplift is resisted by the dead weight of the structure, the weight of the backfill projected vertically above the outside edge of foundations extending beyond the vertical walls, and by frictional resistance between the structure and the backfill. The friction coefficients from Section 6.1.6 can be used for vertical frictional resistance along the earth/structure interface.

### **6.1.8 Drainage Considerations**

Because of the shrink-swell potential of the foundation subgrade soils, site drainage and stormwater management are of critical importance for this Project. We recommend the following implementations be maintained during the operation of the ASR Facilities:

- A minimum 5-foot wide hardscaping/concrete apron should extend around the perimeter of the buildings and should be sloped to drain away from the foundations in all directions;
- Roof downspouts and drains should discharge well beyond the limits of the building footprints;
- Any subsurface drains should be connected to the nearest storm drain or other suitable discharge point;
- Paved surfaces near the buildings should be sloped to drain away from the buildings; and
- Eliminate landscaping around the perimeter of the structures to prevent water infiltration into the foundation subgrade.

## **6.2 Pipelines**

As of the date of issuance of this report, no information has been provided regarding the piping materials, sizes, or invert depths. The recommendations provided herein assume the pipe materials will be flexible (e.g., steel, ductile iron, HDPE, etc.) with a depth of cover of less than 5 feet. Once more detailed pipeline information is provided, the subsequent version of this report will be revised, if warranted.

### **6.2.1 Pipeline Subgrade Support**

We anticipate pipeline subgrade soils will consist of medium stiff to stiff, medium to high plasticity residual soils (e.g., silts and clays). Scattered zones of very soft soil will likely be encountered along the alignment which may require subgrade stabilization. Details of subgrade stabilization are provided in Section 7.3.6.

The new pipeline construction will not result in a net increase in pressure at the base of the pipeline, and therefore pipe settlement under static conditions is expected to be negligible.

## 6.2.2 Soil Design Parameters

Flexible pipes derive their load-carrying capacity from their interaction with the pipe zone backfill as the pipe deflects under load and pushes laterally against the soil. Load-carrying capacity depends on the depth of the pipe, the surrounding soil conditions, the type and density of the backfill, and the thickness of compacted pipe zone backfill between the pipe and the native soil in the trench wall. Based on the anticipated subsurface soil types and relative densities, the following geotechnical design parameters are recommended for pipeline design. These are provided in Table 6-2.

**Table 6-2. Pipeline Geotechnical Design Parameters**

Property	Depth of Cover (feet) <sup>3</sup>	Residual Soil	Granular Backfill	CLSM <sup>1</sup>
Moist Unit Weight, $\gamma_m$ (pcf)	--	115	130	125
Saturated Unit Weight, $\gamma_{sat}$ (pcf)	--	120	135	125
Friction Angle, $\phi$ (degrees)	--	28	36	34
Modulus of Soil Reaction, $E'$ (psi) <sup>2</sup>	$2 \leq D \leq 5$	500	1,000	2,000
Soil/Steel Pipe Friction Coefficient, $\mu$	--	0.2	0.4	0.4

Notes:

1. CLSM: Controlled Low Strength Material, Unit weight of CLSM may be specified by the designer; 125 pcf is typical value.
2. Modulus of soil reaction values are unfactored.
3. D: Depth of cover above top of pipe.

The design parameters presented in Table 6-2 are appropriate for use in the Iowa deflection formula (Spangler, 1941) and are consistent with American Water Works Association Manual M11 (2004). Note that the Modulus of soil reaction,  $E'$ , is approximately equivalent to the constrained soil modulus,  $M_s$ .

The pipe should be designed considering traffic loads. These loads will vary depending on the final depth of the pipeline. Traffic loads are generally insignificant at depths of 10 feet or greater.

## 6.2.3 Pipeline Buoyancy and Flotation

When pipes are installed under the groundwater table, they can be susceptible to buoyancy if the upward buoyant forces on the pipe exceed the downward gravitational forces from the soil cover and the weight of the pipe. We evaluated pipe flotation assuming a 24-inch diameter steel pipe, 2 feet of soil cover and groundwater at the ground surface. The results of our evaluation indicated a factor of safety of greater than 3, which exceeds the typical minimum factor of safety of 1.5.

## 6.3 Infiltration Facilities

We understand that the Project will incorporate green stormwater infrastructure (GSI) into the site design of the WTF. Accordingly, a stormwater infiltration facility is planned within the northwest of the paved area encompassing the WTF. Based on our review of the *Stormwater Design Handbook for Developers and Large Projects* (City of Salem, May 2014), we understand that if an infiltration rate is less than

½ inch per hour, partial infiltration facilities are allowed. Medium to high plasticity, elastic silt (MH) soils were encountered in the upper 5 feet in B-4, drilled at the proposed WTF site. Based on our experience with these types of soils, we anticipate that infiltration rates will be sufficiently less than ½ inch per hour (e.g., likely on the order of zero to 0.1 inch per hour). Therefore, we do not think that infiltration testing for the proposed stormwater infiltration facility is warranted. To be conservative, we recommend a design infiltration rate of zero inch per second be used.

## **7.0 Construction Recommendations**

Construction recommendations for the Project are presented in the following sections. All material specifications referenced in this section referred to 2018 Oregon Standard Specifications for Construction (ODOT, 2018). A number of project details are still undefined at this level of design. McMillen Jacobs should review the design as it is advanced to confirm recommendations are applicable in the event facility layout and details change.

### **7.1 Site Preparation**

#### **7.1.1 Demolition**

If applicable, demolition of any existing structures should include complete removal of all structural elements, including asphalt parking areas, foundations, and concrete slabs. Abandoned buried utilities should similarly be removed or grouted full. Concrete and asphalt debris resulting from demolition may be re-used as structural fill, provided it is processed in accordance with the recommendations presented in Section 7.3.1.2. Alternatively, demolition debris should be hauled off site for disposal.

#### **7.1.2 Site Stripping**

Vegetation, topsoil, and any undocumented fill encountered should be removed from the proposed building and pavement areas, and for a 5-foot-margin around such locations. Based on the results of our field explorations, stripping depths at the site are anticipated to extend up to approximately 2.5 feet bgs for the four proposed structures at the Project site (e.g., overexcavation depth for the footings). These materials may be deeper or shallower at locations away from our explorations. The geotechnical engineer or his representative should provide recommendations for actual stripping depths based on observations during site stripping. Stripped topsoil and rooted soils should be transported off-site for disposal or stockpiled for later use in landscaped areas. Concrete and asphalt debris resulting from demolition may be stockpiled for later re-use as structural fill, as discussed in Section 7.3.1.2.

#### **7.1.3 Existing Utilities & Below-Grade Structures**

All existing utilities should be identified prior to excavation. Abandoned utility lines beneath the new buildings, pavements, and hardscaping features should be completely removed or grouted full. Soft, loose, or otherwise unsuitable soils encountered in utility trench excavations should be removed and replaced with structural fill in conformance with Section 7.3.2 this report. Buried structures (e.g., footings, foundation walls, slabs-on-grade, tanks, etc.), if encountered during site development, should be completely removed and replaced with structural fill in conformance with Section 7.3.2.

#### **7.1.4 Erosion Control**

Erosion and sedimentation control measures should be employed in accordance with applicable City, County, and State regulations.

#### **7.1.5 Subgrade Preparation**

Subgrade preparation for shallow foundations and interior floor slabs are provided in Sections 6.1.1 and 6.1.4.1, respectively. McMillen Jacobs should observe the final subgrade surface, inspect the condition of the subgrade, and identify additional over-excavation as necessary. This subgrade inspection should occur prior to the subgrade being covered with crushed rock or formwork.

### **7.2 Pipeline Trench Excavation**

We anticipate the maximum pipeline trench depths will be on the order of 5 feet. The final trench excavation should be performed with a straight-edged excavator bucket to minimize disturbance to the base of the trench. Following excavation, the trench base should be thoroughly cleaned of loosened or disturbed soils, by hand if necessary.

For pipe sizes up to 24 inches in diameter, the trench width should extend a minimum of 12 inches beyond each side of the pipe (i.e., OD + 24 inches + trench protection). Where trench shielding or shoring is used, the 12 inches should be measured between the pipe and inside face of the shielding or shoring. This will allow for the use of mechanical compaction equipment on the sides of the pipe.

### **7.3 Fill Materials and Compaction Criteria**

#### **7.3.1 On-Site Materials**

##### **7.3.1.1 Residual Soil**

We do *not* recommend the re-use of the native residual soil as structural fill, due to its fine-grained, high-plasticity properties. In addition, these soils are extremely difficult to properly moisture condition and compact during construction; especially during the wet winter months.

##### **7.3.1.2 Asphalt and Concrete Debris**

Any asphalt and concrete debris resulting from the demolition of existing pavements and other features may be re-used as structural fill provided it can be processed into material that is reasonably well-graded. In general, the following recommendations should be considered when using the onsite asphalt and concrete debris as structural fill materials on the Project:

- All processed fill should be free of objectionable debris (clay clumps, organic and/or deleterious material, etc.) and within moisture contents suitable for compaction;
- All processed fill should have less than 15 percent material passing the U.S. Standard No. 200 Sieve as determined by ASTM D1140 (i.e., fines content);

- If encountered, cobbles, boulders, or other oversized particles greater than 4 inches should be removed from on-site materials considered for use as fill;
- Prior to filling operations, representative samples of each proposed fill type should be collected. Gradation tests (particle-size analysis) should be performed on the samples to evaluate their suitability for use as fill materials; and

If used as structural fill, the on-site materials should be prepared in conformance with the following paragraph.

### **7.3.2 Structural Fill**

Structural fill materials should be placed after subgrade preparation and approval. Structural fill below new structure footprints should consist of either 1½-inch or ¾-inch minus Dense-Graded Aggregates conforming to the ODOT OSSC 02630.10. Unless otherwise noted, structural fill should be compacted to 90 percent of ASTM D1557. The structural fill should be placed in maximum lifts of 8 inches of loose material. Each lift of compacted engineered fill should be tested by a qualified testing agency prior to placement of subsequent lifts. This fill condition should extend laterally beyond the exterior perimeter of the building foundation a distance equal to the thickness of the fill or 3 feet; whichever is less.

### **7.3.3 Embedded Walls and Below-Grade Structure Backfill**

Backfill for embedded walls and below-grade structures should consist of imported structural fill as described in Section 7.3.2 and contain less than 5 percent fines (e.g., passing the U.S. Standard No. 200 Sieve). This material should be compacted to a minimum of 90 percent of the maximum dry density, as determined by ASTM D1557. Backfill placed within 3 feet of the below-grade structures should be compacted in lifts less than 6-inches thick using hand-operated tamping equipment (e.g., jumping jack or vibratory plate compactors). If flat work (e.g., concrete slabs or pavements) will be placed atop the wall backfill, we recommend that the upper 2 feet of material be compacted to 92 percent of the maximum dry density, as determined by ASTM D1557.

### **7.3.4 Pipe Bedding and Pipe Zone Backfill**

We recommend that pipe bedding and pipe zone in the trench be constructed with imported, well-graded crushed rock material, such as ¾-inch minus crushed aggregate base material. The material must be suitable for compaction and able to be worked under the curvature of the pipe. We recommend a minimum bedding thickness of 6 inches below the bottom of the pipe, or as determined by the pipeline designer. In areas where weak subgrade is encountered, a foundation stabilization layer should be placed below the bedding. Foundation stabilization is discussed in Section 7.3.6.

Above pipe bedding, imported crushed rock aggregate should be used for backfill within the pipe zone, which typically extends at least 12 inches above the top of the pipe, or as determined by the pipeline designer.

Pipe bedding and pipe zone backfill should be compacted to 90 percent of the maximum dry density, as determined by ASTM D1557, except the portion directly below the pipe that should be leveled without compaction. This will allow for uniform pressure distribution under the pipe invert.

### **7.3.5 CLSM Backfill**

Controlled Low Strength Material (CLSM) is commonly used as an alternative to granular fill bedding in portions of pipelines. CLSM fill mixtures are typically composed of a combination of cement, water, fine aggregate, and fly ash. The material is flowable and self-leveling, which greatly simplifies placement around pipelines. The material typically is specified to have unconfined compressive strength of 50 to 200 psi.

### **7.3.6 Foundation Stabilization**

Based on the subsurface explorations across the alignment, we anticipate competent subgrade conditions at the bottom of the trench. However, the subgrade soils can be disturbed if left exposed to water or general construction activities. If the subgrade becomes weakened or if soft/wet subgrade is encountered in localized areas due to perched groundwater, a foundation stabilization layer may be required.

To construct the foundation stabilization layer, the trench should be overexcavated a minimum 12 inches below the bottom of the bedding and replaced with the foundation stabilization layer. The foundation stabilization layer should consist of compacted, free-draining aggregate consisting of 1-½ to ¾- inch conforming with the requirements of OSSC 00430.11. Vibratory compaction equipment is not recommended due to risk of additional disturbance to the subgrade. A geotextile should be used below the aggregate as described in Section 7.3.7. The foundation stabilization backfill may also be used as the drainage layer for in-trench dewatering, as described in Section 7.3.6.

### **7.3.7 Geotextiles**

#### **7.3.7.1 Separation Geotextiles**

In general, the widespread use of separation geotextiles is not anticipated for the Project. However, they may be required in localized areas of trench seepage or for protection of subgrade, or in other areas identified during construction. They are not required for typical trench construction, however if used, separation geotextiles should consist of a “needle-punched”, non-woven separation fabric meeting the requirements for Type 1, nonwoven drainage geotextiles, as shown in Table 02320-1 in OSSC Section 02320.

#### **7.3.7.2 Reinforcement Geotextiles**

A reinforcement geotextile system should be installed beneath foundation stabilization backfill. We recommend a single-layer system consisting of a strong geotextile, such as Mirafi RS380i, that provides both separation/filtration and reinforcement. The reinforcement/separation geotextile should be installed on the base of the trench and extend up to the top of the foundation stabilization zone (below bedding) at a minimum. Reinforcement geotextiles should meet the requirements for Type 2, woven riprap geotextiles, as shown in Table 02320-2 in OSSC Section 02320.

### **7.3.8 Trench Backfill**

Trench backfill refers to the fill placed above the pipe zone. Where the pipeline is located below paved areas or structures, trench backfill should consist of pipe zone material, per Section 7.3.4. Trench backfill

beneath paved areas or structures should be placed in 12-inch maximum loose lifts and compacted to at least 92 percent of the maximum dry density, as determined by ASTM D1557. The trench backfill should be placed up to the design top-of-subgrade elevation associated with the final pavement section.

For areas outside of the roadways, trench backfill may consist re-processed asphalt and concrete debris, if used for this Project, or imported structural fill. Trench backfill in these areas should be compacted to 90 percent of maximum dry density, as determined by ASTM D1557. The upper 18 inches of the trench should be backfilled with topsoil to allow for vegetation regrowth.

## **7.4 Temporary Excavations**

All excavations should be in accordance with applicable OSHA and state regulations. It is the contractor's responsibility to select the excavation methods, to monitor site excavations for safety, and to provide any shoring required to protect personnel and nearby, existing structures. A competent person, as defined by Oregon OSHA, is an individual that can identify existing and predictable excavation-related hazards and has the authority to take prompt corrective measures to eliminate such hazards. McMillen Jacobs' Project role does not include review or oversight of excavation safety.

We anticipate the pipeline trenches will be on the order of 5 feet deep and excavated using a vertical shoring system. No information has been provided to date regarding the depth of other ancillary structures, such as vaults/manholes and pump stations. For the purposes of this report, we assume a maximum excavation depth of 10 feet. In the case that cut slopes are utilized for any excavations, the maximum slope inclinations must be in accordance with OSHA regulations. For use in the planning and construction of temporary excavations up to 10 feet in depth, an OSHA soil type of "B" can be used for the predominately fine-grained, near-surface residual soils encountered.

Temporary slope recommendations do not consider site constraints such as groundwater, surcharge, or nearby structures. Temporary slopes should be evaluated on a case-by-case basis and incorporate groundwater conditions, soil classification, and site constraints. Slopes should be inspected and maintained as required by OSHA.

With time and the presence of seepage and precipitation, the stability of temporary unsupported cut slopes can be significantly reduced. Therefore, temporary slopes kept open for construction activities should be protected from erosion by installing a surface water diversion ditch or berm at the top of the slope and covering the cut face with well-anchored plastic sheets. In addition, the contractor should monitor the stability of the temporary cut slopes and adjust the construction schedule and slope inclination accordingly. Maintenance of safe working conditions, including temporary excavation stability, is the responsibility of the contractor and all excavations must comply with current federal, state, and local requirements.

## **7.5 Groundwater Control**

Based on our groundwater measurements, we anticipate groundwater could be as shallow as 5 feet bgs. Based on their low hydraulic conductivity, the medium to high plasticity, fine-grained soils are not anticipated to produce large volumes of groundwater. Therefore, we anticipate that groundwater inflow

can be controlled with a well-constructed, sump pumping dewatering system. Sump pumps should be installed with close spacing to maintain water levels below the subgrade surface. In case that large volumes of water seepage are encountered, perforated drainpipes installed in drainage layers (i.e., crushed rock) may be necessary to convey water to the sump pump systems.

## **7.6 Wet Weather Earthwork**

The soils encountered within the project area are highly moisture sensitive and will degrade after being traversed by construction equipment during periods of wet weather or wet conditions. Therefore, during or after wet weather, it will likely be necessary to import granular materials for structural fill or to protect exposed subgrade materials. Delays in site earthwork activities should be anticipated during periods of heavy rainfall. If earthwork is performed during extended periods of wet weather or in wet conditions, we recommend the following:

- Cover the base of trenches within soil with trench stabilization material.
- Haul roads subjected to repeated, heavy, tire-mounted construction traffic (e.g., dump trucks, concrete trucks, etc.) will require a minimum of 18 inches of imported granular material to facilitate traffic. Additional granular material or geo-grid reinforcement may also be recommended based on site conditions at the time of construction.
- Excavations should be protected from surface water runoff by placing sandbags or by other means to direct runoff of precipitation away from work areas and to prevent ponding of water in excavations.
- Plastic covers, sloping, ditching, sumps, dewatering, and other measures should be employed in work areas as necessary to permit timely completion of work. Bales of straw and/or geotextile silt fences should be used to control surface soil movement and erosion.
- Excavations (specifically trench excavations) should be completed in small sections and backfilled at the end of each day to reduce exposure to wet conditions.
- Excavation or the removal of unsuitable soil should be followed promptly by placement and compaction of trench or foundation stabilization fill.
- The size and type of construction equipment used may have to be limited to minimize soil disturbance.

## 8.0 Closure

This report has been prepared for the exclusive use of the City of Salem and Murraysmith, in connection with the City of Salem – Improvements to the Aquifer Storage and Recovery Facility project. The data presented in this report is based on the subsurface conditions encountered during our site explorations and previous geotechnical exploration conducted nearby. The data presented herein is intended to support the design of the proposed improvements. McMillen Jacobs Associates is not responsible for the interpretation of the data contained in this report by anyone; as such interpretations are dependent on each person's subjectivity.

In the performance of geotechnical work, specific information is obtained at specific locations at specific times, and geologic conditions can change over time. It should be acknowledged that variations in soil conditions may exist between exploration and exposed locations and this report does not necessarily reflect variations between different explorations. The nature and extent of variation may not become evident until construction. If, during construction, conditions observed or encountered differ from those disclosed by this report, McMillen Jacobs Associates should be advised at once so we can observe and review these conditions and reconsider our recommendations where necessary.

The geotechnical engineering evaluations and interpretations included in this report are completed within the limitations of McMillen Jacobs Associates approved scope of work, schedule and budget. The services rendered by McMillen Jacobs Associates have been performed in a manner consistent with the level of care and skill ordinarily exercised by members of the profession currently practicing under similar conditions in the same area. The construction recommendations are considered preliminary and provided for planning purposes only. McMillen Jacobs Associates is not responsible for the use of this report in connection with anything other than the project at the location described above.

### MCMILLEN JACOBS ASSOCIATES

---

Yuxin “Wolfe” Lang, P.E., G.E.  
Principal Engineer

---

Jeff Quinn, P.E.  
Senior Project Engineer

## 9.0 References

- American Water Works Association (AWWA), 2004. Steel Pipe – A Guide for Design and Installation, Manual of Water Supply Practices, M11.
- American Society of Civil Engineers (ASCE), 2016. Minimum Design Loads for Buildings and other Structures. ASCE/SEI Standard 7-16.
- Atwater, B.F., 1992. Geologic evidence for earthquakes during the past 2,000 years along the Copalis River, southern coastal Washington: Journal of Geophysical Research, v. 97, p. 1901-1919.
- Bela, J.L., 1981. Geologic Map of the Rickreall, Salem West, Monmouth and Sidney Quadrangles, Marion, Polk and Linn Counties, Oregon. Geological Map Series GMS-18, Oregon Department of Geology and Mineral Industries, Salem, Oregon.
- Boulanger, R. W. and Idriss, I. M., 2014, CPT and SPT Based Liquefaction Triggering Procedures, Report No. UCD/CGM 14-01. Center for Geotechnical Modeling, Department of Civil and Environmental Engineering, UC Davis, April 2014.
- Cascadia Region Earthquake Workshop, 2008. Cascadia Deep Earthquakes. Washington Division of Geology and Earth Resources, Open File Report 2008-1.
- DeMets, C., Gordon, R.G., Argus, D.F., Stein, S., 1990. Current plate motions: Geophysical Journal International, v. 101.
- Foxworthy, B.L., 1970. *Hydrologic Conditions and Artificial Recharge Through a Well in the Salem Heights Area of Salem, Oregon*, Geological Survey Water-Supply Paper 1594-F, United States Department of the Interior Geological Survey, Washington, D.C.
- GeoDesign, 2018, *Report of SPT Hammer Energies – SPT Track and Truck Drill Rig Calibration, Western States Drill Rigs 1, 2, 4, 5, 7, and 8GP*, January 29, 2018, GeoDesign Project WSSC-8-02.
- Geomatrix Consultants, 1993. Seismic margin Earthquake For the Trojan Site: Final Unpublished Report For Portland General Electric Trojan Nuclear Plant, Rainier, Oregon, May 1993.
- Geomatrix Consultants, Inc., 1995, Seismic design mapping, State of Oregon: Technical report to Oregon Department of Transportation, Salem, Oregon, under Contract 11688, January 1995, unpaginated, 5 pls., scale 1:1,250,000.
- Idriss, I.M., and Boulanger, R.W., 2008, Soil liquefaction during earthquakes: Earthquake Engineering Research Institute, EERI MNO-12, Earthquake Engineering Institute, Oakland, California.
- Oregon Department of Geology and Mineral Industries, 2020. Oregon Statewide Hazards Viewer, accessed May 2020, from DOGAMI website: <https://gis.dogami.oregon.gov/maps/hazvu/>.
- Oregon Department of Transportation (ODOT), 2018. *Oregon Standard Specifications for Construction*.
- Oregon Water Resources Department, 2020. Well Log Records, accessed May 2020, from the OWRD website: [https://apps.wrd.state.or.us/apps/gw/well\\_log/Default.aspx](https://apps.wrd.state.or.us/apps/gw/well_log/Default.aspx).

Oregon HazVu, Oregon Department of Geology and Mineral Industries,: Statewide Geohazards Viewer, Interactive map, <https://gis.dogami.oregon.gov/maps/hazvu/>.

Pacific Northwest Seismic Network, 2020. Pacific Northwest Earthquake Sources Overview, accessed May 2020, from PNSN web site, <http://pnsn.org/outreach/earthquakesources/>.


Peterson, C.D., Darienzo, M.E., Burns, S.F., and Burris, W.K., 1993. Field trip guide to Cascadia paleoseismic evidence along the northern California coast: evidence of subduction zone seismicity in the central Cascadia margin. Oregon Department of Geology and Mineral Industries, Oregon Geology, Vol. 55, p. 99-144.

Spangler, M. G., 1941. *The Structural Design of Flexible Pipe Culverts*. Iowa Engineering Experiment Station Bulletin No. 153.

U.S. Geological Survey, 2020. U.S. Quaternary Faults Online Database, accessed May 2020, from USGS website: <https://usgs.maps.arcgis.com/apps/webappviewer/index.html?id=5a6038b3a1684561a9b0aaddf88412fcf>.

Wang, Y., and Leonard, W.J., 1996. *Relative Earthquake Hazard Maps of the Salem East and Salem West Quadrangles, Marion and Polk Counties, Oregon*, Geological Map Series GMS-105, Oregon Department of Geology and Mineral Industries, Salem, Oregon.

Wong, I. G., and Silva, W. J., 1998. Earthquake Ground Shaking Hazards in the Portland and Seattle Metropolitan Areas. American Society of Civil Engineering Geotechnical Special Publication ASCE, no. 75, Vol. 1, p. 66-78.



# PROJECT VICINITY MAP

SCALE: 1"=1MILE 0 1 MILE 2 MILES




## CITY OF SALEM IMPROVEMENTS TO THE ASR FACILITY


GEOTECHNICAL ENGINEERING REPORT  
PROJECT VICINITY MAP

FIG.1

MAY 2020




LATERAL EARTH PRESSURES ON EMBEDDED WALLS & STRUCTURES




- NOTES:
- 1. UNITS ARE POUNDS PER SQUARE FOOT (PSF).
  - 2. BACKFILL PRESSURES BASED ON IMPORTED CRUSHED ROCK.

RESTRAINED (NON-YIELDING) EMBEDDED WALLS & STRUCTURES



NON-RESTRAINED (YIELDING) EMBEDDED WALLS & STRUCTURES



























## **Appendix A**

### **Boring Logs**

## Key to Boring Logs - Soil

### UNIFIED SOIL CLASSIFICATION SYSTEM (USCS based on ASTM D2488)

MAJOR DIVISIONS			GROUP/SYMBOL		TYPICAL DESCRIPTION
COARSE-GRAINED SOILS (50% or more retained on No. 200 sieve)	GRAVELS (more than 50% retained on No. 4 sieve)	CLEAN GRAVELS (less than 5% fines)	GW		WELL-GRADED GRAVEL
			GP		POORLY GRADED GRAVEL
		GRAVELS (with 5 to 12% fines)	GW-GM		WELL-GRADED GRAVEL WITH SILT
			GW-GC		WELL-GRADED GRAVEL WITH CLAY
			GP-GM		POORLY GRADED GRAVEL WITH SILT
			GP-GC		POORLY GRADED GRAVEL WITH CLAY
		GRAVELS WITH FINES (more than 12% fines)	GM		SILTY GRAVEL
			GC		CLAYEY GRAVEL
	SANDS (less than 50% retained on No. 4 sieve)	CLEAN SANDS (less than 5% fines)	SW		WELL-GRADED SAND
			SP		POORLY GRADED SAND
		SANDS (with 5 to 12% fines)	SW-SM		WELL-GRADED SAND WITH SILT
			SW-SC		WELL-GRADED SAND WITH CLAY
			SP-SM		POORLY GRADED SAND WITH SILT
			SP-SC		POORLY GRADED SAND WITH CLAY
		SANDS WITH FINES (more than 12% fines)	SM		SILTY SAND
			SC		CLAYEY SAND
FINE-GRAINED SOILS (50% or more passes No. 200 sieve)	SILTS & CLAYS (liquid limit less than 50)	INORGANIC	ML		SILT
			CL		LEAN CLAY
		ORGANIC	OL		LOW PLASTICITY ORGANIC CLAY
	SILTS AND CLAYS (liquid limit greater than 50)	INORGANIC	MH		ELASTIC SILT
			CH		FAT CLAY
		ORGANIC	OH		HIGH PLASTICITY ORGANIC CLAY
	SILT/CLAY (liquid limit 12-25; PI 4-7)	INORGANIC	CL-ML		CLAYEY SILT/SILTY CLAY
HIGHLY ORGANIC SOILS	PRIMARILY ORGANIC MATTER	PT			PEAT

#### Note:

Dual symbols (symbols separated by a hyphen, e.g. SP-SM) are used for soils between 5% and 12% fines or when liquid limit and plasticity index values plot in the CL-ML area of the plasticity chart.

#### Coare-Grained Soils

Relative Density	N, SPT Blows/Foot
Very Loose	0 - 4
Loose	5 - 10
Medium Dense	11 - 30
Dense	31 - 50
Very Dense	> 50




#### Fine-Grained Soils

Relative Consistency	N, SPT Blows/Foot
Very Soft	< 2
Soft	2 - 4
Medium Stiff	5 - 8
Stiff	9 - 15
Very Stiff	16 - 30
Hard	> 30











### Abbreviations

AL	Atterberg Limit
MC	Moisture Content
SA	Sieve Analysis
LL	Liquid Limit
PL	Plastic Limit




### Sample Symbols

	SPT Sample 2" OD
	Shelby Tube Sample
	Grab Sample
N	Blows/ft

### Well and Backfill Symbols

	Bentonite Chips
	Concrete
	Sand
	Asphalt
	Gravel
	Grout
	Observation Well - Solid Interval
	Observation Well - Screened Interval
	Vibrating Wire Piezometer
	Measured groundwater level

### AL/MC Symbols

	Blows/Ft
	Moisture Content
	Liquid Limit/Plastic Limit

### Modifiers & Percentages

Trace	Component is present at less than 5% of the less than 3-inch portion.
Few (Sand or Gravel)	Coarse particles present at levels estimated at 6-10%.
With (Sand or Gravel)	Coarse particles present at levels estimated at 15-30%.
Sandy or Gravelly	Coarse particles present at levels estimated at 30-50%.

### Moisture Content

Dry	Absence of moisture, dusty, dry to the touch
Moist	Damp, but no visible water
Wet	Visible free water, usually soil is below water table

Project: City of Salem ASR Facility Improvements Project Location: Woodmansee Park Project Number: 6129.0						Log of Boring B-1						
Date(s) Drilled 04/06/2020		Geotechnical Consultant McMillen Jacobs Associates		Logged By A. Judy		Checked By J. Quinn						
Drilling Method/ Rig Type 8.25" Hollow Stem Auger/CME 55 Track Mounted		Drilling Contractor Western States Soil Conservation, Inc.		Total Depth of Borehole 51.5 ft								
Hole Diameter 8.25 in		Hammer Weight/Drop (lb/in.)/Type 140 lb / 30 in / Automatic		Ground Surface Elevation/Datum 380.0 ft								
Location West of center parking lot.		Coordinates 7544037.26E,455771.40N		Elevation Source Google Earth								
ELEV. (FT)	WATER LEVEL	DEPTH (FT)	SAMPLE TYPE	RECOVERY (%)	BLOW COUNTS	SAMPLE NUMBER	<div> <div> <div>□</div> <div>10 20 30 40</div> </div> <div> <div>○</div> <div>20 40 60 80</div> </div> </div> PENETRATION RESISTANCE BLOWS/FT WATER CONTENT (MC) ATTERBERG LL/PL	USCS GRAPHIC	USCS	MATERIAL DESCRIPTION	REMARKS AND TESTS	BACKFILL/INSTALL.
										Moist, dark brown, SILT (ML).	Topsoil thickness estimated from auger cuttings.	
375		5		93	2-4-7 (N=11)	S-1	<div> <div>□</div> <div>10 20 30 40</div> </div> <div> <div>○</div> <div>20 40 60 80</div> </div>		CH	Stiff, moist, red-brown, FAT CLAY (CH); medium plasticity, trace black and yellow mottles, with occasional fine-gravel-sized clasts of decomposed rock, relict rock fabric present. <b>Residual Soil of CRB</b>		
				80	3-5-5 (N=10)	S-2	<div> <div>□</div> <div>10 20 30 40</div> </div> <div> <div>○</div> <div>20 40 60 80</div> </div>					
				100	3-5-6 (N=11)	S-3	<div> <div>□</div> <div>10 20 30 40</div> </div> <div> <div>○</div> <div>20 40 60 80</div> </div>			Stiff, moist, red with light brown and yellow mottling, ELASTIC SILT (MH); high plasticity, with frequent fine to coarse gravel-sized highly weathered to decomposed rock, relict rock fabric present.		
370		10		100	3-4-4 (N=8)	S-4	<div> <div>□</div> <div>10 20 30 40</div> </div> <div> <div>○</div> <div>20 40 60 80</div> </div>			<b>Residual Soil of CRB</b> At 10 feet, grades to medium stiff, with black mottling.		
				100	1-1-2 (N=3)	S-5	<div> <div>□</div> <div>10 20 30 40</div> </div> <div> <div>○</div> <div>20 40 60 80</div> </div>			At 12.5 feet, grades to soft, medium plasticity, becomes wet.		
365		15		100	1-2-3 (N=5)	S-6	<div> <div>□</div> <div>10 20 30 40</div> </div> <div> <div>○</div> <div>20 40 60 80</div> </div>			At 15 feet, grades to medium stiff, color becomes red with light brown and black mottles.		
									MH			
360		20		100	2-4-6 (N=10)	S-7	<div> <div>□</div> <div>10 20 30 40</div> </div> <div> <div>○</div> <div>20 40 60 80</div> </div>			At 20 feet, grades to stiff, becomes red with trace black and yellow mottles, trace fine, moderately weathered gravel.		
355		25		100	1-0-2 (N=2)	S-8	<div> <div>□</div> <div>10 20 30 40</div> </div> <div> <div>○</div> <div>20 40 60 80</div> </div>			At 25 feet, grades to soft, color becomes light brown-gray with red mottles; interfingering with SILT to Sandy SILT (ML).	S-8 25 - 26.5 ft. 74% Fines by ASTM D1140.	

<b>Project: City of Salem ASR Facility Improvements</b> <b>Project Location: Woodmansee Park</b> <b>Project Number: 6129.0</b>						<b>Log of Boring B-1</b>						
Date(s) Drilled <b>04/06/2020</b>		Geotechnical Consultant <b>McMillen Jacobs Associates</b>		Logged By <b>A. Judy</b>		Checked By <b>J. Quinn</b>						
Drilling Method/Rig Type <b>8.25" Hollow Stem Auger/CME 55 Track Mounted</b>		Drilling Contractor <b>Western States Soil Conservation, Inc.</b>		Total Depth of Borehole <b>51.5 ft</b>								
Hole Diameter <b>8.25 in</b>		Hammer Weight/Drop (lb/in.)/Type <b>140 lb / 30 in / Automatic</b>		Ground Surface Elevation/Datum <b>380.0 ft</b>								
Location <b>West of center parking lot.</b>		Coordinates <b>7544037.26E,455771.40N</b>		Elevation Source <b>Google Earth</b>								
ELEV. (FT)	WATER LEVEL	DEPTH (FT)	SAMPLE TYPE	RECOVERY (%)	BLOW COUNTS	SAMPLE NUMBER	<input type="checkbox"/> PENETRATION RESISTANCE BLOWS/FT 10 20 30 40 <input type="checkbox"/> WATER CONTENT (MC) <input type="checkbox"/> ATTERBERG LL/PL 20 40 60 80	USCS GRAPHIC	USCS	MATERIAL DESCRIPTION	REMARKS AND TESTS	BACKFILL/INSTALL.
				100	8-10-12 (N=22)	S-9	<input type="checkbox"/>			Very stiff, moist, light brown with red-brown mottles, Gravelly SILT with sand (ML); non-plastic to low plasticity, coarse gravel-sized, subangular, highly weathered to decomposed rock, trace black mottles, relict rock fabric present. <b>Residual Soil of CRB</b>  <i>At 35 feet, becomes moist to wet; color becomes red-brown.</i>  <i>At 40 feet, grades to hard; becomes moist.</i>		
345	35			87	9-7-9 (N=16)	S-10	<input type="checkbox"/>					
340	40			100	16-15-22 (N=37)	S-11			ML			
335	45			100	19-27-26 (N=53)	S-12						
330	50			100	10-18-19 (N=37)	S-13						
325	55									Borehole completed at 51.5 feet below ground surface (bgs).		

**Project: City of Salem ASR Facility Improvements**  
**Project Location: Woodmansee Park**  
**Project Number: 6129.0**

**Log of Boring B-2**

Date(s) Drilled 04/06/2020	Geotechnical Consultant McMillen Jacobs Associates	Logged By A. Judy	Checked By J. Quinn
Drilling Method/ Rig Type Mud Rotary/CME 55 Track Mounted	Drilling Contractor Western States Soil Conservation, Inc.	Total Depth of Borehole 41.5 ft	
Hole Diameter 3.88 in	Hammer Weight/Drop (lb/in.)/Type 140 lb / 30 in / Automatic	Ground Surface Elevation/Datum 387.0 ft	
Location South of tennis courts.	Coordinates 7544108.04E,455515.67N	Elevation Source Google Earth	

ELEV. (FT)	WATER LEVEL	DEPTH (FT)	SAMPLE TYPE	RECOVERY (%)	BLOW COUNTS	SAMPLE NUMBER	<div> <div> <div>□ PENETRATION RESISTANCE BLOWS/FT</div> <div>10 20 30 40</div> </div> <div> <div>○ WATER CONTENT (MC)</div> <div>20 40 60 80</div> </div> <div> <div>▬ ATTERBERG LL/PL</div> <div>20 40 60 80</div> </div> </div>	USCS GRAPHIC	USCS	MATERIAL DESCRIPTION	REMARKS AND TESTS	BACKFILL/INSTALL.
										Soft, moist, dark brown, SILT (ML).	Topsoil thickness estimated from auger cuttings.	
382		5	▲	100	7-10-11 (N=21)	S-1	□ ○		ML	Very stiff, moist, red-brown with black mottles, SILT with sand (ML); non-plastic, trace fine to coarse-gravel-sized slightly weathered to fresh, subangular rock, fine sand, relict rock fabric present. <b>Residual Soil of CRB</b>  <i>At 5 feet, grades to stiff, becomes orange and wet.</i>		
			▲	100	8-4-10 (N=14)	S-2	□ ○			<i>At 7.5 feet, grades to Gravelly SILT with sand (ML); low plasticity, fine to coarse-gravel-sized, angular, highly weathered to decomposed rock, fine to coarse sand. becomes orange brown with black mottling.</i>		
377		10	▲	100	3-3-6 (N=9)	S-4	□ ○			<i>At 10 feet, grades to stiff, becomes moist to wet, trace black mottles present.</i>		
			▲	100	6-9-11 (N=20)	S-5	□ ○			<i>At 12.5 feet, grades to very stiff, becomes red-brown with gray mottling.</i>		
372		15	▲	100	5-4-5 (N=9)	S-6	□ ○			<i>At 15 feet, grades to stiff.</i>		
			▲	100	2-1-3 (N=4)	S-7	□ ○		MH	Stiff, moist, red-brown, ELASTIC SILT (MH); high plasticity, frequent decomposed rock fragments, relict rock fabric present. <b>Residual Soil of CRB</b>  <i>At 20 feet, grades to soft.</i>		
367		20	▲	100	3-5-8 (N=13)	S-8	□ ○			<i>At 25 feet, grades to stiff, medium plasticity; interfingered with non-plastic, light brown, SILT (ML).</i>		
362		25	▲	100								

Project: City of Salem ASR Facility Improvements Project Location: Woodmansee Park Project Number: 6129.0						Log of Boring B-2			
Date(s) Drilled 04/06/2020		Geotechnical Consultant McMillen Jacobs Associates		Logged By A. Judy		Checked By J. Quinn			
Drilling Method/ Rig Type Mud Rotary/CME 55 Track Mounted		Drilling Contractor Western States Soil Conservation, Inc.		Total Depth of Borehole 41.5 ft					
Hole Diameter 3.88 in		Hammer Weight/Drop (lb/in.)/Type 140 lb / 30 in / Automatic		Ground Surface Elevation/Datum 387.0 ft					
Location South of tennis courts.		Coordinates 7544108.04E,455515.67N		Elevation Source Google Earth					
ELEV. (FT)	WATER LEVEL	DEPTH (FT)	SAMPLE TYPE	RECOVERY (%)	BLOW COUNTS	SAMPLE NUMBER	<div><div><div><div><div></div><div>10</div></div><div><div>20</div><div>30</div><div>40</div></div></div><div><div><div></div><div>20</div></div><div><div>40</div><div>60</div><div>80</div></div></div></div><div><div><div></div><div>20</div></div><div><div>40</div><div>60</div><div>80</div></div></div></div> <div><div><div></div><div>20</div></div><div><div>40</div><div>60</div><div>80</div></div></div>		


USCS GRAPHIC

USCS

McMILLEN JACOBS ASSOCIATES

Boring B-2  
Sheet 2

Project: City of Salem ASR Facility Improvements Project Location: Woodmansee Park Project Number: 6129.0						Log of Boring B-3						
Date(s) Drilled 04/07/2020		Geotechnical Consultant McMillen Jacobs Associates		Logged By A. Judy		Checked By J. Quinn						
Drilling Method/ Rig Type Mud Rotary/CME 55 Track Mounted		Drilling Contractor Western States Soil Conservation, Inc.		Total Depth of Borehole 21.5 ft								
Hole Diameter 3.88 in		Hammer Weight/Drop (lb/in.)/Type 140 lb / 30 in / Automatic		Ground Surface Elevation/Datum 365.0 ft								
Location North edge of park.		Coordinates 7544549.01E,456338.17N		Elevation Source Google Earth								
ELEV. (FT)	WATER LEVEL	DEPTH (FT)	SAMPLE TYPE	RECOVERY (%)	BLOW COUNTS	SAMPLE NUMBER	<div> <div> <div>□</div> <div>10 20 30 40</div> </div> <div> <div>○</div> <div>20 40 60 80</div> </div> </div> PENETRATION RESISTANCE BLOWS/FT WATER CONTENT (MC) ATTERBERG LL/PL	USCS GRAPHIC	USCS	MATERIAL DESCRIPTION	REMARKS AND TESTS	BACKFILL/INSTALL.
									ML	Soft, moist, dark brown, SILT (ML).	Topsoil thickness estimated from auger cuttings.	
360		5		100	0-2-3 (N=5)	S-1	□ — ○ —		CL	Medium stiff, moist, brown to red-brown with black mottles, LEAN CLAY (CL); medium plasticity, relict rock fabric present. <b>Residual Soil of CRB</b>		
				100	3-6-6 (N=12)	S-2	□ ○			At 5 feet, grades to stiff, decomposed rock fabric apparent.	*Groundwater measured 15 minutes after drilling.*	
				100	3-5-4 (N=9)	S-3	□ ○			Stiff, moist, red-brown with black mottling, Gravelly SILT with sand (ML); low plasticity, fine to coarse gravel-sized, highly weathered to decomposed rock, fine sand, relict rock fabric present.		
355		10		100	3-7-9 (N=16)	S-4	□ ○			<b>Residual Soil of CRB</b> At 8 feet, color becomes red. At 10 feet, grades to very stiff, becomes wet, color becomes brown with gray and orange mottling.		
				100	6-9-13 (N=22)	S-5	□ ○			At 12.5 feet, moderately weathered gravel with 3-inch zone of FAT CLAY (CH).		
350		15		100	8-14-20 (N=34)	S-6	○ □		ML	At 15 feet, grades to hard.		
345		20		100	9-12-20 (N=32)	S-7	□			At 20 feet, color becomes brown with black and red mottling.		
340		25									Borehole completed at 21.5 feet below ground surface (bgs).	



Boring B-3

Sheet 1



<b>Project: City of Salem ASR Facility Improvements</b> <b>Project Location: Woodmansee Park</b> <b>Project Number: 6129.0</b>						<b>Log of Boring B-4</b>						
Date(s) Drilled <b>04/07/2020</b>		Geotechnical Consultant <b>McMillen Jacobs Associates</b>		Logged By <b>A. Judy</b>		Checked By <b>J. Quinn</b>						
Drilling Method/Rig Type <b>Mud Rotary/CME 55 Track Mounted</b>		Drilling Contractor <b>Western States Soil Conservation, Inc.</b>		Total Depth of Borehole <b>41.5 ft</b>								
Hole Diameter <b>3.88 in</b>		Hammer Weight/Drop (lb/in.)/Type <b>140 lb / 30 in / Automatic</b>		Ground Surface Elevation/Datum <b>415.0 ft</b>								
Location <b>Northwest of gate.</b>		Coordinates <b>7544530.12E,456124.66N</b>		Elevation Source <b>Google Earth</b>								
ELEV. (FT)	WATER LEVEL	DEPTH (FT)	SAMPLE TYPE	RECOVERY (%)	BLOW COUNTS	SAMPLE NUMBER	<input type="checkbox"/> PENETRATION RESISTANCE BLOWS/FT 10 20 30 40 <input type="checkbox"/> WATER CONTENT (MC) <input type="checkbox"/> ATTERBERG LL/PL 20 40 60 80	USCS GRAPHIC	USCS	MATERIAL DESCRIPTION	REMARKS AND TESTS	BACKFILL/INSTALL.
380	35	100	7-8-13 (N=21)	100	S-9	<input type="checkbox"/> <input type="checkbox"/>			ML	Very stiff, moist, red-brown with black and gray mottles, Sandy SILT (ML); non-plastic, fine sand, relict rock fabric present. <b>Residual Soil of CRB</b> <i>At 30 feet, grades to Sandy SILT (ML); fine sand. Becomes red-brown with black and gray mottles.</i>		
375	40	100	7-11-16 (N=27)	100	S-10	<input type="checkbox"/>				<i>Below 35 feet, grades to Gravelly Sandy SILT (ML); fine to coarse, angular, highly weathered to decomposed gravel.</i>		
		100	13-20-19 (N=39)	100	S-11	<input type="checkbox"/>				<i>At 40 feet, grades to hard, becomes orange with black mottling.</i>		
370	45										Borehole completed at 41.5 feet below ground surface (bgs).	
365	50											
360	55											

## **Appendix B**

### **Laboratory Test Results**

<b>Breccia Geotechnical Testing, LLC.</b>		<b>Natural Moisture Content (ASTM D2216)</b>	
Client:	<u>McMillen Jacobs Associates</u>	By:	<u>JF</u>
Project Name:	<u>Improvements to the ASR Facility</u>	Date:	<u>4/29/2020</u>
Project Number:	<u>6129.0</u>		

Exploration ID	B-1	B-1	B-1	B-1	B-1	B-1
Samples ID	S-1	S-2	S-3	S-4	S-5	S-6
Samples Depth (ft.)	2.5-4	5-6.5	7.5-9	10-11.5	12.5-14	15-16.5
Moisture Content (%)	33.1	36.0	61.1	63.0	75.4	66.4

Exploration ID	B-1	B-1	B-1	B-2	B-2	B-2
Samples ID	S-7	S-9	S-10	S-1	S-2	S-3
Samples Depth (ft.)	20-21.5	30-31.5	35-36.5	2.5-4	5-6.5	7.5-9
Moisture Content (%)	59.7	51.8	54.4	52.5	66.3	46.2

Exploration ID	B-2	B-2	B-2	B-2	B-2	B-2
Samples ID	S-4	S-5	S-6b	S-7	S-8	S-9
Samples Depth (ft.)	10-11.5	12.5-14	15.5-16	20-21.5	25-26.5	30-31.5
Moisture Content (%)	59.5	54.7	82.8	71.5	71.4	72.4

Exploration ID	B-2	B-3	B-3	B-3	B-3	B-3
Samples ID	S-11	S-1	S-2	S-3b	S-4	S-5
Samples Depth (ft.)	40-41.5	2.5-4	5-6.5	8-9	10-11.5	12.5-14
Moisture Content (%)	49.7	32.9	37.6	65.9	63.5	61.0


Exploration ID	B-3	B-4	B-4	B-4	B-4	B-4
Samples ID	S-6	S-1	S-2	S-3	S-4	S-5
Samples Depth (ft.)	15-16.5	2.5-4	5-6.5	7.5-9	10-11.5	12.5-14
Moisture Content (%)	51.5	38.0	39.9	37.3	31.8	63.8

Exploration ID	B-4	B-4	B-4			
Samples ID	S-6	S-8	S-9			
Samples Depth (ft.)	15-16.5	25-26.5	30-31.5			
Moisture Content (%)	64.7	55.6	53.9			

<b>Breccia Geotechnical Testing, LLC.</b>		<b>Percent Fines (ASTM D1140)</b>	
Client:	<u>McMillen Jacobs Associates</u>	By:	<u>JF</u>
Project Name:	<u>Improvements to the ASR Facility</u>	Date:	<u>4/29/2020</u>
Project Number:	6129.0		

Exploration ID	B-1	B-2	B-4			
Samples ID	S-8	S-10	S-7			
Samples Depth (ft.)	25-26.5	35-36.5	20-21.5			
Moisture Content (%)	76.0	57.3	55.0			
Percent Fines (%)	74.0	50.4	57.9			

## ATTERBERG LIMITS TEST RESULTS (ASTM D4318)



	Boring	Sample ID	Depth (feet)	Moisture Content (%)	Atterberg Limits			%Pass #200	USCS
					LL	PL	PI		
◆	B-1	S-1	2.5-4	33.1	54	29	25	--	CH
▲	B-1	S-3	7.5-9	61.1	112	66	46	--	MH
●	B-1	S-6	15-16.5	66.4	79	52	27	--	MH
■	B-2	S-6b	15.5-16	82.8	110	59	51	--	MH
◇	B-3	S-1	2.5-4	32.9	48	24	24	--	CL
△	B-4	S-2	5-6.5	39.9	59	35	24	--	MH
○	B-4	S-5	12.5-14	63.8	73	49	24	--	MH

### Remarks

**Project:** Improvements to the ASR Facility  
**Project No.:** 6129.0  
**Location:** Salem, OR

**Breccia Geotechnical Testing, LLC.**

Brecciageolab@gmail.com

Tel: 971-246-1324



# Shrink-Swell / Expansion Pressure ASTM D 3877m


Job No.: 024-039  
 Client: McMillen Jacobs  
 Project: City of Salem ASR Improvements  
 Boring: B-1 Sample: S-1 & S-2 Depth, ft: 2.5-6.5  
 Soil Desc. Reddish Brown CLAY  
 LL: \_\_\_\_\_ PL: \_\_\_\_\_ PI: \_\_\_\_\_  
 Date: 5/19/2020 By: PJ  
 Checked By: PJ Assumed Determined  
 Specific Gravity: 2.85

Load, psf:	7381	3600	1800	900	450	100
Exp., %	0.00	0.23	0.53	0.75	0.93	1.32


	Field	Inundated	Air-Dry	Oven-Dry
Moisture %:	6.5	32.7	7.3	0.0
Dry Density, pcf	92.7	91.5	95.0	96.4
Saturation, %	20.1	98.6	23.8	0.0
Void Ratio	0.920	0.946	0.875	0.848
Volume Change, %	0.0	1.3	-2.4	-3.8

Remarks:  
This sample was remolded in an air-dried moisture content to approximate a field density.

## Load - Expansion Curve (loaded then expanded)



## Volume Change





# Shrink-Swell / Expansion Pressure ASTM D 3877m

Job No.: 024-039      LL: \_\_\_\_\_      Date: 5/18/2020  
 Client: McMillen Jacobs      PL: \_\_\_\_\_      By: PJ  
 Project: City of Salem ASR Improvements      PI: \_\_\_\_\_      Checked By: PJ      Assumed      Determined  
 Boring: B-1      Sample: S-3 & S-4      Depth, ft: 7.5-11.5      Specific Gravity: 2.8


Soil Desc. Red SILT

Load, psf: 100


Exp., % -0.30

	Field	Inundated	Air-Dry	Oven-Dry	Remarks:
Moisture %:	59.3	59.9	11.5	0.0	This sample was remolded at the as-received moisture content to approximate a field density. This sample did not swell. It consolidated slightly at 100 psf.
Dry Density, pcf	65.0	65.2	86.4	88.0	
Saturation, %	98.3	99.7	31.4	0.0	
Void Ratio	1.689	1.681	1.024	0.987	
Volume Change, %	0.0	-0.3	-24.7	-26.1	

Load - Expansion Curve (loaded then expanded)



Volume Change





# Shrink-Swell / Expansion Pressure ASTM D 3877m

Job No.: 024-039      LL: \_\_\_\_\_      Date: 5/18/2020  
 Client: McMillen Jacobs      PL: \_\_\_\_\_      By: PJ  
 Project: City of Salem ASR Improvements      PI: \_\_\_\_\_      Checked By: PJ      Assumed      Determined  
 Boring: B-4      Sample: S-1 & S-2      Depth, ft: 2.5-6.35      Specific Gravity: 2.8


Soil Desc. Strong Brown SILT

Load, psf: 100

Exp., % -0.39

	Field	Inundated	Air-Dry	Oven-Dry	Remarks:
Moisture %:	39.9	40.2	7.3	0.0	This sample was remolded at the as-received moisture content to approximate a field density. This sample did not swell. It consolidated slightly at 100 psf.
Dry Density, pcf	81.6	81.9	95.8	97.9	
Saturation, %	97.6	99.2	24.7	0.0	
Void Ratio	1.144	1.135	0.827	0.787	
Volume Change, %	0.0	-0.4	-14.8	-16.6	

Load - Expansion Curve (loaded then expanded)



Volume Change

