STORMWATER CALCULATIONS

Prepared For:

Scott Martin Construction, Inc.

PO Box 5850

Salem, OR 97304

Project Location:

Riverbend Road Site Phase II 2499 Wallace Rd NW

Salem, OR 97304

Prepared By:



RENEWS: 6/30/2022



Westech Engineering, Inc. 3841 Fairview Industrial Drive SE, Suite 100 Salem, OR 97302 (503) 585-2474 FAX: (503) 585-3986

J.O. 3168.3000.0

TABLE OF CONTENTS

Chap	pter P	age
1	Project Overview & Description	1-1
1.1	Size & Location of Project	1-1
1.2	Brief description of project scope and proposed improvements	1-1
1.3	Description of Size of Watershed Draining to the Site	1-1
1.4 Sensi	Description of the Existing Site Conditions, Constraints, Trees & Native Vegetation, tive Areas & Waterways	1-1
1.5	Summary of Green Stormwater Infrastructure	1-1
1.6	Regulatory Permits Required	1-1
1.7	100-Year Emergency Storm Escape Routes	1-2
2	Methodology	2-1
2.1	Depth to Groundwater	2-1
2.2	Maximum Infiltration and Vegetative Treatment	2-1
2.3	Soil Information	2-1
2.4	Hazardous Material	2-1
3	Analysis	3-1
3.1	Methods & Software Used	3-1
3.2	Curve Number and Time of Concentration Calculations	3-1
3.3	Treatment & Flow Control Sizing Calculations	3-2
3.4	Conveyance Capacity Calculations	3-4
3.5	Summary	3-4

LIST OF TABLES

Table	Page
Table 1 City of Salem 24-hour Design Storms	3-1
Table 2 General Basin Characteristics	3-2
Table 3 Vegetated Swale Design	3-3
Table 4 Facility Outlet Sizing and Release Rates	3-4

APPENDICES

Appendix A	Basin Maps
Appendix B	NRCS Soil Report
Appendix C	HydroCAD Summaries
Appendix D	Geotechnical Report

PROJECT OVERVIEW & DESCRIPTION

1.1 SIZE & LOCATION OF PROJECT

The proposed project is the second phase of the Riverbend Road Site project and sits on 8-acres located at 2499 Wallace Rd NW in Salem, Oregon. Refer to the Civil Drawings for a site map of the project area.

1.2 BRIEF DESCRIPTION OF PROJECT SCOPE AND PROPOSED IMPROVEMENTS

The project scope is to develop the property for multi-family housing consisting of 177 units, indoor recreation facilities, and an office. The project includes site preparation, construction of the facilities, and associated improvements.

1.3 DESCRIPTION OF SIZE OF WATERSHED DRAINING TO THE SITE

A drainage area of 6.84 acres from the site drains to the proposed stormwater facilities including an existing roadway at the southeast corner that connects to the first phase of the project. Some perimeter landscaping will not drain to the proposed stormwater facilities. Refer to the Developed Basin Map in Appendix A and the Civil Drawings for more details.

1.4 DESCRIPTION OF THE EXISTING SITE CONDITIONS, CONSTRAINTS, TREES & NATIVE VEGETATION, SENSITIVE AREAS & WATERWAYS

The existing site contains several rural residential lots predominately covered in grass with a few shrubs and trees located throughout. No other existing sensitive areas, waterways, etc. exist on-site.

1.5 SUMMARY OF GREEN STORMWATER INFRASTRUCTURE

Per Appendix 4E of the City of Salem (COS) Design Standards, a large project will be considered to have met the maximum extent feasible (MEF) requirement when the stormwater runoff from the total amount of new plus replaced impervious surfaces flows into an area set aside for GSI that is at least 10% of the total area of the new plus replaced impervious surfaces or at least 80% of all impervious area must be treated by GSI. The design implements GSI for the entire site and therefore meets MEF for GSI. See the Civil Drawings for more details.

1.6 REGULATORY PERMITS REQUIRED

A 1200-C permit from DEQ will be required since more than one acre is disturbed by the project. City of Salem permits are required. No other permits are required for this project.

1.7 100-YEAR EMERGENCY STORM ESCAPE ROUTES

Please refer to the Developed Basin Map in Appendix A for emergency overflow routes.

2.1 DEPTH TO GROUNDWATER

The proposed stormwater design does not implement infiltration facilities and therefore depth to groundwater is not applicable. However, groundwater is predicted to be as shallow as 10-12 feet below ground surface per the Geotechnical Report in Appendix A. No groundwater was encountered during testing with test pits dug up to 21 feet below ground surface.

2.2 MAXIMUM INFILTRATION AND VEGETATIVE TREATMENT

Measured infiltration rates onsite were zero or nearly zero per the Geotechnical Report. Therefore infiltration facilities are not included in the stormwater design. The proposed stormwater design will treat and detain the entire site with vegetated swales and a dry detention basin. Since stormwater from the entire site will be treated via GSI facilities, GSI has been implemented to the maximum extent feasible.

2.3 SOIL INFORMATION

The pre-developed project site contains approximately 50% hydrologic soil group C soils and 50% group C/D soils. Per the NRCS Soil Report, a C/D classification indicates a D rating for natural soil conditions. Soils for 50% of the pre-developed and developed site are assumed D-rated. Refer to the NRCS Soils Report in Appendix B for more details.

2.4 HAZARDOUS MATERIAL

The owner is not aware of any hazardous material contamination onsite.

3.1 METHODS & SOFTWARE USED

HydroCAD modeling software was used to size the stormwater facilities. The Santa Barbara Unit Hydrograph Type 1A storm was used to model the required design storms. Per the City of Salem (COS) Design Standards the design storms used were the 1.38 inch, 24-hour (water quality storm), half the 2-year, 24-hour, the 10-year, 24-hour, the 25-year, 24-hour, and the 100-year, 24-hour storm events.

		24-Ho	ur Rainfa	all Depth:	s for Sale	em, OR	
Recurrence Interval, Years	WQ	2	5	10	25	50	100
24-Hour Depths, Inches	1.38	2.2	2.7	3.2	3.6	4.1	4.4

Source: City of Salem Administrative Rules Chapter 109 – Division 004 Appendix D

3.2 CURVE NUMBER AND TIME OF CONCENTRATION CALCULATIONS

Per the COS Design Standards, the pre-developed site is considered to be covered in a combination of woods and good-grass, which corresponds to a pre-developed curve number of 72 and 79 for hydrologic soil group C and D-rated soils, respectively.

The developed impervious areas were assigned a curve number of 98 which corresponds to paved/parking and roof areas. The pervious areas were assigned curve numbers of 74 and 80 which corresponds to open space with C and D-rated soils, respectively, per the City of Salem Design Standards.

Time of concentration (Tc) for the pre-developed conditions was calculated using sheet and shallow concentrated flow equations to be 40.8 minutes. See the Pre-Developed Basin Map in Appendix A for the flow path used and refer to the HydroCAD Summaries in Appendix C for calculations. A minimum time of concentration of 5 minutes is applied to the developed basins due to the minimum time-step used by the HydroCAD modeling software.

3.3 TREATMENT & FLOW CONTROL SIZING CALCULATIONS

The project site was analyzed as one basin for pre-developed conditions and two basins for developed stormwater runoff calculations. General basin characteristics of predeveloped and developed conditions are listed in Table 2 below. For more detail refer to the Basin Maps in Appendix A and the Civil Drawings.

	Source	Impervious	Pervious	Design Storms (cfs)				
Basin ID	(Roof/ Road/ Other)	Area (ac)	Area (ac)	½ 2 Yr	10 Yr	25 Yr	100 Yr	CN ¹
Predeveloped Basin								
PD ²	Native	-	6.84	0.14	0.89	1.20	1.88	76
Developed Basins								
Basin 1	Paved/ Roof/ Landscape	1.60	0.40	0.37	1.29	1.48	1.85	94
Basin 2	Road/ Landscape	3.08	1.76	0.71	2.72	3.15	4.04	90

Table 2 | General Basin Characteristics

¹ Area-weighted curve number (CN).

² PD = pre-developed site conditions (i.e., pre-developed release rates)

Two vegetated swales at the bottom of a dry detention basin are proposed to treat and detain the runoff from the site. Swale 1 will treat Basin 1, and Swale 2 will treat Basin 2. Both swales are part of the same detention basin. The detention basin has a lower section to detain the half 2-year storm event.

Table 3 compares the designed and allowable swale parameters during the water quality and conveyance storms for Swale 1 and Swale 2. Per the Design Standards, a Manning's "n" of 0.25 was used to design treatment of the water quality storm. Refer to the Civil Drawings and HydroCAD calculations for more details.

COS Design Standards	Swala 1	Swalo 2	
Criteria	Allowable	Swale I	Swale 2
Manning's n – Water Quality	0.25	0.25	0.25
Maximum Water Quality Flow Depth (ft)	0.33	0.30	0.33
Maximum Water Quality Flow Velocity (fps)	0.90	0.17	0.21
Min hydraulic Residence Time (min)	9	9.8	9.1
Manning's n – Conveyance (100-yr)	0.03	0.03	0.03
Max. Conveyance Flow Depth (ft)	1.0	0.19	0.23
Max. Conveyance Flow Velocity (fps)	3.0	1.12	1.39
Min Length (ft)	100	100	115
Side Slope (ft:ft)	3:1	3:1	3:1
Longitudinal Slope (%)	-	0.5	0.6
Bottom Width (ft)	-	8	12

 Table 3 | Vegetated Swale Design

The design meets or exceeds all the allowed values in Section 4.4 of the COS Design Standards. The calculations in Table 3 above assumes free discharge from the swales which may not be the case during larger storms due to flow-control requirements. As shown in Table 4 below, the proposed flow-control design results in a water surface elevation of 146.59 feet reached in the water quality storm. This is 0.09-feet (1-inch) above the downstream finish grade of both swales (146.5-feet) and therefore meets the 4-inch maximum depth for vegetated swales in the water quality storm per the COS Design Standards.

Stormwater release from the detention basin facility is controlled by a flow-control manhole. See Table 4 below for a summary of facility outlet sizing and release rates. The 100-year storm is released by a 12-inch overflow riser in the flow-control manhole. An emergency overflow weir is provided along the east edge of the detention basin. Refer to the Developed Basin Map in Appendix A and the Civil Drawings for more details.

Outlet ID/ Storm Event	Orifice Size (in)	Orifice Elevation (ft)	Release Rate (cfs)	Allowed Release (cfs)	Peak WSE ¹ (ft)	Emergency Overflow Elevation (ft)
½ - 2 Year	1.9	144.20	0.14	0.14	146.42	149.0
WQ Event	-	-	0.26	-	146.59	149.0
10 Year	5.0	146.50	0.84	0.89	147.52	149.0
25 Year	8.0 ²	147.60	0.98	1.20	147.71	149.0
100 Year	12.0 ³	147.80	1.76	1.88	147.92	149.0

Table 4 | Facility Outlet Sizing and Release Rates

¹ WSE = water surface elevation

²25-year storm controlled by 8.0-inch wide weir cut from top of riser tee.

³ 100-year storm controlled by 12-inch internal overflow riser.

3.4 CONVEYANCE CAPACITY CALCULATIONS

The stormwater facilities were designed to convey the developed 100-year, 24-hour storm, which has a peak flow of 1.76 cfs released from the flow control manhole. Stormwater runoff is conveyed by 12-inch pipe from the flow-control structure to a 12-inch public storm drain in Wallace Rd. See the Civil Drawings for more detail. The 12-inch pipe has a full-flow capacity of 7.99 cfs using a slope of 5.0% and Manning's n of 0.013, which exceeds the peak release rate from the stormwater facilities.

3.5 SUMMARY

The stormwater system has been designed to release half the 2-year, 24-hour, the 10-year, 24-hour, 25-year, 24-hour, and the 100-year, 24-hour storm events at rates less than their respective pre-developed storm. The proposed design also treats the water quality storm. Therefore, the project meets the flow control and treatment requirements as set forth in Administrative Rule 109 Division 004 - Stormwater System.

RIVERBEND ROAD SITE PHASE II Stormwater Calculations Salem, Oregon

> APPENDIX A BASIN MAPS







/2021 2:01:54 PM vg\Martin, Scott\Riverbend Rd Phase II\Civil\Plots\zDeveloped Basin Map.dwg, (Layout1 -



RIVERBEND ROAD SITE PHASE II Stormwater Calculations Salem, Oregon

APPENDIX B NRCS SOIL REPORT



USDA Natural Resources

Conservation Service

7/6/2021 Page 1 of 4



Hydrologic Soil Group

Map unit symbol	Map unit name	Rating	Acres in AOI	Percent of AOI	
3	Amity silt loam	C/D	4.7	56.6%	
77A Woodburn silt loam, 0 to 3 percent slopes		С	3.6	43.4%	
Totals for Area of Intere	st	8.3	100.0%		

Description

Hydrologic soil groups are based on estimates of runoff potential. Soils are assigned to one of four groups according to the rate of water infiltration when the soils are not protected by vegetation, are thoroughly wet, and receive precipitation from long-duration storms.

The soils in the United States are assigned to four groups (A, B, C, and D) and three dual classes (A/D, B/D, and C/D). The groups are defined as follows:

Group A. Soils having a high infiltration rate (low runoff potential) when thoroughly wet. These consist mainly of deep, well drained to excessively drained sands or gravelly sands. These soils have a high rate of water transmission.

Group B. Soils having a moderate infiltration rate when thoroughly wet. These consist chiefly of moderately deep or deep, moderately well drained or well drained soils that have moderately fine texture to moderately coarse texture. These soils have a moderate rate of water transmission.

Group C. Soils having a slow infiltration rate when thoroughly wet. These consist chiefly of soils having a layer that impedes the downward movement of water or soils of moderately fine texture or fine texture. These soils have a slow rate of water transmission.

Group D. Soils having a very slow infiltration rate (high runoff potential) when thoroughly wet. These consist chiefly of clays that have a high shrink-swell potential, soils that have a high water table, soils that have a claypan or clay layer at or near the surface, and soils that are shallow over nearly impervious material. These soils have a very slow rate of water transmission.

If a soil is assigned to a dual hydrologic group (A/D, B/D, or C/D), the first letter is for drained areas and the second is for undrained areas. Only the soils that in their natural condition are in group D are assigned to dual classes.

Rating Options

Aggregation Method: Dominant Condition

USDA

Component Percent Cutoff: None Specified Tie-break Rule: Higher



RIVERBEND ROAD SITE PHASE II Stormwater Calculations Salem, Oregon

APPENDIX C

HYDROCAD SUMMARIES



Runoff = 0.28 cfs @ 8.93 hrs, Volume= 0.297 af, Depth= 0.52" Routed to nonexistent node 25L

Runoff by SBUH method, Split Pervious/Imperv., Time Span= 0.50-120.00 hrs, dt= 0.05 hrs Type IA 24-hr Salem 2 YR Rainfall=2.20"

	Area	(ac) (CN Des	cription			
*	3.	420	72 Sale	em Pre-Dev	/eloped, HS	SG C	
*	3.	420	79 Sale	m Pre-Dev	/eloped, HS	SG D	
	6.	840	76 Wei	ghted Aver	age		
6.840 100.00% Pervious Area							
	Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description	
	37.5	300	0.0400	0.13		Sheet Flow, Predeveloped n= 0.300 P2= 2.20"	
	3.3	200	0.0400	1.00		Shallow Concentrated Flow, Woodland Kv= 5.0 fps	
	40.8	500	Total				



8.26 hrs, Volume= 0.657 af, Depth= 1.15" Runoff 0.89 cfs @ Routed to nonexistent node 25L

Runoff by SBUH method, Split Pervious/Imperv., Time Span= 0.50-120.00 hrs, dt= 0.05 hrs Type IA 24-hr Salem 10 YR Rainfall=3.20"

	Area	(ac) (CN Des	cription			
*	3.	420	72 Sale	em Pre-Dev	veloped, HS	SG C	
*	3.	420	79 Sale	em Pre-Dev	veloped, HS	SG D	
6.840 76 Weighted Average							
	6.	840	100	.00% Pervi	ous Area		
	Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description	
	37.5	300	0.0400	0.13		Sheet Flow, Predeveloped n= 0.300 P2= 2.20"	
	3.3	200	0.0400	1.00		Shallow Concentrated Flow, Woodland Kv= 5.0 fps	
	40.8	500	Total				



1.20 cfs @ 8.22 hrs, Volume= 0.820 af, Depth= 1.44" Runoff = Routed to nonexistent node 25L

Runoff by SBUH method, Split Pervious/Imperv., Time Span= 0.50-120.00 hrs, dt= 0.05 hrs Type IA 24-hr Salem 25 YR Rainfall=3.60"

	Area	(ac) (CN Des	cription			
*	3.	420	72 Sale	em Pre-Dev	veloped, HS	SG C	
*	3.	420	79 Sale	em Pre-Dev	veloped, HS	SG D	
_	6.	840	76 Wei	ghted Aver	age		
	6.	840	100	.00% Pervi	ous Area		
	Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description	
	37.5	300	0.0400	0.13		Sheet Flow, Predeveloped n= 0.300 P2= 2.20"	
	3.3	200	0.0400	1.00		Shallow Concentrated Flow, Woodland Kv= 5.0 fps	
	40.8	500	Total				



1.88 cfs @ 8.18 hrs, Volume= 1.169 af, Depth= 2.05" Runoff = Routed to nonexistent node 25L

Runoff by SBUH method, Split Pervious/Imperv., Time Span= 0.50-120.00 hrs, dt= 0.05 hrs Type IA 24-hr Salem 100 YR Rainfall=4.40"

	Area	(ac)	CN De	scription						
*	3.	420	72 Sa	lem Pre-De	veloped, HS	SG C				
*	3.	420	79 Sa	lem Pre-De	veloped, HS	SG D				
_	6.	840	76 We	eighted Ave						
6.840			10	100.00% Pervious Area						
	Tc (min)	Length (feet)	slope) (ft/ft	e Velocity) (ft/sec)	Capacity (cfs)	Description				
	37.5	300	0.0400	0.13		Sheet Flow, Predeveloped n= 0.300 P2= 2.20"				
	3.3	200	0.0400	0 1.00		Shallow Concentrated Flow, Woodland Kv= 5.0 fps				
	40.8	500	Total							



Hydrograph

Summary for Subcatchment 1B: Basin 1

Runoff = 0.37 cfs @ 7.92 hrs, Volume= 0.121 af, Depth= 0.72" Routed to Pond 3P : Detention Basin

Runoff by SBUH method, Split Pervious/Imperv., Time Span= 0.50-120.00 hrs, dt= 0.05 hrs Type IA 24-hr Salem 1/2 2 YR Rainfall=1.10"

_	Area (ac)	CN	Desc	ription			
*	1.6	600	98	Pave	ed parking	& roof, HS	G D	
*	0.2	200	74	Oper	ו Space, וׂ	ISG C		
*	0.2	200	80	Oper	n Space, ⊦	ISG D		
	2.0	000	94	Weig	hted Aver	age		
	0.4	.400 20.00% Pervious Area						
	1.6	1.600 80.00% Impervious Area				vious Area		
	Та	Langet	h.	Clana	Valacity	Conositu	Description	
		Lengt	n	Siope	velocity	Capacity	Description	
	(min)	(fee	[)	(π/ft)	(III/SeC)	(CIS)		
	5.0						Direct Entry.	

Subcatchment 1B: Basin 1



Summary for Subcatchment 2B: Basin 2

7.92 hrs, Volume= 0.239 af, Depth= 0.59" Runoff 0.71 cfs @ = Routed to Pond 3P : Detention Basin

Runoff by SBUH method, Split Pervious/Imperv., Time Span= 0.50-120.00 hrs, dt= 0.05 hrs Type IA 24-hr Salem 1/2 2 YR Rainfall=1.10"

	Area ((ac)	CN	Desc	ription			
*	3.0	080	98	Pave	d parking	& roof, HS	G D	
*	0.8	880	74	Oper	n Śpace, ŀ	ISG C		
*	0.0	880	80	Oper	n Space, F	ISG D		
	4.8	840	90	Weig	hted Aver	age		
	1.7	760		36.36	5% Pervio	us Area		
	3.0	080		63.64	4% Imperv	vious Area		
	Тс	Lengt	h :	Slope	Velocity	Capacity	Description	
_	(min)	(feet	:)	(ft/ft)	(ft/sec)	(cfs)		
	50						Direct Entry	



pirect Entry,

Subcatchment 2B: Basin 2



Summary for Pond 3P: Detention Basin

Inflow Area	a =	6.840 ac, 6	8.42% Impe	ervious,	Inflow De	pth =	0.63	3" for	Salem	1/2 2 `	YR event
Inflow	=	1.08 cfs @	7.92 hrs,	Volume	=	0.359	af				
Outflow	=	0.14 cfs @	19.77 hrs,	Volume	=	0.359	af, /	Atten= 8	37%, L	.ag= 71	1.1 min
Primary	=	0.14 cfs @	19.77 hrs,	Volume	=	0.359	af			•	
Routed	to none>	kistent node 2	23L								

Routing by Stor-Ind method, Time Span= 0.50-120.00 hrs, dt= 0.05 hrs Peak Elev= 146.42' @ 19.77 hrs Surf.Area= 7,403 sf Storage= 6,590 cf

Plug-Flow detention time= 567.8 min calculated for 0.359 af (100% of inflow) Center-of-Mass det. time= 568.0 min (1,289.8 - 721.8)

Volume	Invert A	vail.Storage	Storage De	escription	
#1	144.30'	72,067 cf	Custom St	age Data (Pris	smatic)Listed below (Recalc)
Elevation	Surf.Are	a Inc	.Store	Cum.Store	
(feet)	(sq-f	t) (cubi	c-feet)	(cubic-feet)	
144.30		0	0	0	
144.50	2,12	0	212	212	
145.00	2,56	0	1,170	1,382	
146.00	3,36	0	2,960	4,342	
147.00	13,04	0	8,200	12,542	
148.00	19,23	0	16,135	28,677	
149.00	21,93	0 2	20,580	49,257	
150.00	23,69	0 2	22,810	72,067	
Device Ro	outing	Invert Out	et Devices		
#1 Pr	imary 1	44.20' 1.9 "	Horiz. Orifi	ce C= 0.600	Limited to weir flow at low heads
#2 Pr	imary 1	46.50' 5.0 "	Horiz. Orifi	ce C= 0.600	Limited to weir flow at low heads
#3 Pr	imary 1	47.60' 8.0 "	W x 3.0" H	Vert. Weir Cut	C= 0.600
		Limi	ted to weir flo	ow at low head	s
#4 Pr	imary 1	47.80' 12.0	" Horiz. O/F	Riser C= 0.6	600 Limited to weir flow at low heads
Primary Ou 1=Orific	utFlow Max=0. e (Orifice Conti	14 cfs @ 19. rols 0.14 cfs (77 hrs HW= @ 7.17 fps)	146.42' (Free	Discharge)

-2=Orifice (Controls 0.00 cfs)

-3=Weir Cut (Controls 0.00 cfs)

-4=O/F Riser (Controls 0.00 cfs)

Riverbend Phase II_V1 Prepared by Westech Engineering, Inc. HydroCAD® 10.10-6a s/n 07289 © 2020 HydroCAD Software Solutions LLC

Type IA 24-hr Salem 1/2 2 YR Rainfall=1.10" Printed 7/25/2021

Pond 3P: Detention Basin



Summary for Subcatchment 1B: Basin 1

Runoff 1.29 cfs @ 7.91 hrs, Volume= = Routed to Pond 3P : Detention Basin

0.436 af, Depth= 2.62"

Runoff by SBUH method, Split Pervious/Imperv., Time Span= 0.50-120.00 hrs, dt= 0.05 hrs Type IA 24-hr Salem 10 YR Rainfall=3.20"

	Area (a	ac) C	CN	Desc	ription			
*	1.6	00	98	Pave	d parking	& roof, HS	GD	
*	0.2	00	74	Oper	n Śpace, ŀ	ISG C		
*	0.2	00	80	Oper	n Space, ⊦	ISG D		
	2.0	00	94	Weig	hted Aver	age		
	0.400			20.00)% Pervio	us Area		
	1.600			80.00)% Imperv	vious Area		
	Tc	Length	S	lope	Velocity	Capacity	Description	
	(min)	(feet)	((ft/ft)	(ft/sec)	(cfs)		
	50						Direct Entry	



Direct Entry,

Subcatchment 1B: Basin 1



Summary for Subcatchment 2B: Basin 2

0.939 af, Depth= 2.33" Runoff 2.72 cfs @ 7.92 hrs, Volume= = Routed to Pond 3P : Detention Basin

Runoff by SBUH method, Split Pervious/Imperv., Time Span= 0.50-120.00 hrs, dt= 0.05 hrs Type IA 24-hr Salem 10 YR Rainfall=3.20"

	50					Direct Entry		
	(min) ((feet)	(ft/ft)	(ft/sec)	(cfs)			
	IC LE	ength	Slope	velocity	Capacity	Description		
	T . I.		01	V/-1	0	Description		
	3.000	J	03.04	4% imperv	nous Area			
	2 000	- -	62.6	40/ Impon				
	1 760)	36 3	6% Pervio	us Area			
	4.840) 90	Weig	phted Aver	age			
*	0.880	J 80	Oper	n Space, F	ISG D			
÷	0.000			1 Opuco, 1				
*	0 880) 74	Oper	n Space F	ISGC			
*	3.080) 98	Pave	ed parking	& roof, HS	G D		
	Alea (ac		Dest	прион				
	Aron (no) CN	Deec	rintion				



Direct Entry,

Subcatchment 2B: Basin 2



Summary for Pond 3P: Detention Basin

Inflow Area	a =	6.840 ac,	68.42% Imp	ervious,	Inflow	Depth =	2.41"	for	Sale	n 10 Y	'R eve	nt
Inflow	=	4.01 cfs @	7.92 hrs,	Volume	=	1.375	af					
Outflow	=	0.84 cfs @	11.00 hrs,	Volume	=	1.375	af, At	ten= 7	'9%,	Lag=	185.0 ı	min
Primary	=	0.84 cfs @	11.00 hrs,	Volume	=	1.375	af			•		
Routed	to nonex	distent node	23L									

Routing by Stor-Ind method, Time Span= 0.50-120.00 hrs, dt= 0.05 hrs Peak Elev= 147.52' @ 11.00 hrs Surf.Area= 16,290 sf Storage= 20,241 cf

Plug-Flow detention time= 393.8 min calculated for 1.375 af (100% of inflow) Center-of-Mass det. time= 393.8 min (1,088.2 - 694.4)

Volume	Inve	t Avail.St	orage St	orage Desci	ription	
#1	144.30)' 72,	067 cf C	ustom Stag	e Data (Pri	smatic)Listed below (Recalc)
Elevatio	on S	Surf.Area	Inc.St	ore C	um.Store	
(fee	et)	(sq-ft)	(cubic-fe	et) (ci	ubic-feet)	
144.3	30	0		0	0	
144.5	50	2,120	2	212	212	
145.0	00	2,560	1,1	70	1,382	
146.0	00	3,360	2,9	960	4,342	
147.0	00	13,040	8,2	200	12,542	
148.0	00	19,230	16,1	35	28,677	
149.0	00	21,930	20,5	580	49,257	
150.0	00	23,690	22,8	310	72,067	
Device	Routing	Inver	t Outlet [Devices		
#1	Primary	144.20	' 1.9" Ho	riz. Orifice	C= 0.600	Limited to weir flow at low heads
#2	Primary	146.50	' 5.0" Ho	riz. Orifice	C= 0.600	Limited to weir flow at low heads
#3	Primary	147.60	' 8.0" W	x 3.0" H Ve	rt. Weir Cu	t C= 0.600
			Limited	to weir flow	at low head	ls
#4	Primary	147.80	' 12.0" H	oriz. O/F Ri	ser C= 0.6	600 Limited to weir flow at low heads
Drimary	OutFlow	Max-0.84 cfc	@ 11 00 F	$V_{\rm re} = H M - 1.17$	7.52' (Eroo	Discharge)

Primary OutFlow Max=0.84 cfs @ 11.00 hrs HW=147.52' (Free Discharge) —1=Orifice (Orifice Controls 0.17 cfs @ 8.78 fps)

-2=Orifice (Orifice Controls 0.66 cfs @ 4.87 fps)

-3=Weir Cut (Controls 0.00 cfs)

-4=O/F Riser (Controls 0.00 cfs)

Riverbend Phase II_V1 Prepared by Westech Engineering, Inc. HydroCAD® 10.10-6a s/n 07289 © 2020 HydroCAD Software Solutions LLC

Type IA 24-hr Salem 10 YR Rainfall=3.20" Printed 7/25/2021

Pond 3P: Detention Basin



Runoff 1.48 cfs @ 7.91 hrs, Volume= = Routed to Pond 3P : Detention Basin

0.499 af, Depth= 2.99"

Runoff by SBUH method, Split Pervious/Imperv., Time Span= 0.50-120.00 hrs, dt= 0.05 hrs Type IA 24-hr Salem 25 YR Rainfall=3.60"

	Area (a	ac) C	CN	Desc	ription			
*	1.6	00	98	Pave	d parking	& roof, HS	GD	
*	0.2	00	74	Oper	n Śpace, ŀ	ISG C		
*	0.2	00	80	Oper	n Space, ⊦	ISG D		
	2.0	00	94	Weig	hted Aver	age		
	0.400			20.00)% Pervio	us Area		
	1.600			80.00)% Imperv	vious Area		
	Tc	Length	S	lope	Velocity	Capacity	Description	
	(min)	(feet)	((ft/ft)	(ft/sec)	(cfs)		
	50						Direct Entry	



Direct Entry,

Subcatchment 1B: Basin 1



1.085 af, Depth= 2.69" Runoff 3.15 cfs @ 7.92 hrs, Volume= = Routed to Pond 3P : Detention Basin

Runoff by SBUH method, Split Pervious/Imperv., Time Span= 0.50-120.00 hrs, dt= 0.05 hrs Type IA 24-hr Salem 25 YR Rainfall=3.60"

	Area (ac)) CN	Desc	cription			
*	3.080) 98	Pave	ed parking	& roof, HS	G D	
*	0.880) 74	Oper	n Space, F	ISG C		
*	0.880) 80	Oper	n Space, ⊦	ISG D		
	4.840) 90	Weig	ghted Aver	age		
	1.760)	36.3	6% Pervio	us Area		
	3.080	C	63.6	4% Imperv	vious Area		
	Tc Le (min) (ength (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description	
	5.0					Direct Entry,	



Subcatchment 2B: Basin 2



Summary for Pond 3P: Detention Basin

Inflow Area	a =	6.840 ac, 6	8.42% Imp	ervious,	Inflow	Depth =	2.78	" for	Sale	m 25 Y	'R ever	nt
Inflow	=	4.63 cfs @	7.92 hrs,	Volume	=	1.584	af					
Outflow	=	0.98 cfs @	10.86 hrs,	Volume	=	1.584	af, A	tten=	79%,	Lag=	176.6 n	nin
Primary	=	0.98 cfs @	10.86 hrs,	Volume	=	1.584	af			•		
Routed	to nonex	kistent node 2	23L									

Routing by Stor-Ind method, Time Span= 0.50-120.00 hrs, dt= 0.05 hrs Peak Elev= 147.71' @ 10.86 hrs Surf.Area= 17,452 sf Storage= 23,409 cf

Plug-Flow detention time= 403.3 min calculated for 1.584 af (100% of inflow) Center-of-Mass det. time= 403.3 min (1,095.0 - 691.6)

Volume	Inve	rt Avai	I.Storage	Storage	e Descri	ption	
#1	144.3	0'	72,067 cf	Custon	n Stage	Data (Pri	smatic)Listed below (Recalc)
		~ ~ ^ ^		01	0	01	
Elevatio	on	Surf.Area		Inc.Store		m.Store	
(fee	et)	(sq-ft)		(cubic-feet)		<u>bic-feet)</u>	
144.3	30	0		0		0	
144.50		2,120	212			212	
145.00		2,560 1,170		1,170		1,382	
146.0	00	3,360		2,960		4,342	
147.0	00	13,040		8,200		12,542	
148.0	00	19,230	1	16,135		28,677	
149.0	00	21,930	2	20,580		49,257	
150.0	00	23,690		22,810		72,067	
Device	Routing	In	vert Outle	et Device	es		
#1	Primarv	144	.20' 1.9"	Horiz. O	rifice	C= 0.600	Limited to weir flow at low heads
#2	Primary	146	.50' 5.0"	Horiz. O	rifice	C= 0.600	Limited to weir flow at low heads
#3	Primary	hary 147.60' 8.0" W x 3.0" H Vert. Weir Cut C= 0.600					
	-		Limi	ted to we	ir flow a	at low head	ds
#4	Primary	Primary 147.80' 12.0" Horiz. O/F Riser C= 0.600 Limited to weir flow at low h					600 Limited to weir flow at low heads
Driment OutFlow May-0.00 of a 20.00 km UW-147.741 (Erec Discharge)							

Primary OutFlow Max=0.98 cfs @ 10.86 hrs HW=147.71' (Free Discharge)

1=Orifice (Orifice Controls 0.18 cfs @ 9.02 fps)

-2=Orifice (Orifice Controls 0.72 cfs @ 5.30 fps)

-3=Weir Cut (Orifice Controls 0.08 cfs @ 1.08 fps)

-4=O/F Riser (Controls 0.00 cfs)

Pond 3P: Detention Basin


Summary for Subcatchment 1B: Basin 1

Runoff 1.85 cfs @ 7.91 hrs, Volume= 0.626 af, Depth> 3.76" = Routed to Pond 3P : Detention Basin

Runoff by SBUH method, Split Pervious/Imperv., Time Span= 0.50-120.00 hrs, dt= 0.05 hrs Type IA 24-hr Salem 100 YR Rainfall=4.40"

	Area (ac)) CN	l Desc	cription			
*	1.600) 98	B Pave	ed parking	& roof, HS	GD	
*	0.200) 74	Ope	n Śpace, ⊦	ISG C		
*	0.200) 80	Ope	n Space, ⊦	ISG D		
	2.000) 94	Weig	ghted Aver	age		
	0.400 20.00% Pervious Area			us Area			
	1.600)	80.0	0% Imperv	vious Area		
	Tc Le	ength	Slope	Velocity	Capacity	Description	
	<u>(min) (</u>	(feet)	(ft/ft)	(ft/sec)	(cfs)		
	50					Direct Entry	



Direct Entry,

Subcatchment 1B: Basin 1



Summary for Subcatchment 2B: Basin 2

1.381 af, Depth> 3.42" Runoff 4.04 cfs @ 7.92 hrs, Volume= = Routed to Pond 3P : Detention Basin

Runoff by SBUH method, Split Pervious/Imperv., Time Span= 0.50-120.00 hrs, dt= 0.05 hrs Type IA 24-hr Salem 100 YR Rainfall=4.40"

	Area (ac) CN	Desc	cription				
*	3.080	0 98	Pave	ed parking	& roof, HS	GD		
*	0.880	0 74	Oper	n Śpace, ŀ	ISG C			
*	0.880	0 80	Oper	n Space, ⊦	ISG D			
	4.840	0 90	Weig	ghted Aver	age			
	1.760	0	36.3	6% Pervio	us Area			
	3.080	0	63.6	4% Imperv	vious Area			
	Tc Le	ength	Slope	Velocity	Capacity	Description		
_	<u>(min) (</u>	(feet)	(ft/ft)	(ft/sec)	(cfs)			
	5.0					Direct Entry.		



Direct Entry,

Subcatchment 2B: Basin 2



Summary for Pond 3P: Detention Basin

Inflow Area	a =	6.840 ac, 68	3.42% Imperv	vious, Inflow	/ Depth >	3.52"	for Saler	n 100 Y	R event
Inflow	=	5.89 cfs @	7.92 hrs, V	′olume=	2.007	af			
Outflow	=	1.76 cfs @	9.14 hrs, V	′olume=	2.007	af, Atte	n= 70%,	Lag= 73	3.2 min
Primary	=	1.76 cfs @	9.14 hrs, V	′olume=	2.007	af		•	
Routed	to none	kistent node 2	3L						

Routing by Stor-Ind method, Time Span= 0.50-120.00 hrs, dt= 0.05 hrs Peak Elev= 147.92' @ 9.14 hrs Surf.Area= 18,749 sf Storage= 27,201 cf

Plug-Flow detention time= 376.5 min calculated for 2.007 af (100% of inflow) Center-of-Mass det. time= 376.4 min (1,063.3 - 686.9)

Volume	Inv	vert Ava	ail.Storage	Storage	Description	
#1	144.	30'	72,067 cf	Custom	n Stage Data (Pri	i smatic) Listed below (Recalc)
Elovati	on	Surf Aroa	In	Store	Cum Storo	
	- 4)	Sun Area	1110 (
(10	et)	(sq-π)	(CUD)	ic-teet)	(cudic-feet)	
144.	30	0		0	0	
144.	50	2,120		212	212	
145.	00	2,560		1,170	1,382	
146.	00	3,360		2,960	4,342	
147.	00	13,040		8,200	12,542	
148.	00	19,230		16,135	28,677	
149.	00	21,930	:	20,580	49,257	
150.	00	23,690		22,810	72,067	
	-					
Device	Routing	Ir	nvert Out	let Device	S	
#1	Primary	144	4.20' 1.9 '	' Horiz. O	rifice C= 0.600	Limited to weir flow at low heads
#2	Primary	140	6.50' 5.0 '	' Horiz. O	rifice C= 0.600	Limited to weir flow at low heads
#3	Primary	147	7.60' 8.0 '	' W x 3.0"	' H Vert. Weir Cu	It C= 0.600
	-		Lim	ited to we	ir flow at low hea	ds
#4	Primary	14	7.80' 12.0)" Horiz. (D/F Riser C= 0.	600 Limited to weir flow at low heads

Primary OutFlow Max=1.75 cfs @ 9.14 hrs HW=147.92' (Free Discharge)

1=Orifice (Orifice Controls 0.18 cfs @ 9.29 fps)

-2=Orifice (Orifice Controls 0.78 cfs @ 5.74 fps)

-3=Weir Cut (Orifice Controls 0.35 cfs @ 2.10 fps)

-4=O/F Riser (Weir Controls 0.44 cfs @ 1.14 fps)

Riverbend Phase II_V1 Prepared by Westech Engineering, Inc. HydroCAD® 10.10-6a s/n 07289 © 2020 HydroCAD Software Solutions LLC

Type IA 24-hr Salem 100 YR Rainfall=4.40" Printed 7/25/2021

Pond 3P: Detention Basin



Summary for Subcatchment 1B: Basin 1

Runoff = 0.48 cfs @ 7.91 hrs, Volume= Routed to Pond 3P : Detention Basin 0.160 af, Depth= 0.96"

Runoff by SBUH method, Split Pervious/Imperv., Time Span= 0.50-120.00 hrs, dt= 0.05 hrs Type IA 24-hr Salem WQ Rainfall=1.38"

	Area (ad	c) Cl	N Dese	cription			
*	1.60	0 98	8 Pave	ed parking	& roof, HS	GD	
*	0.20	0 74	4 Ope	n Śpace, ł	ISG C		
*	0.20	0 8) Ope	n Space, ⊦	ISG D		
	2.00)0 94	4 Weig	ghted Aver	age		
	0.40	0.400 20.00% Pervious Area			us Area		
	1.60	00	80.0	0% Imperv	vious Area		
	Tc L	ength	Slope	Velocity	Capacity	Description	
_	(min)	(feet)	(ft/ft)	(ft/sec)	(cfs)		
	5.0					Direct Entry,	

Subcatchment 1B: Basin 1



Summary for Subcatchment 2B: Basin 2

Runoff 0.92 cfs @ 7.91 hrs, Volume= 0.322 af, Depth= 0.80" = Routed to Pond 3P : Detention Basin

Runoff by SBUH method, Split Pervious/Imperv., Time Span= 0.50-120.00 hrs, dt= 0.05 hrs Type IA 24-hr Salem WQ Rainfall=1.38"

	Area (ac)	CN	Desc	cription				
*	3.080	98	Pave	vaved parking & roof, HSG D				
*	0.880	74	Oper	n Śpace, ł	ISG C			
*	0.880	80	Oper	n Space, F	ISG D			
	4.840	90	Weig	ghted Aver	age			
	1.760		36.3	6% Pervio	us Area			
	3.080		63.6	4% Imperv	∕ious Area			
	Tc Len	gth	Slope	Velocity	Capacity	Description		
	<u>(min)</u> (fe	eet)	(ft/ft)	(ft/sec)	(cfs)			
	50					Direct Entry		



Direct Entry,

Subcatchment 2B: Basin 2



Summary for Pond 3P: Detention Basin

Inflow Area	a =	6.840 ac, 6	8.42% Imp	ervious,	Inflow	Depth =	0.85	" for	Sale	m WQ	event	
Inflow	=	1.40 cfs @	7.91 hrs,	Volume	=	0.482	af					
Outflow	=	0.26 cfs @	12.62 hrs,	Volume	=	0.482	af, A	tten=	82%,	Lag=	282.7	min
Primary	=	0.26 cfs @	12.62 hrs,	Volume	=	0.482	af			•		
Routed	to nonex	kistent node	23L									

Routing by Stor-Ind method, Time Span= 0.50-120.00 hrs, dt= 0.05 hrs Peak Elev= 146.59' @ 12.62 hrs Surf.Area= 9,034 sf Storage= 7,975 cf

Plug-Flow detention time= 542.3 min calculated for 0.482 af (100% of inflow) Center-of-Mass det. time= 542.6 min (1,258.1 - 715.5)

Volume	Inve	rt Avail	.Storage	Storage	Description		
#1	144.3	0' 7	2,067 cf	Custom	Stage Data	a (Pris	smatic)Listed below (Recalc)
		o ()		01	0 0		
Elevation	on	Surf.Area	Inc	.Store	Cum.St	ore	
(fee	et)	(sq-ft)	(cubio	c-feet)	(cubic-fe	et)	
144.3	30	0		0		0	
144.5	50	2,120		212	2	212	
145.0	00	2,560		1,170	1,3	382	
146.0	00	3,360		2,960	4,3	342	
147.0	00	13,040		8,200	12,5	542	
148.0	00	19,230	1	6,135	28,6	577	
149.0	00	21,930	2	0,580	49,2	257	
150.0	00	23,690	2	2,810	72,0)67	
D	Denting	L					
Device	Routing	Inv	ert Outle	et Device	S		
#1	Primary	144.:	20' 1.9''	Horiz. O	rifice C=C	.600	Limited to weir flow at low heads
#2	Primary	146.	50' 5.0''	Horiz. O	rifice C=C	.600	Limited to weir flow at low heads
#3	Primary	147.	60' 8.0''	W x 3.0"	H Vert. We	ir Cut	t C= 0.600
			Limit	ed to wei	ir flow at low	head	ls
#4	Primary	147.	80' 12.0 '	" Horiz. (O/F Riser	C= 0.6	600 Limited to weir flow at low heads
	0	May-0.05	fa @ 10 0			/ Г ио о	Discharge

Primary OutFlow Max=0.25 cfs @ 12.62 hrs HW=146.59' (Free Discharge)

- **1=Orifice** (Orifice Controls 0.15 cfs @ 7.44 fps)
- -2=Orifice (Weir Controls 0.11 cfs @ 0.96 fps)
- -3=Weir Cut (Controls 0.00 cfs)
- -4=O/F Riser (Controls 0.00 cfs)

Pond 3P: Detention Basin





Summary for Reach 1R: Veg. Swale

 Inflow Area =
 2.000 ac, 80.00% Impervious, Inflow Depth =
 0.96" for Salem WQ event

 Inflow =
 0.48 cfs @
 7.91 hrs, Volume=
 0.160 af

 Outflow =
 0.46 cfs @
 8.00 hrs, Volume=
 0.160 af, Atten= 3%, Lag= 5.6 min

Routing by Stor-Ind method, Time Span= 0.50-120.00 hrs, dt= 0.05 hrs Max. Velocity= 0.17 fps, Min. Travel Time= 9.5 min Avg. Velocity = 0.07 fps, Avg. Travel Time= 25.1 min

Peak Storage= 265 cf @ 8.00 hrs Average Depth at Peak Storage= 0.30', Surface Width= 9.79' Bank-Full Depth= 1.00' Flow Area= 11.0 sf, Capacity= 3.88 cfs

8.00' x 1.00' deep channel, n= 0.250 Side Slope Z-value= 3.0 '/' Top Width= 14.00' Length= 100.0' Slope= 0.0050 '/' Inlet Invert= 147.00', Outlet Invert= 146.50'



Reach 1R: Veg. Swale



Summary for Reach 2R: Veg. Swale

 Inflow Area =
 4.840 ac, 63.64% Impervious, Inflow Depth =
 0.80" for Salem WQ event

 Inflow =
 0.92 cfs @
 7.91 hrs, Volume=
 0.322 af

 Outflow =
 0.90 cfs @
 8.00 hrs, Volume=
 0.322 af, Atten= 3%, Lag= 5.3 min

Routing by Stor-Ind method, Time Span= 0.50-120.00 hrs, dt= 0.05 hrs Max. Velocity= 0.21 fps, Min. Travel Time= 9.1 min Avg. Velocity = 0.08 fps, Avg. Travel Time= 24.8 min

Peak Storage= 492 cf @ 8.00 hrs Average Depth at Peak Storage= 0.33', Surface Width= 13.98' Bank-Full Depth= 1.00' Flow Area= 15.0 sf, Capacity= 6.09 cfs

12.00' x 1.00' deep channel, n= 0.250 Side Slope Z-value= 3.0 '/' Top Width= 18.00' Length= 115.0' Slope= 0.0061 '/' Inlet Invert= 147.20', Outlet Invert= 146.50'





Summary for Reach 1R: Veg. Swale

 Inflow Area =
 2.000 ac, 80.00% Impervious, Inflow Depth > 3.76" for Salem 100 YR event

 Inflow =
 1.85 cfs @
 7.91 hrs, Volume=
 0.626 af

 Outflow =
 1.85 cfs @
 7.92 hrs, Volume=
 0.626 af, Atten= 0%, Lag= 0.9 min

Routing by Stor-Ind method, Time Span= 0.50-120.00 hrs, dt= 0.05 hrs Max. Velocity= 1.12 fps, Min. Travel Time= 1.5 min Avg. Velocity = 0.53 fps, Avg. Travel Time= 3.2 min

Peak Storage= 166 cf @ 7.92 hrs Average Depth at Peak Storage= 0.19', Surface Width= 9.16' Bank-Full Depth= 1.00' Flow Area= 11.0 sf, Capacity= 32.31 cfs

8.00' x 1.00' deep channel, n= 0.030 Side Slope Z-value= 3.0 '/' Top Width= 14.00' Length= 100.0' Slope= 0.0050 '/' Inlet Invert= 147.00', Outlet Invert= 146.50'







Summary for Reach 2R: Veg. Swale

 Inflow Area =
 4.840 ac, 63.64% Impervious, Inflow Depth > 3.42" for Salem 100 YR event

 Inflow =
 4.04 cfs @
 7.92 hrs, Volume=
 1.381 af

 Outflow =
 4.04 cfs @
 7.93 hrs, Volume=
 1.381 af, Atten= 0%, Lag= 0.9 min

Routing by Stor-Ind method, Time Span= 0.50-120.00 hrs, dt= 0.05 hrs Max. Velocity= 1.39 fps, Min. Travel Time= 1.4 min Avg. Velocity = 0.65 fps, Avg. Travel Time= 3.0 min

Peak Storage= 334 cf @ 7.93 hrs Average Depth at Peak Storage= 0.23', Surface Width= 13.37' Bank-Full Depth= 1.00' Flow Area= 15.0 sf, Capacity= 50.73 cfs

12.00' x 1.00' deep channel, n= 0.030 Side Slope Z-value= 3.0 '/' Top Width= 18.00' Length= 115.0' Slope= 0.0061 '/' Inlet Invert= 147.20', Outlet Invert= 146.50'





RIVERBEND ROAD SITE PHASE II Stormwater Calculations Salem, Oregon

APPENDIX D

GEOTECHNICAL REPORT

Geotechnical Engineering Report

Riverbend Phase 2 Wallace Road NW Salem, Oregon

for Scott Martin Construction, Inc.

December 23, 2020





Geotechnical Engineering Report

Riverbend Phase 2 Wallace Road NW Salem, Oregon

for Scott Martin Construction, Inc.

December 23, 2020



333 High Street NE, Suite 102Salem, Oregon 97301971.304.3078

Geotechnical Engineering Report

Riverbend Phase 2 Wallace Road NW Salem, Oregon

File No. 23198-001-00

December 23, 2020

Prepared for:

Scott Martin Construction, Inc. 2600 Michigan City Rd NW Salem, Oregon 97304

Attention: Scott Martin

Prepared by:

GeoEngineers, Inc. 333 High Street NE, Suite 102 Salem, Oregon 97301 971.304.3078

Benjamin J. Hoffman, PE Senior Engineer







BJH:JLL:JCV:cje

Disclaimer: Any electronic form, facsimile or hard copy of the original document (email, text, table, and/or figure), if provided, and any attachments are only a copy of the original document. The original document is stored by GeoEngineers, Inc. and will serve as the official document of record.



Table of Contents

2.0 SCOPE OF SERVICES 1 3.0 SITE CONDITIONS 3 3.1 Site Geology 3 3.2 Surface Conditions 3 3.3 Slope Conditions 3 3.4 Subsurface Conditions 3 3.4 Subsurface Conditions 4 4.0 CONCLUSIONS 4 4.1 General 4 5.0 INFILTRATION TESTING 6 5.1 General 6 5.2 Suitability of Infiltration System 7 6.1 General 7 6.1 Deneral 7 6.1 Deneral 6 6.2 Suitability of Infiltration System 7 6.1 Deneral 7 6.1 Deneral 8 6.2 Subgrade Protection and Evaluation 8 6.3 Subgrade Protection and Evaluation 8 6.4 Cemert Treated Subgrade Design 10 6.5 Excavation 10 6.5 Evavation 11	1.0	INTRODUCTION	1
3.0 SITE CONDITIONS	2.0	SCOPE OF SERVICES	1
3.1. Site Geology 3 3.2. Surface Conditions 3 3.3. Slope Conditions 3 3.4. Subsurface Conditions 4 4.5. Groundwater 4 4.0. CONCLUSIONS 4 4.1. General 4 5.0. INFILTRATION TESTING 6 5.1. General 6 5.2. Suitability of Infiltration System 7 6.0. EARTHWORK RECOMMENDATIONS 7 6.1.1. Demolition 7 6.1.2. Stripping and Grubbing 8 6.2. Subgrade Preparation and Evaluation. 8 6.3. Subgrade Preparation and Evaluation. 8 6.4. Cement Treated Subgrade Design 10 6.5. Excavation 11 16. Dewatering 11 6.7. Trench Cuts and Trench Shoring 12 6.9.1. General 12 6.9.2. On-Site Soils 12 6.9.3. Imported Select Structural Fill 12 6.9.4. Aggregate Base 13 6.9.5. Trench Backfill 13 6.9.6. Retaining Wall Backfill 12 6.9.7. Trench Backfill 13 6.9.8. Retaining Wall	3.0	SITE CONDITIONS	3
3.2. Surface Conditions. 3 3.3. Slope Conditions. 3 3.4. Subsurface Conditions 4 4.5. Groundwater 4 4.0 CONCLUSIONS 4 4.1. General 4 5.0 INFILTRATION TESTING 6 5.1. General 6 5.2. Suitability of Infiltration System 7 6.0 EARTHWORK RECOMMENDATIONS 7 6.1.1. Demolition 7 6.1.2. Stripping and Grubbing 8 6.2. Subgrade Preparation and Evaluation 8 6.3. Subgrade Protection and Wet Weather Considerations 9 6.4. Cement Treated Subgrade Design 10 6.5. Excavation 11 6.6. Dewatering 11 6.7. Structural Fill and Backfill 12 6.9.1. General 12 6.9.2. On-Site Soils 12 6.9.3. Unported Select Structural Fill 12 6.9.4. Aggregate Base 13 6.9.5. French Backfill 12 6.9.4. Aggregate Base 13 6.9.5. French Backfill 13 6.9.6. Retaining Wall Backfill 13 6.9.7	3.1.	Site Geology	3
3.3. Slope Conditions 3 3.4. Subsurface Conditions 4 3.5. Groundwater 4 4.0. CONCLUSIONS 4 4.0. CONCLUSIONS 4 4.1. General 4 5.0. INFILTRATION TESTING 6 5.1. General 6 5.2. Suitability of Infiltration System 7 6.0. EARTHWORK RECOMMENDATIONS 7 6.1. Demolition 8 6.1.2. Stripping and Grubbing 8 6.3. Subgrade Preparation and Evaluation 8 6.3. Subgrade Properation and Wet Weather Considerations 9 6.4. Cement Treated Subgrade Design 10 6.5. Excavation 11 6.6. Dewatering 11 6.7. Trench Cuts and Trench Shoring 11 6.8. Forsion Control 12 6.9.1. General 12 6.9.2. On-Site Soils 12 6.9.3. Imported Select Structural Fill 13 6.9.4. Aggregate Base 13 6.9.5. Trench Backfill 13 6.9.6. Retaining Wall Backfill 13 6.9.6. Retaining Wall Backfill 13 6.9	3.2.	Surface Conditions	3
3.4. Subsurface Conditions 4 3.5. Groundwater 4 4.0 CONCLUSIONS 4 4.1. General. 4 5.0 INFLITRATION TESTING 6 5.1. General. 6 5.2. Suitability of Infiltration System 7 6.0 EARTHWORK RECOMMENDATIONS 7 6.1. Site Preparation 7 6.1.1. Demolition 8 6.1.2. Stripping and Grubbing 8 6.3. Subgrade Properation and Evaluation 8 6.3. Subgrade Protection and Wet Weather Considerations 9 6.4. Cement Treated Subgrade Design 10 6.5. Excavation 11 6.6. Dewatering 11 6.7. Trench Cuts and Trench Shoring 12 6.9.1. General 12 6.9.2. On-Site Soils 12 6.9.3. Imported Select Structural Fill 13 6.9.5. Trench Backfill 13 6.9.6. Reatining Wall Backfill 13 6.9.7. Trench Backfill 13 6.9.8. Imported Select Structural Fill 13 6.9.6. Trench Backfill 13 6.9.7. Trench Backfill 13	3.3.	Slope Conditions	3
3.5. Groundwater 4 4.0 CONCLUSIONS 4 4.1. General 4 5.0 INFILTRATION TESTING 6 5.1. General 6 5.2. Suitability of Infiltration System 7 6.0 EARTHWORK RECOMMENDATIONS 7 6.1. Demolition 7 6.1.1. Demolition 8 6.1.2. Stripping and Grubbing 8 6.3. Subgrade Preparation and Evaluation 8 6.3. Subgrade Protection and Wet Weather Considerations 9 6.4. Cement Treated Subgrade Design 10 6.5. Excavation 11 6.7. Trench Cuts and Trench Shoring 11 6.8. Subgrade Protection and Wet Weather Considerations 12 6.9.1. General 12 6.9.2. On-Site Solis 12 6.9.3. Imported Select Structural Fill 12 6.9.4. Aggregate Base 13 6.9.5. Trench Backfill 13 6.9.4. Regregate Base 13 6.9.5. Trench Backfill 13 6.9.6. Retaining Wall Backfill 13 6.9.1. General 13 6.9.2. On-Site Soles 14	3.4.	Subsurface Conditions	4
4.0 CONCLUSIONS 4 4.1. General 4 5.0 INFILTRATION TESTING 6 5.1. General 6 5.2. Suitability of Infiltration System 7 6.0 EARTHWORK RECOMMENDATIONS 7 6.1. Demolition 7 6.1.1. Demolition 7 6.1.2. Stripping and Grubbing. 8 6.3. Subgrade Preparation and Evaluation. 8 6.3. Subgrade Protection and Wet Weather Considerations. 9 6.4. Cement Treated Subgrade Design. 10 6.5. Excavation 11 6.6. Dewatering 11 6.7. Trench Cuts and Trench Shoring. 11 6.8. Erosion Control. 12 6.9.1. General 12 6.9.2. On-Site Soils 12 6.9.3. Imported Select Structural Fill 12 6.9.4. Aggregate Base 13 6.9.5. Trench Backfill 13 6.9.6. Retaining Wall Backfill. 13 6.9.6. Retaining Wall Backfill. 13 6.9.1. General and Compaction 13 6.9.1. Structrural Slopes 14 6.11.1. Pere	3.5.	Groundwater	4
4.1. General 4 5.0 INFILTRATION TESTING 6 5.1. General 6 5.2. Suitability of Infiltration System 7 6.0 EARTHWORK RECOMMENDATIONS 7 6.1. Demolition 7 6.1.1. Demolition 7 6.1.2. Stripping and Grubbing 8 6.3. Subgrade Preparation and Evaluation 8 6.3. Subgrade Protection and Weather Considerations 9 6.4. Cement Treated Subgrade Design 10 6.5. Excavation 11 6.6. Dewatering 11 6.7. Trench Cuts and Trench Shoring 11 6.8. Erosion Control 12 6.9.1. General 12 6.9.2. On-Site Soils 12 6.9.3. Imported Select Structural Fill 12 6.9.4. Aggregate Base 13 6.9.5. Trench Backfill 13 6.9.6. Retaining Wall Backfill 13 6.9.6. Retaining Wall Backfill 13 6.11.1. Permanent Slopes 14 6.11.2. Temporary Slopes 14 6.11.3. Slope Drainage 15 7.0 STRUCTURAL DESIGN RECOMMENDATIONS 15 </th <th>4.0</th> <th>CONCLUSIONS</th> <th>4</th>	4.0	CONCLUSIONS	4
5.0 INFILTRATION TESTING 6 5.1. General 6 5.2. Suitability of Infiltration System 7 6.0 EARTHWORK RECOMMENDATIONS. 7 6.1. Site Preparation 7 6.1.1. Demolition 8 6.1.2. Stripping and Grubbing. 8 6.2. Subgrade Preparation and Evaluation. 8 6.3. Subgrade Protection and Wet Weather Considerations. 9 6.4. Cernent Treated Subgrade Design 10 6.5. Excavation 11 6.6. Dewatering 11 6.7. Trench Cuts and Trench Shoring. 11 6.8. Erosion Control. 12 6.9.1. General 12 6.9.2. On-Site Soils 12 6.9.3. Imported Select Structural Fill 12 6.9.4. Aggregate Base 13 6.9.5. Trench Backfill 13 6.9.6. Retaining Wall Backfill 13 6.9.7. Imported Select Structural Fill 13 6.9.6. <t< td=""><td>4.1.</td><td>General</td><td>4</td></t<>	4.1.	General	4
5.1. General 6 5.2. Suitability of Infiltration System 7 6.0 EARTHWORK RECOMMENDATIONS 7 6.1. Site Preparation 7 6.1.1. Demolition 8 6.1.2. Stripping and Grubbing 8 6.2. Subgrade Preparation and Evaluation. 8 6.3. Subgrade Preparation and Wet Weather Considerations 9 6.4. Cement Treated Subgrade Design 10 6.5. Excavation 11 6.6. Dewatering 11 6.6. Dewatering 11 6.7. Trench Cuts and Trench Shoring 11 6.8. Structural Fill and Backfill 12 6.9.1. General 12 6.9.2. On-Site Soils 12 6.9.3. Imported Select Structural Fill 12 6.9.4. Aggregate Base 13 6.9.5. Trench Backfill 13 6.9.6. Retaining Wall Backfill 13 6.10. Fill Placement and Compaction 13 6.11.1. Permanent Slopes 14 6.11.2. Temporary Slopes 14 6.11.3. Slope Drainage 15 7.1. Foundation Support Recommendations 15 7.1.1. Foundation	5.0	INFILTRATION TESTING	6
5.2. Suitability of Infiltration System 7 6.0 EARTHWORK RECOMMENDATIONS 7 6.1. Site Preparation 7 6.1.1. Demolition 8 6.1.2. Stripping and Grubbing 8 6.2. Subgrade Preparation and Evaluation. 8 6.3. Subgrade Preparation and Wet Weather Considerations 9 6.4. Cement Treated Subgrade Design 10 6.5. Excavation 11 6.6. Dewatering 11 6.7. Trench Cuts and Trench Shoring 11 6.8. Erosion Control 12 6.9.1 General 12 6.9.2. On-Site Soils 12 6.9.3. Imported Select Structural Fill 12 6.9.4. Aggregate Base 13 6.9.5. Trench Backfill 13 6.9.6. Retaining Wall Backfill 13 6.9.7. Trench Backfill 13 6.9.8. Inported Select Structural Fill 13 6.9.9. Trench Backfill 13 6.10. Fill Placement and Compaction 13 6.11.1. Permanent Slopes 14 6.11.2. Temporary Slopes 14 6.11.3. Slope Drainage 15 7.1. Foundatio	5.1.	General	6
6.0 EARTHWORK RECOMMENDATIONS 7 6.1. Site Preparation 7 6.1.1. Demolition 8 6.1.2. Stripping and Grubbing 8 6.2. Subgrade Preparation and Evaluation 8 6.3. Subgrade Protection and Wet Weather Considerations 9 6.4. Cement Treated Subgrade Design 10 6.5. Excavation 11 6.6. Dewatering 11 6.7. Trench Cuts and Trench Shoring 11 6.8. Erosion Control 12 6.9. Structural Fill and Backfill 12 6.9.1. General 12 6.9.2. On-Site Soils 12 6.9.3. Imported Select Structural Fill 12 6.9.4. Aggregate Base 13 6.9.5. Trench Backfill 13 6.9.6. Retaining Wall Backfill 13 6.10. Fill Placement and Compaction 13 6.11.3. Slopes 14 6.11.4. Permanent Slopes 14 6.11.3. Slope Drainage 15 7.0 STRUCTURAL DESIGN RECOMMENDATIONS 15 7.1. Foundation Subgrade Properation 16	5.2.	Suitability of Infiltration System	7
6.1. Site Preparation 7 6.1.1. Demolition 8 6.1.2. Stripping and Grubbing. 8 6.2. Subgrade Preparation and Evaluation 8 6.3. Subgrade Protection and Wet Weather Considerations. 9 6.4. Cement Treated Subgrade Design 10 6.5. Excavation 11 6.6. Dewatering 11 6.7. Trench Cuts and Trench Shoring. 11 6.8. Erosion Control. 12 6.9. Structural Fill and Backfill 12 6.9.1. General 12 6.9.2. On-Site Soils 12 6.9.3. Imported Select Structural Fill 12 6.9.4. Aggregate Base 13 6.9.5. Trench Backfill 13 6.9.6. Retaining Wall Backfill 13 6.11.1. Permanent Slopes 14 6.11.2. Temporary Slopes 14 6.11.3. Slope Drainage 15 7.0. STRUCTURAL DESIGN RECOMMENDATIONS 15 7.1. Foundation Subgrade Preparation 16	6.0	EARTHWORK RECOMMENDATIONS	7
6.1.1. Demolition 8 6.1.2. Stripping and Grubbing. 8 6.2. Subgrade Preparation and Evaluation 8 6.3. Subgrade Protection and Wet Weather Considerations. 9 6.4. Cement Treated Subgrade Design 10 6.5. Excavation 11 6.6. Dewatering 11 6.6. Dewatering 11 6.7. Trench Cuts and Trench Shoring. 11 6.8. Erosion Control 12 6.9. Structural Fill and Backfill 12 6.9.1. General 12 6.9.2. On-Site Soils 12 6.9.3. Imported Select Structural Fill 12 6.9.4. Aggregate Base 13 6.9.5. Trench Backfill 13 6.9.6. Retaining Wall Backfill 13 6.9.6. Retaining Wall Backfill 13 6.10. Fill Placement and Compaction 13 6.11.1. Permanent Slopes 14 6.11.2. Temporary Slopes 14 6.11.3. Slope Drainage 15 7.0 STRUCTURAL DESIGN RECOMMENDATIONS 15 7.1. Foundation Subgrade Preparation 16	6.1.	Site Preparation	7
6.1.2. Stripping and Grubbing. .8 6.2. Subgrade Preparation and Evaluation. .8 6.3. Subgrade Protection and Wet Weather Considerations. .9 6.4. Cement Treated Subgrade Design. .10 6.5. Excavation .11 6.6. Dewatering .11 6.6. Dewatering .11 6.6. Dewatering .11 6.7. Trench Cuts and Trench Shoring .11 6.8. Erosion Control. .12 6.9. Structural Fill and Backfill .12 6.9.1. General .12 6.9.2. On-Site Soils .12 6.9.3. Imported Select Structural Fill .12 6.9.4. Aggregate Base .13 6.9.5. Trench Backfill .13 6.9.6. Retaining Wall Backfill .13 6.9.6. Retaining Wall Backfill .13 6.11.1. Permanent Slopes .14 6.11.2. Temporary Slopes .14 6.11.3. Slope Drainage. .15 7.0 STRUCTURAL DESIGN RECOMMENDATIONS .15 7.1. Foundation Support Recommendations .15 7.1.1. Foundation Subgrade Preparation .16	6	5.1.1. Demolition	8
6.2. Subgrade Preparation and Evaluation .8 6.3. Subgrade Protection and Wet Weather Considerations .9 6.4. Cement Treated Subgrade Design .10 6.5. Excavation .11 6.6. Dewatering .11 6.6. Dewatering .11 6.7. Trench Cuts and Trench Shoring .11 6.8. Erosion Control .12 6.9. Structural Fill and Backfill .12 6.9.1. General .12 6.9.2. On-Site Soils .12 6.9.3. Imported Select Structural Fill .12 6.9.4. Aggregate Base .13 6.9.5. Trench Backfill .13 6.9.6. Retaining Wall Backfill .13 6.10. Fill Placement and Compaction .13 6.11.1. Permanent Slopes .14 6.11.2. Temporary Slopes .14 6.11.3. Slope Drainage .15 7.0 STRUCTURAL DESIGN RECOMMENDATIONS .15 7.1. Foundation Support Recommendations .15 7.1.2. Pearing Conscience .16	6	5.1.2. Stripping and Grubbing	8
6.3. Subgrade Protection and Wet Weather Considerations .9 6.4. Cement Treated Subgrade Design .10 6.5. Excavation .11 6.6. Dewatering .11 6.7. Trench Cuts and Trench Shoring .11 6.8. Erosion Control .12 6.9. Structural Fill and Backfill .12 6.9.1. General .12 6.9.2. On-Site Soils .12 6.9.3. Imported Select Structural Fill .12 6.9.4. Aggregate Base .13 6.9.5. Trench Backfill .12 6.9.6. Retaining Wall Backfill .13 6.10. Fill Placement and Compaction .13 6.11.1. Permanent Slopes .14 6.11.2. Temporary Slopes .14 6.11.3. Slope Drainage .15 7.0 STRUCTURAL DESIGN RECOMMENDATIONS .15 7.1. Foundation Support Recommendations .15 7.1.1. Foundation Subgrade Preparation .16	6.2.	Subgrade Preparation and Evaluation	8
6.4. Cement Treated Subgrade Design	6.3.	Subgrade Protection and Wet Weather Considerations	9
6.5. Excavation 11 6.6. Dewatering 11 6.6. Dewatering 11 6.7. Trench Cuts and Trench Shoring 11 6.8. Erosion Control 12 6.9. Structural Fill and Backfill 12 6.9.1. General 12 6.9.2. On-Site Soils 12 6.9.3. Imported Select Structural Fill 12 6.9.4. Aggregate Base 13 6.9.5. Trench Backfill 13 6.9.6. Retaining Wall Backfill 13 6.9.1. Sippes 14 6.11.1. Permanent Slopes 14 6.11.2. Temporary Slopes 14 6.11.3. Slope Drainage 15 7.0 STRUCTURAL DESIGN RECOMMENDATIONS 15 7.1. Foundation Subprot Recommendations 15 7.1.1. Foundation Subgrade Preparation 16 7.1.2. Reaging Concept 16 7.1.3. Slope Trainage 15 7.1.4. Provide Tool Subgrade Preparation 16 7.1.1. Foundation Subgrade Preparation 16	6.4.	Cement Treated Subgrade Design	10
6.6. Dewatering 11 6.7. Trench Cuts and Trench Shoring 11 6.8. Erosion Control 12 6.9. Structural Fill and Backfill 12 6.9.1. General 12 6.9.2. On-Site Soils 12 6.9.3. Imported Select Structural Fill 12 6.9.4. Aggregate Base 13 6.9.5. Trench Backfill 13 6.9.6. Retaining Wall Backfill 13 6.10. Fill Placement and Compaction 13 6.11.1. Slopes 14 6.11.2. Temporary Slopes 14 6.11.3. Slope Drainage 15 7.0 STRUCTURAL DESIGN RECOMMENDATIONS 15 7.1.1. Foundation Support Recommendations 15 7.1.1. Foundation Support Recommendations 15 7.1.2. Rearing Canceity Spread Eacting	6.5.	Excavation	11
6.7. Trench Cuts and Trench Shoring. 11 6.8. Erosion Control. 12 6.9. Structural Fill and Backfill 12 6.9.1. General 12 6.9.2. On-Site Soils 12 6.9.3. Imported Select Structural Fill 12 6.9.4. Aggregate Base 13 6.9.5. Trench Backfill 13 6.9.6. Retaining Wall Backfill 13 6.10. Fill Placement and Compaction 13 6.11.1. Slopes 14 6.11.2. Temporary Slopes 14 6.11.3. Slope Drainage 15 7.0 STRUCTURAL DESIGN RECOMMENDATIONS 15 7.1.1. Foundation Support Recommendations 15 7.1.2. Pearing Canacity Stread Exciting	6.6.	Dewatering	11
6.8. Erosion Control. 12 6.9. Structural Fill and Backfill 12 6.9.1. General 12 6.9.2. On-Site Soils 12 6.9.3. Imported Select Structural Fill 12 6.9.4. Aggregate Base 13 6.9.5. Trench Backfill 13 6.9.6. Retaining Wall Backfill 13 6.10. Fill Placement and Compaction 13 6.11. Slopes 14 6.11.2. Temporary Slopes 14 6.11.3. Slope Drainage 15 7.0 STRUCTURAL DESIGN RECOMMENDATIONS 15 7.1. Foundation Subport Recommendations 15 7.1.1. Foundation Subgrade Preparation 16 7.1.2. Program 16	6.7.	Trench Cuts and Trench Shoring	11
6.9. Structural Fill and Backfill 12 6.9.1. General 12 6.9.2. On-Site Soils 12 6.9.3. Imported Select Structural Fill 12 6.9.4. Aggregate Base 13 6.9.5. Trench Backfill 13 6.9.6. Retaining Wall Backfill 13 6.10. Fill Placement and Compaction 13 6.11. Slopes 14 6.11.2. Temporary Slopes 14 6.11.3. Slope Drainage 15 7.0 STRUCTURAL DESIGN RECOMMENDATIONS 15 7.1. Foundation Support Recommendations 15 7.1.1. Foundation Subgrade Preparation 16 7.1.2. Pasating Capacity Spread Easting	6.8.	Erosion Control	12
6.9.1. General 12 6.9.2. On-Site Soils 12 6.9.3. Imported Select Structural Fill 12 6.9.4. Aggregate Base 13 6.9.5. Trench Backfill 13 6.9.6. Retaining Wall Backfill 13 6.10. Fill Placement and Compaction 13 6.11. Slopes 14 6.11.1. Permanent Slopes 14 6.11.2. Temporary Slopes 14 6.11.3. Slope Drainage 15 7.0 STRUCTURAL DESIGN RECOMMENDATIONS 15 7.1. Foundation Support Recommendations 15 7.1.1. Foundation Subgrade Preparation 16 7.1.2 Pagaring Congetive Strong Factoring	6.9.	Structural Fill and Backfill	12
6.9.2. On-Site Soils 12 6.9.3. Imported Select Structural Fill 12 6.9.4. Aggregate Base 13 6.9.5. Trench Backfill 13 6.9.6. Retaining Wall Backfill 13 6.10. Fill Placement and Compaction 13 6.11. Slopes 14 6.11.1. Permanent Slopes 14 6.11.2. Temporary Slopes 14 6.11.3. Slope Drainage 15 7.0 STRUCTURAL DESIGN RECOMMENDATIONS 15 7.1. Foundation Support Recommendations 15 7.1.1. Foundation Subgrade Preparation 16 7.1.2. Pearing Capacity Spread Feetings	(5.9.1. General	12
6.9.3. Imported Select Structural Fill 12 6.9.4. Aggregate Base 13 6.9.5. Trench Backfill 13 6.9.6. Retaining Wall Backfill 13 6.10. Fill Placement and Compaction 13 6.11. Slopes 14 6.11.1. Permanent Slopes 14 6.11.2. Temporary Slopes 14 6.11.3. Slope Drainage 15 7.0 STRUCTURAL DESIGN RECOMMENDATIONS 15 7.1. Foundation Support Recommendations 15 7.1.1. Foundation Subgrade Preparation 16 7.1.2. Reparing Connective Spread Factings	(5.9.2. Un-Site Soils	12
6.9.4. Aggregate Base 13 6.9.5. Trench Backfill 13 6.9.6. Retaining Wall Backfill 13 6.10. Fill Placement and Compaction 13 6.11. Slopes 14 6.11.1. Permanent Slopes 14 6.11.2. Temporary Slopes 14 6.11.3. Slope Drainage 15 7.0 STRUCTURAL DESIGN RECOMMENDATIONS 15 7.1. Foundation Support Recommendations 15 7.1.1. Foundation Subgrade Preparation 16 7.1.2. Regaring Consoity Stread Exectings	6	5.9.3. Imported Select Structural Fill	12
6.9.5. Trench Backfill 13 6.9.6. Retaining Wall Backfill 13 6.10. Fill Placement and Compaction 13 6.11. Slopes 14 6.11.1. Permanent Slopes 14 6.11.2. Temporary Slopes 14 6.11.3. Slope Drainage 15 7.0 STRUCTURAL DESIGN RECOMMENDATIONS 15 7.1. Foundation Support Recommendations 15 7.1.1. Foundation Subgrade Preparation 16 7.12. Pearing Capacity Spread Eastings 7.13. Structure Capacity Spread Eastings	ť	5.9.4. Aggregate Base	13
6.9.6. Retaining wall Backfill 13 6.10. Fill Placement and Compaction 13 6.11. Slopes 14 6.11.1. Permanent Slopes 14 6.11.2. Temporary Slopes 14 6.11.3. Slope Drainage 15 7.0 STRUCTURAL DESIGN RECOMMENDATIONS 15 7.1. Foundation Support Recommendations 15 7.1. Foundation Subgrade Preparation 16 7.1.2. Pearing Capacity Spread Eastings	e e	5.9.5. Trench Backfill	13
6.10. Fill Placement and Compaction 13 6.11. Slopes 14 6.11.1. Permanent Slopes 14 6.11.2. Temporary Slopes 14 6.11.3. Slope Drainage 15 7.0 STRUCTURAL DESIGN RECOMMENDATIONS 15 7.1. Foundation Support Recommendations 15 7.1.1. Foundation Subgrade Preparation 16 7.1.2. Poaring Capacity Spread Factings	6 1 0	5.9.6. Retaining Wall Backfill	13
0.11. Slopes 14 6.11.1. Permanent Slopes 14 6.11.2. Temporary Slopes 14 6.11.3. Slope Drainage 15 7.0 STRUCTURAL DESIGN RECOMMENDATIONS 15 7.1. Foundation Support Recommendations 15 7.1.1. Foundation Subgrade Preparation 16 7.1.2. Pearing Capacity Spread Factings 16 16	6.10		11
0.11.1. Permanent Stopes 14 6.11.2. Temporary Slopes 14 6.11.3. Slope Drainage 15 7.0 STRUCTURAL DESIGN RECOMMENDATIONS 15 7.1. Foundation Support Recommendations 15 7.1.1. Foundation Subgrade Preparation 16 7.1.2. Poaring Capacity Spread Featings 16 16	0.11	S 11 1 Dermanent Slenec	14 17
6.11.2. Temporary Slopes 14 6.11.3. Slope Drainage 15 7.0 STRUCTURAL DESIGN RECOMMENDATIONS 15 7.1. Foundation Support Recommendations 15 7.1.1. Foundation Subgrade Preparation 16 7.1.2. Rearing Capacity Spread Factings 16 16	6	S 11 2 Temporary Slopes	14 1/
7.0 STRUCTURAL DESIGN RECOMMENDATIONS 15 7.1. Foundation Support Recommendations 15 7.1.1. Foundation Subgrade Preparation 16 7.1.2. Popring Capacity Spread Featings 16 16	(5.11.3. Slope Drainage	15
7.1. Foundation Support Recommendations 15 7.1.1. Foundation Subgrade Preparation 16 7.1.2. Rearing Capacity Spread Featings 16 16	7.0	STRUCTURAL DESIGN RECOMMENDATIONS	15
7.1.1. Foundation Subgrade Preparation	7.1	Foundation Support Recommendations	15
7.1.2 Poaring Canacity - Spread Eastings 16		7.1.1. Foundation Subgrade Preparation	16
1.1.2. Deaning Capacity - Spieau Fullings	-	7.1.2. Bearing Capacity – Spread Footings	16

7.1.4. Lateral Resistance 17
7.2. Drainage Considerations
7.3. Floor Slabs
7.4. Seismic Design
7.4.1. Liquefaction Potential
7.5. Retaining Walls 19
7.5.1. Drainage
7.5.2. Lateral Earth Pressures 19
8.0 OTHER CONSIDERATIONS
8.1. Frost Penetration
8.2. Expansive Soils 20
9.0 PAVEMENT RECOMMENDATIONS 21
9.1. Dynamic Cone Penetrometer (DCP) Testing
9.2. Asphalt Concrete (AC) Pavement Sections
10.0 DESIGN REVIEW AND CONSTRUCTION SERVICES
11.0 LIMITATIONS

LIST OF FIGURES

Figure 1. Vicinity Map Figure 2. Site Plan

APPENDICES

Appendix A. Field Explorations and Laboratory Testing
Figure A-1. Key to Exploration Logs
Figures A-2 through A-13. Logs of Borings
Figures A-14 and A-15. Logs of Dynamic Cone Penetrometer Testing
Figures A-16 through A-18. Atterberg Limits Test Results
Appendix B. Report Limitations and Guidelines for Use



1.0 INTRODUCTION

GeoEngineers, Inc. (GeoEngineers), is pleased to submit this geotechnical engineering report for the proposed Phase 2 of the Riverbend Neighborhood Center and Apartment Development located along the west side of Wallace Road NW at approximately 2501 Wallace Road NW in Salem, Oregon. Phase 2 of the Riverbend development is located adjacent to and north of Phase 1 of the same development constructed by Scott Martin Construction, Inc. Our understanding of the project is based on the preliminary master plan for proposed development provided to us by Steve Ward with Westech Engineering, Inc., as well as our previous work performed on Phase 1. The location of the site relative to the surrounding area is shown in the Vicinity Map, Figure 1.

Based on the information provided to us, we understand that the development will include neighborhood use (clubhouse type) and commercial structures, multi-family residential apartment structures, and associated parking areas, drive aisles and sidewalks. Two commercial structures are identified on the preliminary plan, consisting of a 7,600 square-foot (sf) retail building and a 7,600 sf live-work over retail building. Typical apartment structures are noted as three-story, wood-framed apartment buildings consistent with those of Phase 1 development. Paved areas include 283 parking stalls between the commercial and the residential structures and the drive aisles. We have also assumed that maximum cuts and fills will be less than 5 feet each and that on-site retaining walls will be less than 8 feet in height.

Our structural design recommendations are based on the following:

- For commercial buildings, we assumed that maximum column and wall loads will be on the order of 60 kips per column and 4 kips per lineal foot (klf) respectively, and that floor loads for slabs on grade will be 100 pounds per square foot (psf) or less.
- For apartments, we assumed typical light wood-frame structural loads, including column loads less than 30 kips, wall loads of 3 klf or less, and floor slab loads of 100 psf or less.

2.0 SCOPE OF SERVICES

The purpose of our services was to evaluate soil and groundwater conditions as a basis for developing geotechnical engineering design recommendations as well as a Geological Assessment in general accordance with the requirements of the City of Salem (City) Revised Code Chapter 810.030 (a) for the site.

Our proposed scope of services included the following:

- 1. Reviewed existing available subsurface soil and groundwater information, geologic maps and other available geotechnical engineering related information pertinent to the site.
- 2. Coordinated and managed the field investigation, including public utility notification and scheduling of subcontractors and GeoEngineers' field staff.
- 3. Explored subsurface soil and groundwater conditions at the site by drilling a total of 12 borings. Ten borings (B-1 and B-2, B-4, and B-6 through B-12) advanced within or near proposed apartment and commercial building footprints, each extending to a depth of 16½ to 21½ feet below ground surface (bgs), and two borings (B-3 and B-5) advanced in proposed paved and parking areas, extending to a



depth of 6½ feet bgs. Exploration locations are shown in the Site Plan, Figure 2. Logs of each exploration are provided in Appendix A.

- 4. Obtained samples at representative intervals from the explorations, observed groundwater conditions and maintained detailed logs in general accordance with ASTM International (ASTM) Standard Practices Test Method D 2488. Qualified staff from our office observed and documented field activities.
- Performed two infiltration tests (IT-1 and IT-2) at select locations at the project site as shown in Figure
 Infiltration testing was conducted as required by Division 004 of the *City of Salem Department of Public Works Administrative Rules Design Standards* (COSDS).
- 6. Performed laboratory tests on selected soil samples obtained from the explorations to evaluate pertinent engineering characteristics. Laboratory test results are included in the exploration logs in Appendix A.
- Performed a general geologic assessment of slopes at the site relative to existing stability and impact on proposed site development consistent with the requirements of Salem Revised Code (SRC) Chapter 810.030 (a).
- 8. Provided a geotechnical evaluation of the site and provided project-specific design recommendations in this geotechnical report that address the following geotechnical components:
 - a. A general description of site topography, geology and subsurface conditions.
 - b. An opinion as to the existing general stability of site slopes and conclusions regarding the effect of the existing geologic conditions on potential fill slope construction as performed in general accordance with our recommendations.
 - c. An opinion as to the adequacy of the proposed development from a geotechnical engineering standpoint.
 - d. Recommendations for site preparation measures, including disposition of undocumented fill and unsuitable native soils, recommendations for temporary cut slopes and constraints for wet weather construction.
 - e. Provide estimates of groundwater level and management recommendations.
 - f. Recommendations for temporary excavation and temporary excavation protection, such as excavation sheeting and bracing.
 - g. Recommendations for earthwork construction, including use of on-site and imported structural fill, and fill placement and compaction requirements.
 - h. Recommendations for use in designing conventional retaining walls up to 8 feet tall, including backfill and drainage requirements, and static and seismic lateral earth pressures.
 - i. Recommendations for shallow foundations to support the proposed structures, including minimum width and embedment, design soil bearing pressures, settlement estimates (total and differential), coefficient of friction and passive earth pressures for sliding resistance.
 - j. Recommendations for supporting on-grade slabs, including base rock, capillary break, and modulus of subgrade reaction.
 - k. Summary of infiltration testing and discussion of suitability of on-site infiltration facilities based on subsurface conditions.



- I. Seismic design parameters, including soil site class evaluation in accordance with the current version of the International Building Code (IBC).
- m. Recommendations for constructing asphaltic concrete (AC) pavements on-site, including subgrade, drainage, base rock, and pavement section.

Our geotechnical work has been directly supervised by a professional engineer licensed in the state of Oregon.

3.0 SITE CONDITIONS

3.1. Site Geology

The project site is located within the western edge of the Willamette Basin physiographic province in the lowermost foothills of the Eola Hills. The project site is located on a raised terrace west of Greene Creek, a second-order tributary of the Willamette River.

The "Geologic Map of the Rickreall and Salem West Quadrangles, Oregon" (Bela 1981) shows the site mantled by higher Pleistocene terrace deposits. This alluvial sediment is described as "semiconsolidated... sand, silt, and clay." The topography of the site and our field investigation suggests that the near-surface site geology is generally consistent with published geologic mapping.

3.2. Surface Conditions

The proposed new development is located on an approximate 7-acre property consisting of a group of several residential properties with existing house and barn and related structures, driveways, fencing, trees, and open grass fields. The property gently slopes from the west at approximate Elevation 180 feet North American Vertical Datum of 1988 (NAVD88) to the east at Wallace Road NW at approximate Elevation 160 feet NAVD88.

3.3. Slope Conditions

A general geologic assessment of slopes at the site relative to existing stability and impact on proposed site development consistent with the requirements of SRC, Chapter 810.030 (a) was performed. We performed a visual geologic reconnaissance on November 5, 2020, to observe existing slope conditions. Site topography generally slopes down to the east, while the ground surface is typically undulatory to gently sloping, with maximum gradients typically less than 5H:1V (horizontal to vertical) to as low as 30H:1V or flatter.

The interior site slopes appear planar to convex and regular. We did not observe indications of large, deeply seated, recent or active slope instability such as concave, steeply inclined bare-soil scarps, bulging or hummocky topography, anomalous drainage features or vegetation.

Light Detection and Ranging (LiDAR) landslide hazard mapping has not been completed for the West Salem area. The Oregon State Landslide Information Layer (SLIDO) (DOGAMI 2017) shows a portion of the southernmost edge and northern corner of the site within the "moderate – landslide possible" hazard zone. The SLIDO legend does not provide a mapped source of this supposed hazard and our observations do not support the SLIDO classification.



3.4. Subsurface Conditions

We completed field explorations at the project site on November 5 and 6, 2020. Our explorations included 12 drilled borings (B-1 through B-12) to depths of between $6\frac{1}{2}$ to $21\frac{1}{2}$ feet bgs, two infiltration tests (IT-1 and IT-2) at depths of $2\frac{1}{2}$ and 3 feet bgs, respectively, and two dynamic cone penetrometer (DCP) readings (DCP-1 and DCP-2) to depths ranging from 24 to 61 inches bgs. A member of our professional staff maintained detailed logs of the soils encountered, test results collected, and gathered representative soil samples. A summary of our exploration methods as well as the boring logs, DCP test logs and infiltration test logs can be found in Appendix A. Laboratory test results are also provided in the boring logs and described in Appendix A. The approximate locations of the explorations are shown in Figure 2.

The upper approximately 20 feet of the subsurface primarily consists of gray and brown silt to sandy silt that was observed to be generally medium stiff to very stiff with sand content decreasing with depth. Drilling was terminated within the medium stiff to very stiff silt to sandy silt layer in all but three of the borings (B-2, B-9, and B-10). Borings B-2, B-9, and B-10 were each drilled to a depth of 21½ feet and are located in the eastern half of the project site where a coarser grained soil layer was encountered below a depth of approximately 20 feet. Near the bottom of each of the three borings a gray poorly graded sand and gravel layer that was observed to be dense to very dense was encountered. All three borings were terminated within the dense to very dense poorly graded sand and gravel layer at a depth of 21½ feet. The reader is referred to the exploration logs for more detailed information about the soils encountered in the explorations.

3.5. Groundwater

Groundwater was not encountered during drilling; however, due to increasing moisture content and condition of soil samples, it could be inferred that groundwater is present at or just below the maximum depth drilled of $21\frac{1}{2}$ feet bgs. Explorations were conducted at the end of the dry weather cycle. Groundwater elevations will be shallower after prolonged periods of wet weather and may be as shallow as 10 to 12 feet bgs.

Also, groundwater may be present at relatively shallow depths in a perched or capillary condition during wet times of the year or during extended periods of wet weather. Groundwater conditions at the site are expected to vary seasonally due to rainfall events and other factors not observed in our explorations.

4.0 CONCLUSIONS

4.1. General

Based on our explorations, testing and analyses, it is our opinion that the site is suitable for the proposed project from a geotechnical standpoint, provided the recommendations in this report are included in design and construction. We offer the following summary of conclusions regarding geotechnical design at the site.

Groundwater was not encountered in the upper 21½ feet bgs during drilling. However, based on our experience and our observations, perched groundwater may be present during periods of persistent rainfall and may be as shallow as 10 to 12 feet bgs near the end of a wet cycle of weather. Perched groundwater conditions may require dewatering of trenches or deeper excavations by use of sumps during construction and site grading.



- Surface conditions at the site consist primarily of several residential properties with existing house and barn and related structures, driveways, fencing, trees, and open grass fields; therefore, stripping and demolition will be required in all proposed development areas. We anticipate a stripping depth of approximately 6 inches bgs to remove the grass roots. Grubbing and deeper excavations up to several feet will be required to remove the root zones of shrubs and trees. Existing structures should be demolished and removed from the site and existing utilities should be abandoned in-place or removed from the site.
- Minimal (near zero) rates of infiltration were measured during the testing period. The water level in IT-1, left to infiltrate overnight, declined approximately 0.75 inch in 15 hours, or approximately 0.05 inch/hour (in/hr). In general, soils with infiltration rates less than 2 in/hr are not well suited as the sole means of stormwater disposal for sites.
- Typical infiltration facilities require at least 5 feet of separation between the base of the facility and the seasonal high groundwater level. Groundwater was not encountered at depths of at least 21¹/₂ feet bgs.
- On-site near surface soils generally consist of silt. The silty soil will become significantly disturbed when trafficked during earthwork, particularly when construction traffic over the site occurs during periods of wet weather or when the moisture content of the soil is more than a few percentage points above optimum. Wet weather construction practices will be required over exposed native soils unless earthwork occurs during the dry summer months (typically mid-July to mid-September).
- Proposed structures can be satisfactorily supported on continuous and isolated shallow foundations supported on medium stiff to very stiff native soils or on structural fill that extends to native soil.
- For proposed commercial structures, our foundation recommendations are based on maximum anticipated loads of 60 kips or less for columns, 4 klf or less for walls, and floor loads of 100 psf or less. Based on these design loads, we estimate total settlement to be less than 1 inch. If larger structural loads are anticipated, we should review and reassess the estimated settlement.
- For proposed apartment structures, our foundation recommendations are based on maximum anticipated loads of 30 kips or less for columns, 3 klf or less for walls, and floor loads of 100 psf or less. Based on these design loads, we estimate total settlement to be less than 1 inch. If larger structural loads are anticipated, we should review and reassess the estimated settlement.
- Fill material encountered at subgrade elevation should be evaluated by GeoEngineers during construction. Soft fill or fill with significant debris or unsuitable material should be removed to native stiff or firmer material and replaced with compacted structural fill.
- Slabs-on-grade will be satisfactorily supported on medium stiff to very stiff native soils with a minimum 6-inch-thick layer of compacted crushed rock base overlying approved subgrade or on structural fill over medium stiff to stiff native soils.
- Standard pavement sections prepared as described in this report will suitably support the estimated traffic loads provided the site subgrade is prepared as recommended.



5.0 INFILTRATION TESTING

5.1. General

As is typical for development projects in the Salem area, we conducted infiltration tests on site to assist in evaluation of the site for potential stormwater infiltration design. We conducted two infiltration tests, at depths of 3 and $2\frac{1}{2}$ feet bgs; one (IT-1) in the northeast portion of the site near boring B-5, the other (IT-2) near the south property boundary about 250 feet west of the edge of the Wallace Road right-of-way. This is a typical depth for consideration of stormwater disposal.

Testing was conducted using the encased falling head procedure consistent with the method outlined in "Division 004" of the COSDS. A 2- to 3-inch-thick layer of pea gravel was placed in the pipes prior to adding water to diminish disturbance from flowing water at the base of the pipe interior. The test areas were presoaked over a 4-hour period by repeated addition of water into the pipe when necessary. Based on observations, a good seal was present between the base of the pipe and the underlying soil.

After the saturation period, both pipes were filled with clean water to at least 1 foot above the bottom of the pipe placed in the boring. The water level was then monitored over three, 1-hour iterations. In the case where water levels fall during the time-measured testing, infiltration rates diminish as a result of less head from the water column in the test.

Both test locations showed a minimal measurable decline in head during the saturation or the three, 1-hour test periods. Therefore IT-1 was left to infiltrate overnight; approximately 15 hours later the water level was 0.75 inches lower than the final test reading, yielding an infiltration rate of roughly 0.05 in/hr.

Field test results are summarized in Table 1.

TABLE 1. INFILTRATION RESULTS

Infiltration Test No.	Location	Depth (feet)	USCS Material Type	Field Measured Infiltration Rate ¹ (inches/hour)
IT-1	East-central area of site (near B-5)	3	ML	0.05 (see above)
IT-2	Southeast area of site	2.5	ML	0.0 ²

Notes:

¹ Appropriate factors should be applied to the field-measured infiltration rate, based on the design methodology and specific system. ² Measured rate not perceptible over 3-hour test period. Likely similar to rate noted for IT-1 in long-term observation.

USCS = Unified Soil Classification System

Infiltration rates shown in Table 1 are field-measured rates and represent a relatively short-term measured rate. It is likely that IT-2 has some amount of infiltration, it is just not measurable in the test time window. Further, for matters of facility design, factors of safety have not been applied for the type of infiltration system being considered, or for variability that may be present in the on-site soil. In our opinion, and consistent with the state of the practice, correction factors should be applied to this measured rate to reflect the small area of testing and the number of tests conducted. Correction factors to minimal amounts would result in even lower rates for design, effectively resulting in a zero rate of infiltration.

Actual depths, lateral extent, and estimated infiltration rates can vary from the values presented above. Field testing/confirmation during construction is often required in large or long systems or other situations where soil conditions may vary within the area where the system is constructed. The results of this field-testing during construction may yield a higher rate of infiltration for the overall area, but would require modifying the system design for higher rates.

Even in the best of circumstances. the infiltration flow rate of a focused stormwater system typically diminishes over time as suspended solids and precipitates in the stormwater slowly clog the void spaces between soil particles or cake on the infiltration surface. The serviceable life of a stormwater system can be extended by pre-filtering or with on-going accessible maintenance. Eventually, most systems will fail and will need to be replaced or have media regenerated or replaced. We recommend that infiltration systems include an overflow that is connected to a suitable discharge point. Also, infiltration systems can cause localized high groundwater levels and should not be located near basement walls, retaining walls, or other embedded structures unless these are specifically designed to account for resulting hydrostatic pressure. Infiltration locations should not be located on or adjacent to sloping ground, unless it is approved by the project geotechnical engineer of record, and should not be infiltrated at a location that allows for flow to travel laterally toward a slope face, such as a mounded water condition or too near the slope face.

5.2. Suitability of Infiltration System

Successful design and implementation of stormwater infiltration systems, and whether a system is suitable for a development depend on several site-specific factors. Stormwater infiltration systems are generally best suited for sites having sandy or gravelly soil with saturated hydraulic conductivities greater than 2 in/hr. Sites with silty or clayey soil, including sites with fine sand, silty sand such as at the upper portions of this site, or gravel with a high percentage of silt or clay in the matrix are generally not well suited for stormwater infiltration. Soil that has higher fine-grained matrices is susceptible to volumetric change and softening during wetting and drying cycles. Fine-grained soil also has large variations in the magnitude of infiltration rates because of bedding and stratification that occurs during deposition and often has thin layers of less permeable or impermeable soil within a larger layer.

As a result of fine-grained soil conditions and relatively low measured infiltration rates, we recommend infiltration of stormwater not be used in the upper soils, or at the very least not be used as the sole method of stormwater management at this site unless those design factors can be otherwise accounted for by increasing infiltration area or coupling with other methods of stormwater disposal. At a minimum, an overflow method should be provided for the overall system.

6.0 EARTHWORK RECOMMENDATIONS

6.1. Site Preparation

In general, site preparation and earthwork for site development will include demolition of existing residential and farm structures, excavation for removal of existing tree and tree root removal, stripping and grubbing, grading the site and excavating for utilities and foundations, and may also include removal or relocation of existing site utilities where present beneath proposed buildings.

6.1.1. Demolition

Existing structures, or remnants of structures or other debris should be demolished and removed from the site. If present, existing utilities that will be abandoned on site should be identified prior to project construction. Abandoned utility lines beneath proposed structural areas should be completely removed or filled with grout if abandoned and left in-place in order to reduce potential settlement or caving in the future. Materials generated during demolition of existing utilities should be transported off site for disposal.

Existing voids and new depressions created due to removal of existing utilities, or other subsurface elements, should be cleaned of loose soil or debris down to firm soil and backfilled with compacted structural fill. Disturbance to a greater depth should be expected if site preparation and earthwork are conducted during periods of wet weather.

6.1.2. Stripping and Grubbing

Based on our observations at the site, we estimate that the depth of stripping of on-site organics in wild grass-covered areas will be on the order of about 6 inches. Greater stripping depths may be required to remove localized zones of loose or organic soil, and in areas where moderate to heavy vegetation may be present, or surface disturbance has occurred. In addition, if present in areas of proposed development, the primary root systems of trees should be completely removed. Stripped material should be transported off site for disposal or processed and used as fill in landscaping areas.

Where encountered, trees and their root balls should be grubbed to the depth of the roots, which could exceed 3 feet bgs. Depending on the methods used to remove the preceding material, considerable disturbance and loosening of the subgrade could occur. We recommend that disturbed soil be removed to expose stiff native soil. The resulting excavations should be backfilled with structural fill.

6.2. Subgrade Preparation and Evaluation

Upon completion of site preparation activities, exposed subgrades that are to receive fill should be compacted in-place prior to fill placement due to the presence of a tilled zone that extends to depths of approximately 12 inches bgs in open areas of the project site. If site grading extends to below these depths, and to the native in-place (non-tilled) soils, compaction of in-place subgrade is not required.

Exposed subgrades should be proof-rolled with a fully loaded dump truck or similar heavy rubber-tired construction equipment, where space allows, to identify soft, loose or unsuitable areas. Probing may be used for evaluating smaller areas or where proof-rolling is not practical. Proof-rolling and probing should be conducted prior to placing fill, and should be performed by a representative of GeoEngineers who will evaluate the suitability of the subgrade and identify areas of yielding that are indicative of soft or loose soil. If soft or loose zones are identified during proof-rolling or probing, these areas should be excavated to the extent indicated by our representative and replaced with structural fill.

As discussed in Section 4.1 of this report, the native fine-grained, silty soil can be sensitive to small changes in moisture content and will be difficult, if not impossible, to compact adequately during wet weather. While tilling and compacting the subgrade is the economical method for subgrade improvement, it will likely only be possible during extended dry periods and following moisture conditioning of the soil.

During wet weather, or when the exposed subgrade is wet or unsuitable for proof-rolling, the prepared subgrade should be evaluated by observing excavation activity and probing with a steel foundation probe.



Observations, probing, and compaction testing should be performed by a member of our staff. Wet soil that has been disturbed due to site preparation activities or soft or loose zones identified during probing should be removed and replaced with compacted structural fill.

6.3. Subgrade Protection and Wet Weather Considerations

The upper fine-grained soils at the site are highly susceptible to moisture. Wet weather construction practices will be necessary if work is performed during periods of wet weather. If site grading will occur during wet weather conditions, it will be necessary to use track-mounted equipment, load material into trucks supported on gravel work pads and employ other methods to reduce ground disturbance. The contractor should be responsible to protect the subgrade during construction, reflective of their proposed means and methods and time of year.

Earthwork planning should include considerations for minimizing subgrade disturbance. The following recommendations can be implemented if wet weather construction is considered:

- The ground surface in and around the work area should be sloped so that surface water is directed to a sump or discharge location. The ground surface should be graded such that areas of ponded water do not develop. Measures should be taken by the contractor to prevent surface water from collecting in excavations and trenches. Measures should be implemented to remove surface water from the work area.
- Earthwork activities should not take place during periods of heavy precipitation.
- Slopes with exposed soils should be covered with plastic sheeting or similar means.
- The site soils should not be left uncompacted and exposed to moisture. Sealing the surficial soils by rolling with a smooth-drum roller prior to periods of precipitation will reduce the extent to which these soils become wet or unstable.
- Construction activities should be scheduled so that the length of time that soils are left exposed to moisture is reduced to the extent practicable.
- Construction traffic should be restricted to specific areas of the site, preferably areas that are surfaced with working pad materials not susceptible to wet weather disturbance such as haul roads and rocked staging areas.
- When on-site fine-grained soils are wet of optimum, they are easily disturbed and will not provide adequate support for construction traffic or the proposed development. The use of granular haul roads and staging areas will be necessary for support of construction traffic. Generally, a 12- to 16-inch-thick mat of imported granular base rock aggregate material is sufficient for light staging areas for building pad and light staging activities but is not expected to be adequate to support repeated heavy equipment or truck traffic. The granular mat for haul roads and areas with repeated heavy construction traffic should be increased to between 18 and 24 inches. The actual thickness of haul roads and staging areas should be based on the contractor's approach to site development, and the amount and type of construction traffic.
- During periods of wet weather, concrete should be placed as soon as practical after preparation of the footing excavations. Foundation bearing surfaces should not be exposed to standing water. If water collects in the excavation, it should be removed before placing structural fill or reinforcing steel.



Subgrade protection for foundations consisting of a lean concrete mat may be necessary if footing excavations are exposed to extended wet weather conditions.

The base rock (Aggregate Base and Aggregate Subbase) thicknesses described in Section 9.0 of this report is intended to support post-construction design traffic loads. The design base rock thicknesses will likely not support repeated heavy construction traffic during site construction, or during pavement construction. A thicker base rock section, as described above for haul roads, will likely be required to support construction traffic.

During wet weather, or when the exposed subgrade is wet or unsuitable for proof-rolling, the prepared subgrade should be evaluated by observing excavation activity and probing with a steel foundation probe. Observations, probing and compaction testing should be performed by a member of our staff. Wet soil that has been disturbed due to site preparation activities or soft or loose zones identified during probing should be removed and replaced with compacted structural fill.

6.4. Cement Treated Subgrade Design

These recommendations are included as a potential alternative to the use of imported granular material for wet weather structural fill provided areas being graded or developed make the cement treating process a feasible option.

An experienced contractor may be able to amend the on-site soil with portland cement to obtain suitable support properties. Successful use of soil amendment depends on the use of correct mixing techniques, soil moisture content and amendment quantities. Specific recommendations, based on exposed site conditions, for soil amending can be provided if necessary. However, for preliminary planning purposes, it may be assumed that a minimum of 5 percent cement (by dry weight, assuming a unit weight of 100 pounds per cubic foot [pcf]) will be sufficient for subgrade and general fill amendment. Treatment depths of 12 to 16 inches for roadway subgrades are typical (assuming a seven-day unconfined compressive strength of at least 80 pounds per square inch [psi]), though they may be adjusted in the field depending on site conditions. Soil amending should be conducted in accordance with the specifications provided in Oregon Structural Specialty Code 00344 (Treated Subgrade).

Portland cement-amended soil is hard and has low permeability; therefore, this soil does not drain well nor is it suitable for planting. Future landscape areas should not be cement amended, if practical, or accommodations should be planned for drainage and planting. Cement amendment should not be used if runoff during construction cannot be directed or drained away from areas that would be negatively affected by runoff from the amended surface, including adjacent building foundations, low-lying wet areas or active waterways, and area drainage paths.

We recommend a target strength for cement-amended soils of 80 psi. The amount of cement used to achieve this target generally varies with moisture content and soil type. It is difficult to predict field performance of soil to cement amendment due to variability in soil response, and we recommend laboratory testing to confirm expectations. However, for preliminary design purposes, 4 to 5 percent cement by weight of dry soil can generally be used when the soil moisture content does not exceed approximately 25 percent. If the soil moisture content is in the range of 25 to 35 percent, 5 to 7 percent by weight of dry soil is recommended. The amount of cement added to the soil may need to be adjusted based on field observations and performance.



When used for construction of pavement, staging, or haul road subgrades, the amended surface should be protected from abrasion by placing a minimum 4-inch thickness of crushed rock. To prevent strength loss during curing, cement-amended soil should be allowed to cure for a minimum of four days prior to placing the crushed rock. The crushed rock may typically become contaminated with soil during construction. Contaminated base rock should be removed and replaced with clean rock in pavement areas such that the minimum thickness of free-draining base at the surface is 4 inches.

It is not possible to amend soil during heavy or continuous rainfall. Work should be completed during suitable conditions.

6.5. Excavation

Based on the materials encountered in our subsurface exploration, it is our opinion that conventional earthmoving equipment in proper working condition should be capable of making necessary general excavations.

The earthwork contractor should be responsible for reviewing this report, including the boring logs, providing their own assessments, and providing equipment and methods needed to excavate the site soils while protecting subgrades.

6.6. Dewatering

As discussed in Section 3.5 of this report, groundwater was not encountered during drilling in the upper 21½ feet at the site. We do not anticipate excavations to extend below this depth. However, if excavations do extend into saturated/wet soils they should be dewatered. Sump pumps are expected to adequately address groundwater encountered in shallow excavations. Deeper excavations may require more intensive or filtered dewatering or use of well points. Deeper excavations that extend below groundwater into sandier soils (encountered below depths of 15 feet bgs) may be difficult to dewater with conventional sumps because inflow of water may promote a "running soils" condition into excavations, where sandy material flows in with seeping groundwater. For deep excavations or where running soils are encountered, dewatering from well points would likely be required to maintain an open and workable trench.

In addition to groundwater seepage and upward confining flow, surface water inflow to the excavations during the wet season can be problematic. Provisions for surface water control during earthwork and excavations should be included in the project plans and should be installed prior to commencing earthwork.

6.7. Trench Cuts and Trench Shoring

All trench excavations should be made in accordance with applicable Occupational Safety and Health Administration (OSHA) and state regulations. Site soils within expected excavation depths typically range from medium stiff to stiff silt. In our opinion, native soils are generally OSHA Type B, provided there is no seepage and excavations occur during periods of dry weather. Excavations deeper than 4 feet should be shored or laid back at an inclination of 1H:1V for Type B soils. Flatter slopes may be necessary if workers are required to enter. Excavations made to construct footings or other structural elements should be laid back or shored at the surface as necessary to prevent soil from falling into excavations.

Shoring for trenches less than 6 feet deep that are above the effects of groundwater should be possible with a conventional box system. Slight to moderate sloughing should be expected outside the box. Shoring



deeper than 6 feet or below the groundwater table should be designed by a registered engineer before installation. Further, the shoring design engineer should be provided with a copy of this report.

In our opinion, the contractor will be in the best position to observe subsurface conditions continuously throughout the construction process and to respond to the soil and groundwater conditions. Construction site safety is generally the sole responsibility of the contractor, who also is solely responsible for the means, methods and sequencing of the construction operations and choices regarding excavations and shoring. Under no circumstances should the information provided by GeoEngineers be interpreted to mean that GeoEngineers is assuming responsibility for construction site safety or the contractor's activities; such responsibility is not being implied and should not be inferred.

6.8. Erosion Control

Erosion control plans are required on construction projects located within Marion County in accordance with Oregon Administrative Rules (OAR) 340-41-006 and 340-41-455 and City regulations. Measures that can be employed to reduce erosion include the use of silt fences, hay bales, buffer zones of natural growth, sedimentation ponds and granular haul roads.

6.9. Structural Fill and Backfill

6.9.1. General

Structural areas include areas beneath foundations, floor slabs, pavements, and any other areas intended to support structures or within the influence zone of structures, should generally meet the criteria for structural fill presented below. All structural fill soils should be free of debris, clay balls, roots, organic matter, frozen soil, man-made contaminants, particles with greatest dimension exceeding 4 inches (3-inch maximum particle size in building footprints) and other deleterious materials. The suitability of soil for use as structural fill will depend on the gradation and moisture content of the soil. As the amount of fines in the soil matrix increases, the soil becomes increasingly more sensitive to small changes in moisture content and achieving the required degree of compaction becomes more difficult or impossible. Recommendations for suitable fill material are provided in the following sections.

6.9.2. On-Site Soils

On-site near-surface soil consists of native silt to sandy silt. On-site soils can be used as structural fill, provided the material meets the above requirements, although due to moisture sensitivity, this material will likely be unsuitable as structural fill during most of the year. If the soil is too wet to achieve satisfactory compaction, moisture conditioning by drying back the material will be required. If the material cannot be properly moisture conditioned, we recommend using imported material for structural fill.

An experienced geotechnical engineer from GeoEngineers should determine the suitability of on-site soil encountered during earthwork activities for reuse as structural fill.

6.9.3. Imported Select Structural Fill

Select imported granular material may be used as structural fill. The imported material should consist of pit or quarry run rock, crushed rock, or crushed gravel and sand that is fairly well-graded between coarse and fine sizes (approximately 25 to 65 percent passing the U.S. No. 4 sieve). It should have less than 5 percent passing the U.S. No. 200 sieve and have a minimum of 75 percent fractured particles according to American Association of State Highway and Transportation Officials (AASHTO) TP-61.



6.9.4. Aggregate Base

Aggregate base material located under floor slabs and pavements and crushed rock used in footing overexcavations should consist of imported clean, durable, crushed angular rock. Such rock should be well-graded, have a maximum particle size of 1 inch and have less than 5 percent passing the U.S. No. 200 sieve (3 percent for retaining walls), and meet the gradation requirements in Table 2. In addition, aggregate base shall have a minimum of 75 percent fractured particles according to AASHTO TP-61 and a sand equivalent of not less than 30 percent based on AASHTO T-176.

Sieve Size	Percent Passing (by weight)
1 inch	100
1/2 inch	50 to 65
No. 4	40 to 60
No. 40	5 to 15
No. 200	0 to 5

TABLE 2. RECOMMENDED GRADATION FOR AGGREGATE BASE

6.9.5. Trench Backfill

Backfill for pipe bedding and in the pipe zone should consist of well-graded granular material with a maximum particle size of ³/₄ inch and less than 5 percent passing the U.S. No. 200 sieve. The material should be free of organic matter and other deleterious materials. Further, the backfill should meet the pipe manufacturer's recommendations. Above the pipe zone backfill, Imported Select Structural Fill may be used as described above.

6.9.6. Retaining Wall Backfill

Fill placed to provide a drainage zone behind retaining walls should meet the general requirements above and consist of free-draining sand and gravel or crushed rock with a maximum particle size of ³/₄ inch and less than 3 percent passing the U.S. No. 200 sieve.

6.10. Fill Placement and Compaction

Structural fill should be compacted at moisture contents that are within 3 percent of the optimum moisture content as determined by ASTM Test Method D 1557 (Modified Proctor). The optimum moisture content varies with gradation and should be evaluated during construction. Fill material that is not near the optimum moisture content should be moisture conditioned prior to compaction.

Fill and backfill material should be placed in uniform, horizontal lifts, and compacted with appropriate equipment. The appropriate lift thickness will vary depending on the material and compaction equipment used. Fill material should be compacted in accordance with Table 3, below. It is the contractor's responsibility to select appropriate compaction equipment and place the material in lifts that are thin enough to meet these criteria. However, in no case should the loose lift thickness exceed 18 inches.



TABLE 3. COMPACTION CRITERIA

	Compaction Requirements		
Fill Type	Percent Maximum Dry Density Determined by ASTM Test Method D 1557 at \pm 3% of Optimum Moisture		
	0 to 2 Feet Below Subgrade	> 2 Feet Below Subgrade	Pipe Zone
Fine-grained soils (non-expansive)	92	92	
Imported Granular, maximum particle size < 1¼ inch	95	95	
Imported Granular, maximum particle size 1¼ inch to 4 inches (3-inch maximum under building footprints)	n/a (proof-roll)	n/a (proof-roll)	
Retaining Wall Backfill*	92	92	
Nonstructural Zones	90	90	90
Trench Backfill	95	90	90

Note:

* Measures should be taken to prevent overcompaction of the backfill behind retaining walls. We recommend placing the zone of backfill located within 5 feet of the wall in lifts not exceeding about 6 inches in loose thickness and compacting this zone with hand-operated equipment such as a vibrating plate compactor and a jumping jack.

A representative from GeoEngineers should evaluate compaction of each lift of fill. Compaction should be evaluated by compaction testing unless other methods are proposed for oversized materials and are approved by GeoEngineers during construction. These other methods typically involve procedural placement and compaction specifications together with verifying requirements such as proof-rolling.

6.11. Slopes

6.11.1. Permanent Slopes

Permanent cut or fill slopes should not exceed a gradient of 2H:1V. Where access for landscape maintenance is desired, we recommend a maximum gradient of 3H:1V. Fill slopes should be overbuilt by at least 12 inches and trimmed back to the required slope to maintain a firm face.

Slopes should be planted with appropriate vegetation to provide protection against erosion as soon as possible after grading. Surface water runoff should be collected and directed away from slopes to prevent water from running down the face of the slope.

6.11.2. Temporary Slopes

All temporary soil cuts associated with site excavations (greater than 4 feet in depth) should be adequately sloped back to prevent sloughing and collapse, in accordance with applicable OSHA and state guidelines.

Temporary cut slopes should not exceed a gradient appropriate for the soil type being excavated. As noted in Section 6.7, medium stiff to very stiff silt soils should be considered OSHA Soil Type B. However, because of the variables involved, actual slope angles required for stability in temporary cut areas can only be estimated before construction.



The stability and safety of cut slopes depend on a number of factors, including:

- The type and density of the soil.
- The presence and amount of any seepage.
- Depth of cut.
- Proximity and magnitude of the cut to any surcharge loads, such as stockpiled material, traffic loads or structures.
- Duration of the open excavation.
- Care and methods used by the contractor.

We recommend that stability of the temporary slopes used for construction be the responsibility of the contractor, since the contractor is in control of the construction operation and is continuously at the site to observe the nature and condition of the subsurface. If groundwater seepage is encountered within the excavation slopes, the cut slope inclination may have to be flatter than 1.5H:1V. However, appropriate inclinations will ultimately depend on the actual soil and groundwater seepage conditions exposed in the cuts at the time of construction. It is the responsibility of the contractor to ensure that the excavation is properly sloped or braced for worker protection, in accordance with applicable guidelines. To assist with this effort, we make the following recommendations regarding temporary excavation slopes:

- Protect the slope from erosion with plastic sheeting for the duration of the excavation to minimize surface erosion and raveling.
- Limit the maximum duration of the open excavation to the shortest time period possible.
- Place no surcharge loads (equipment, materials, etc.) within 10 feet of the top of the slope.

More restrictive requirements may apply depending on specific site conditions, which should be continuously assessed by the contractor.

If temporary sloping is not feasible based on site spatial constraints, excavations could be supported by internally braced shoring systems, such as a trench box or other temporary shoring. There are a variety of options available. We recommend that the contractor be responsible for selecting the type of shoring system to apply.

6.11.3. Slope Drainage

If seepage is encountered at the face of permanent or temporary slopes, it will be necessary to flatten the slopes or install a subdrain to collect the water. We should be contacted to evaluate such conditions on a case-by-case basis.

7.0 STRUCTURAL DESIGN RECOMMENDATIONS

7.1. Foundation Support Recommendations

Proposed structures can be satisfactorily founded on continuous strip or isolated column footings supported on firm native soils, or on structural fill placed over native soils. Exterior footings should be



established at least 18 inches below the lowest adjacent grade. The recommended minimum footing depth is greater than the anticipated frost depth. Interior footings can be founded a minimum of 12 inches below the top of the floor slab. Isolated column and continuous wall footings should have minimum widths of 24 and 18 inches, respectively. For the proposed commercial structures, we have assumed that the maximum isolated column loads will be on the order of 60 kips, wall loads will be 4 klf or less and floor loads for slabs-on-grade will be 100 psf or less for the proposed development. For the proposed apartment structures, we have assumed that the maximum isolated column loads for slabs-on-grade will be 3 klf or less and floor loads for slabs-on-grade will be 3 klf or less and floor loads for slabs-on-grade will be 3 klf or less and floor loads for slabs-on-grade will be 100 psf or less. If design loads exceed these values, we should be notified as our recommendations may need to be revised.

7.1.1. Foundation Subgrade Preparation

We recommend that prepared subgrades be observed by a member of our firm, who will evaluate the suitability of the subgrade and identify any areas of yielding, which are indicative of soft or loose soil. The exposed subgrade soil should be probed with a ½-inch-diameter steel rod. If soft, yielding or otherwise unsuitable areas are revealed during probing the unsuitable soils should be removed and replaced with structural fill, as needed.

Fill material encountered at subgrade elevation should be evaluated by GeoEngineers during construction. Soft fill or fill with significant debris or unsuitable material should be removed to native medium stiff or stiffer material and replaced with compacted structural fill. The width of the overexcavation should extend beyond the edge of the footing a distance equal to the depth of the overexcavation below the base of the footing.

We recommend loose or disturbed soils be removed before placing reinforcing steel and concrete. Foundation bearing surfaces should not be exposed to standing water. If water infiltrates and pools in the excavation, the water, along with any disturbed soil, should be removed before placing reinforcing steel. A thin layer (2 to 3 inches) of crushed rock can be used to provide protection to the subgrade from light foot traffic. Compaction should be performed as described in Section 6.10.

We recommend GeoEngineers observe all foundation excavations before placing concrete forms and reinforcing steel to determine that bearing surfaces have been adequately prepared and the soil conditions are consistent with those observed during our explorations.

7.1.2. Bearing Capacity – Spread Footings

We recommend conventional footings be proportioned using a maximum allowable bearing pressure of 2,500 psf if supported on medium stiff or stiffer native silt or structural fill bearing on these materials. The recommended bearing pressure applies to the total of dead and long-term live loads and may be increased by one-third when considering earthquake or wind loads. This is a net bearing pressure. The weight of the footing and overlying backfill can be ignored in calculating footing sizes.

7.1.3. Foundation Settlement

Foundations designed and constructed as recommended are expected to experience settlements of less than 1 inch. Differential settlements of up to one half of the total settlement magnitude can be expected between adjacent footings supporting comparable loads.

7.1.4. Lateral Resistance

Lateral loads on footings can be resisted by passive earth pressures on the sides of footings and by friction on the bearing surface. We recommend that passive earth pressures be calculated using an equivalent fluid unit weight of 250 pcf for foundations confined by native medium stiff or stiffer silt and 400 pcf if confined by a minimum of 2 feet of imported granular fill.

We recommend using a friction coefficient of 0.38 for foundations placed on the native medium stiff or stiffer silt, or 0.48 for foundations placed on a minimum 1-foot thickness of compacted crushed rock. The passive earth pressure and friction components may be combined provided the passive component does not exceed two-thirds of the total.

The passive earth pressure value is based on the assumptions that the adjacent grade is level and static groundwater remains below the base of the footing throughout the year. The top 1 foot of soil should be neglected when calculating passive lateral earth pressures unless the adjacent area is covered with pavement or slab-on-grade. The lateral resistance values include a safety factor of approximately 1.5.

7.2. Drainage Considerations

We recommend the ground surface be sloped away from the buildings at least 2 percent. All downspouts should be tightlined away from the building foundation areas and should also be discharged into a stormwater disposal system. Downspouts should not be connected to footing drains.

Although not required based on expected groundwater depths, if perimeter footing drains are used for below-grade structural elements or crawlspaces, they should be installed at the base of the exterior footings. If used, perimeter footing drains should be provided with cleanouts and should consist of at least 4-inch-diameter perforated pipe placed on a 3-inch bed of, and surrounded by, 6 inches of drainage material enclosed in a non-woven geotextile such as Mirafi 140N (or approved equivalent) to prevent fine soil from migrating into the drain material. We recommend against using flexible tubing for footing drainpipes. The perimeter drains should be sloped to drain by gravity to a suitable discharge point, preferably a storm drain. We recommend that the cleanouts be covered and placed in flush-mounted utility boxes. Water collected in roof downspout lines must not be routed to the footing drain lines.

If an elevator pit or utility vaults or other subterranean open structural elements are installed below the expected level of groundwater, we recommend foundation drains be installed as described above. Active dewatering or tightline routing of draining water will be required during wet times of the year at these locations in order to provide a removal pathway.

7.3. Floor Slabs

Satisfactory subgrade support for floor slabs supporting up to 100 psf floor loads can be obtained provided the floor slab subgrade is as described in Section 6.2 of this report. Slabs should be reinforced according to their proposed use and per the structural engineer's recommendations. Subgrade support for concrete slabs can be obtained from the medium stiff or stiffer native soils. We recommend that on-grade slabs be underlain by a minimum 6-inch-thick compacted crushed rock base section to reduce the potential for moisture migration into the slab and to provide structural support as noted below. The crushed rock base material should consist of Aggregate Base material as described Section 6.9 of this report. The material should be placed as recommended in Section 6.10.
If dry slabs are required (e.g., where moisture-sensitive adhesives are used to anchor carpet or tile to the slab), a waterproof liner may be placed as a vapor barrier below the slab. The vapor barrier should be selected by the structural engineer and should be accounted for in the design floor section and mix design selection for the concrete, to accommodate the effect of the vapor barrier on concrete slab curing. Load-bearing concrete slabs should be designed assuming a modulus of subgrade reaction (k) of 125 psi per inch. We estimate that concrete slabs constructed as recommended will settle less than ½ inch. We recommend that the floor slab subgrade be evaluated by proof-rolling prior to placing concrete.

7.4. Seismic Design

Parameters provided in Table 4 are based on the conditions encountered during our subsurface exploration program and the procedure outlined in the 2018 IBC, which references the 2016 Minimum Design Loads for Buildings and Other Structures (American Society of Civil Engineers [ASCE] 7-16). Per ASCE 7-16 Section 11.4.8, a ground motion hazard analysis or site-specific response analysis is required to determine the design ground motions for structures on Site Class D sites with S₁ greater than or equal to 0.2g.

For this project, the site is classified as Site Class D with an S₁ value of 0.421g; therefore, the provision of 11.4.8 applies. The parameters listed in Table 4 below may be used to determine the design ground motions if Exception 2 of Section 11.4.8 of ASCE 7-16 is used. Using this exception, the seismic response coefficient (C_s) is determined by Equation (Eq.) (12.8-2) for values of $T \le 1.5T_s$, and taken as equal to 1.5 times the value computed in accordance with either Eq. (12.8-3) for $T_L \ge T > 1.5T_s$ or Eq. (12.8-4) for $T > T_L$, where T represents the fundamental period of the structure and T_S=0.809 sec. If requested, we can complete a site-specific seismic response analysis, which might provide somewhat reduced seismic demands from the parameters in Table 4 and the requirements for using Exception 2 of Section 11.4.8 in ASCE 7-16. The reduced values will likely not be significant enough to warrant the additional cost of further evaluation if designing to 2018 IBC.

Parameter	Recommended Value ^{1,2}
Site Class	D
Mapped Spectral Response Acceleration at Short Period (S_S)	0.841 g
Mapped Spectral Response Acceleration at 1 Second Period (S_1)	0.421 g
Site Modified Peak Ground Acceleration (PGA _M)	0.473 g
Site Amplification Factor at 0.2 second period (Fa)	1.164
Site Amplification Factor at 1.0 second period (F_v)	1.879
Design Spectral Acceleration at 0.2 second period (S_{DS})	0.652 g
Design Spectral Acceleration at 1.0 second period (SD1)	0.527 g

TABLE 4. MAPPED 2018 IBC SEISMIC DESIGN PARAMETERS

Notes:

¹ Parameters developed based on Latitude 44. 9700373° and Longitude -123.0638420° using the ATC Hazards online tool. ² These values are only valid if the structural engineer utilizes Exception 2 of Section 11.4.8 (ASCE 7-16).

7.4.1. Liquefaction Potential

Liquefaction is a phenomenon caused by a rapid increase in pore water pressure that reduces the effective stress between soil particles to near zero. The excessive buildup of pore water pressure results in the sudden loss of shear strength in a soil. Granular soil, which relies on interparticle friction for strength, is



susceptible to liquefaction until the excess pore pressures can dissipate. Sand boils and flows observed at the ground surface after an earthquake are the result of excess pore pressures dissipating upwards, carrying soil particles with the draining water. In general, loose, saturated sand soil with low silt and clay contents is the most susceptible to liquefaction. Low plasticity, silty sand may be moderately susceptible to liquefaction under relatively higher levels of ground shaking.

Based on our boring logs at the project site, the groundwater is located at or below the extent of the depth of drilling of $21\frac{1}{2}$ feet bgs, indicating that the soils encountered within our boring logs are not susceptible to liquefaction. Liquefaction is not considered a hazard for the project.

7.5. Retaining Walls

7.5.1. Drainage

Positive drainage is imperative behind retaining structures. This can be accomplished by providing a drainage zone behind the wall consisting of free-draining material and perforated pipes to collect and dispose the water. The drainage material should consist of Aggregate Base having less than 3 percent passing the U.S. No 200 sieve. The wall drainage zone should extend horizontally at least 18 inches from the back of the wall.

A perforated smooth-walled rigid drainpipe, having a minimum diameter of 4 inches, should be placed at the bottom of the drainage zone along the entire length of the wall, with the pipe invert at or below the base of the wall footing. The drainpipes should discharge to a tightline leading to an appropriate collection and disposal system. An adequate number of cleanouts should be incorporated into the design of the drains to provide access for regular maintenance. Roof downspouts, perimeter drains, or other types of drainage systems should not be connected to retaining wall drain systems.

7.5.2. Lateral Earth Pressures

Static and seismic lateral earth pressures were evaluated for use in design of the project. The evaluation assumed that: (1) backfill placed directly against walls will be free draining and meet the requirements of Section 6.9 of this report; (2) the backfill above the wall is level; and (3) that backfill placed within 2 feet of the wall is compacted using hand-operated equipment. The following subsections present recommended lateral earth pressures for use in design of conventional gravity retaining walls as well as braced walls such as the walls required for the below-grade parking floor for the proposed structure.

The recommended static lateral earth pressure coefficients and equivalent fluid pressures (triangular pressure distribution) for use in design of conventional gravity walls are presented in Table 5 for both imported structural fill as well as native on-site soil. Active earth pressure conditions assume that walls are not structurally restrained and are free to rotate. At-rest pressure conditions assume walls are structurally restrained from movement, or are to be designed for no lateral relaxation (rotational movement) as a function of elements that are being supported within a distance of twice the wall height from the top of the wall.



State of Stress	Earth Pressu	re Coefficient	Equivalent Fluid Pressure (psf)				
	Structural Fill	Native Soil	Structural Fill	Native Soil			
At-Rest (K ₀)	0.41	0.50	53*H	58*H			
Active (K _A)	0.24	0.30	31*H	35*H			
Passive (K _P)	3.0	2.5	390*H	288*H			

TABLE 5. STATIC EARTH PRESSURES FOR CONVENTIONAL GRAVITY WALLS

Notes:

1. The magnitude of lateral earth pressure at a given height of wall is presented in units of pcf per foot of wall height (H), or psf. The wall height is the distance between the ground surface and the base of the wall. Walls should be designed to resist loads from surcharge and adjacent at-grade structures.

For drained earth pressures to be used for design, provisions for adequate drainage behind the wall must be included.
 Compaction within 2 horizontal feet of the walls should be performed with lightweight, hand-operated equipment so that compaction-induced lateral stresses are limited.

For seismic active earth pressures for conventional gravity walls, use an additional dynamic increment force equal to 11*H psf, where H is the wall height, applied at 0.6*H from the exposed wall base (centroid location of seismic force).

The recommended pressures do not include the effects of surcharges from surface loads. If vehicles will be operated within one-half the height of the wall, a traffic surcharge should be added to the wall pressure. The traffic surcharge can be approximated by the equivalent weight of an additional 2 feet of backfill behind the wall. Additional surcharge loading conditions should also be considered on a case-by-case basis.

Retaining walls founded on native soil or structural fill extending to these materials may be designed using the allowable soil bearing values and lateral resistance values presented above in Section 7.1 of this report. We estimate settlement of retaining structures will be similar to the values previously presented for building foundations.

8.0 OTHER CONSIDERATIONS

8.1. Frost Penetration

The near-surface soils are slightly susceptible to frost heave. However, floor slabs are expected to bear on compacted granular fill and the foundations will be founded below the anticipated depth of frost penetration in the region, which is approximately 12 inches. The recommended exterior and interior footing embedment depths provided above should allow adequate frost protection.

8.2. Expansive Soils

Based on our laboratory test results and experience with similar soils in the area, we do not consider the soils encountered in our borings to be expansive.

9.0 PAVEMENT RECOMMENDATIONS

9.1. Dynamic Cone Penetrometer (DCP) Testing

We conducted DCP testing in general accordance with ASTM D 6951 to estimate the subgrade resilient modulus (M_R) at each test location. We recorded penetration depth of the cone versus hammer blow count and terminated testing when at a depth of approximately 5 feet bgs. The approximate locations of the explorations are presented in Figure 2. We plotted depth of penetration versus blow count and visually assessed portions of the data where slopes were relatively constant using the equation from the Oregon Department of Transportation (ODOT) Pavement Design Guide to estimate the moduli using a conversion coefficient, $C_f = 0.35$. Table 6 lists our estimate of the subgrade resilient modulus, and Appendix A (Figures A-14 and A-15) provides a summary of the field data.

TABLE 6. ESTIMATED SUBGRADE RESILIENT MODULI BASED ON DCP TESTING

Boring Number	Estimated Resilient Modulus (psi)
DCP-1	5,400
DCP-2	6,200

9.2. Asphalt Concrete (AC) Pavement Sections

Pavement recommendations are provided herein for paved parking and drive areas at the project site. Standards used for pavement design for asphalt pavement design are listed below:

- ODOT Pavement Design Guide (ODOT 2019)
- AASHTO Guide for Design of Pavement Structures (AASHTO 1993)

Our pavement recommendations assume that traffic at the site will consist of occasional truck traffic and passenger cars. We do not have specific information on the frequency and type of vehicles that will use the area; however, we have based our design analysis on traffic consisting of up to eight heavy trucks per day to account for the proposed commercial properties as well as delivery and service-type vehicles and passenger car traffic for pavement sections within drive areas, and passenger car traffic only for pavement sections within parking areas. Our pavement recommendations are based on the following assumptions:

- The on-site soil subgrade below proposed fill placed to raise site grades or below aggregate base sections has been prepared as described in Section 6.0 of this report, and observations indicate that subgrade is in a firm and unyielding condition.
- A resilient modulus of 20,000 psi was estimated for base rock prepared and compacted as recommended.
- A resilient modulus of 5,400 psi was estimated for firm in-place soils or structural fill placed on firm native soils.
- Initial and terminal serviceability indices of 4.2 and 2.5, respectively.
- Reliability and standard deviations of 90 percent and 0.49, respectively.
- Structural coefficients of 0.42 and 0.10 for the asphalt and base rock, respectively.

A 20-year design life.

If any of the noted assumptions vary from project design use, our office should be contacted with the appropriate information so that the pavement designs can be revised or confirmed adequate. The recommended minimum pavement sections are provided in Table 7 below.

	Minimum Asphalt Thickness (inches)	Minimum Base Thickness (inches)
Drive Lanes	4.0	5.0
Parking (cars only)	3.0	6.0

TABLE 7.	MINIMUM	PAVEMENT	SECTIONS	FOR C)N-SITE	ROADWAYS	AND	PARKING /	AREAS

The aggregate base course should conform to Section 6.9.4 of this report and be compacted to at least 95 percent of the maximum dry density (MDD) determined in accordance with AASHTO T-180/ASTM Test Method D 1557.

The AC pavement should conform to Section 00745 of the most current edition of the ODOT Standard Specifications for Highway Construction. The Job Mix Formula should meet the requirements for a ¹/₂-inch Dense Graded Level 2 Mix. The AC should be PG 64-22 grade meeting the ODOT Standard Specifications for Asphalt Materials. AC pavement should be compacted to 91.0 percent at Maximum Theoretical Unit Weight (Rice Gravity) of AASHTO T-209.

The recommended pavement sections assume that final improvements surrounding the pavement will be designed and constructed such that stormwater or excess irrigation water from landscape areas does not infiltrate below the pavement section into the crushed base.

10.0 DESIGN REVIEW AND CONSTRUCTION SERVICES

Recommendations provided in this report are based on the assumptions and design information stated herein. We welcome the opportunity to review and discuss construction plans and specifications for this project as they are being developed. In addition, GeoEngineers should be retained to review the geotechnical-related portions of the plans and specifications to evaluate whether they are in conformance with the recommendations provided in this report.

Satisfactory construction and earthwork performance depend to a large degree on quality of construction. Sufficient monitoring of the contractor's activities is a key part of determining that the work is completed in accordance with the construction drawings and specifications. Subsurface conditions observed during construction should be compared with those encountered during the subsurface explorations. Recognition of changed conditions often requires experience; therefore, qualified personnel should visit the site with sufficient frequency to detect whether subsurface conditions change significantly from those anticipated.

In order to continue as geotechnical engineer of record for the project, we recommend that GeoEngineers be retained to observe construction at the site to confirm that subsurface conditions are consistent with the site explorations, and to confirm that the intent of project plans and specifications relating to earthwork, pavement and foundation construction are being met.



11.0 LIMITATIONS

We have prepared this report for the exclusive use of Scott Martin Construction, Inc., and their authorized agents and/or regulatory agencies for the proposed Riverbend Phase 2 Development Project in Salem, Oregon.

This report is not intended for use by others, and the information contained herein is not applicable to other sites. No other party may rely on the product of our services unless we agree in advance and in writing to such reliance.

Within the limitations of scope, schedule, and budget, our services have been executed in accordance with generally accepted practices in the area at the time this report was prepared. No warranty or other conditions, express or implied, should be understood.

Please refer to Appendix B titled "Report Limitations and Guidelines for Use" for additional information pertaining to use of this report.

12.0 REFERENCES

- American Association of State Highway and Transportation Officials (AASHTO). 1993. Guide for Design of Pavement Structures.
- American Society of Civil Engineers (ASCE). 2017. Minimum Design Loads and Associated Criteria for Buildings and Other Structures.
- Bela, J.L. 1981. Geology of the Rickreall, Salem West, Monmouth, and Sidney 7½ minute quadrangles, Marion, Polk, and Linn Counties, Oregon: Oregon Department of Geology and Mineral Industries Geological Map Series GMS-18, 1 plate, 1:24,000 scale.
- City of Salem Department of Public Works Administrative Rules Design Standards (COSDS). 2014. City of Salem Administrative Rules Division 004.

International Code Council. 2018. International Building Code (IBC).

- Occupational Safety and Health Administration (OSHA) Technical Manual Section V: Chapter 2, Excavations: Hazard Recognition in Trenching and Shoring: <u>http://www.osha.gov/dts/osta/otm/otm_v/otm_v_2.html</u>
- Oregon Department of Geology and Mineral Industries (DOGAMI). 2020. SLIDO: Statewide Landslide Information Layer for Oregon. Accessed online <u>https://gis.dogami.oregon.gov/maps/slido/</u> 11/24/20 at 2:35pm.
- Oregon Department of Transportation (ODOT). 2018. Standard Specifications for Highway Construction. Salem, Oregon.

Oregon Department of Transportation (ODOT). 2019. ODOT Pavement Design Guide. Salem, Oregon.









- Data Source: ESRI Clarity. Overlay from Lenity architecture, inc.
- $oldsymbol{O}$ Infiltration Test Number and Approximate Location



Projection: NAD 1983 UTM Zone 10N

65



Figure 2



APPENDIX A Field Explorations and Laboratory Testing

APPENDIX A FIELD EXPLORATIONS AND LABORATORY TESTING

Field Explorations

Soil and groundwater conditions at the site were explored on November 5 and 6, 2020, by completing twelve drilled borings, two infiltration tests, and two direct cone penetrometer (DCP) tests at the approximate locations shown in the Site Plan, Figures 2. The machine-drilled borings were advanced with a solid-stem auger using a trailer-mounted drill rig owned and operated by Dan Fischer Drilling.

The drilling was continuously monitored by an engineering geologist from our office who maintained detailed logs of subsurface exploration, visually classified the soil encountered, and obtained representative soil samples from the borings. Samples were collected using a 1-inch, inside-diameter, standard split spoon sampler and a 3-inch, inside-diameter, Dames and Moore (D&M) split spoon sampler. Samplers were driven into the soil using a rope and cathead 140-pound hammer, free-falling 30 inches on each blow. The number of blows required to drive the sampler each of three, 6-inch increments of penetration were recorded in the field. The sum of the blow counts for the last two, 6-inch increments of penetration was reported on the boring logs as the ASTM International (ASTM) Standard Practices Test Method D 1556 standard penetration testing (SPT) N-value. The approximate N-values for D&M samples to SPT N-values using the Lacroix-Horn Conversion were converted [N(SPT) (2*N1*W1*H1)/(175*D1*D1*L1), where N1 is the non-standard blowcount, W1 is the hammer weight in pounds (140), H1 is the hammer drop height in inches (30), D1 is the non-standard sampler outside diameter in inches (3.23), and L1 is the length of penetration in inches (12)].

Recovered soil samples were visually classified in the field in general accordance with ASTM D 2488 and the classification chart listed in Key to Exploration Logs, Figure A-1. Logs of the borings are presented in Figures A-2 through A-13. The logs are based on interpretation of the field and laboratory data and indicate the depth at which subsurface materials or their characteristics change, although these changes might actually be gradual. Logs of DCP testing results are presented in Figures A-14 and A-15.

Laboratory Testing

Soil samples obtained from the explorations were visually classified in the field and in our laboratory using the Unified Soil Classification System (USCS) and ASTM classification methods. ASTM Test Method D 2488 was used to visually classify the soil samples, while ASTM D 2487 was used to classify the soils, based on laboratory tests results. Moisture content tests were performed in general accordance with ASTM D 2216-05, moisture density tests of the ring samples were estimated in general accordance with ASTM Test Method D 7263, Percent Passing the No. 200 Sieve tests were performed in general accordance with ASTM D 1140, and Atterberg Limits tests were performed in general accordance with ASTM Test Method D 4318-05. Results of the laboratory testing are presented in the appropriate exploration logs at the respective sample depths and Atterberg Limits test results are presented in Figures A-16 through A-18.



I	MAJOR DIVIS	IONS	SYMBOLS	
	GRAVEL	CLEAN GRAVELS	GW	WELL-GRADED GRAVELS, GRAVEL - SAND MIXTURES
	AND GRAVELLY SOILS	(LITTLE OR NO FINES)	GP	POORLY-GRADED GRAVELS, GRAVEL - SAND MIXTURES
COARSE GRAINED	MORE THAN 50%	GRAVELS WITH FINES	GM	SILTY GRAVELS, GRAVEL - SAND - SILT MIXTURES
30113	FRACTION RETAINED ON NO. 4 SIEVE	(APPRECIABLE AMOUNT OF FINES)	GC	CLAYEY GRAVELS, GRAVEL - SAND - CLAY MIXTURES
ORE THAN 50%	SAND	CLEAN SANDS		WELL-GRADED SANDS, GRAVELLY SANDS
TAINED ON 200 SIEVE	AND SANDY SOILS	(LITTLE OR NO FINES)	SP	POORLY-GRADED SANDS, GRAVELLY SAND
	MORE THAN 50% OF COARSE FRACTION PASSING	SANDS WITH FINES	SM	SILTY SANDS, SAND - SILT MIXTURES
	ON NO. 4 SIEVE	(APPRECIABLE AMOUNT OF FINES)	sc	CLAYEY SANDS, SAND - CLAY MIXTURES
			ML	INORGANIC SILTS, ROCK FLOUR, CLAYEY SILTS WITH SLIGHT PLASTICITY
FINE GRAINED SOILS MORE THAN 50% PASSING NO. 200 SIEVE	SILTS AND CLAYS	LIQUID LIMIT LESS THAN 50	CL	INORGANIC CLAYS OF LOW TO MEDIUM PLASTICITY, GRAVELLY CLAYS, SANDY CLAYS, SILTY CLAYS, LEAN CLAYS
			OL	ORGANIC SILTS AND ORGANIC SILTY CLAYS OF LOW PLASTICITY
			МН	INORGANIC SILTS, MICACEOUS OR DIATOMACEOUS SILTY SOILS
	SILTS AND CLAYS	LIQUID LIMIT GREATER THAN 50	СН	INORGANIC CLAYS OF HIGH PLASTICITY
			ОН	ORGANIC CLAYS AND SILTS OF MEDIUM TO HIGH PLASTICITY
	HIGHLY ORGANIC	SOILS	PT	PEAT, HUMUS, SWAMP SOILS WITH HIGH ORGANIC CONTENTS
	San 2.4 2.4 Sta Pist Dire Bull Con lowcount is re	mpler Symb inch I.D. split k indard Penetrat Iby tube on ect-Push < or grab tinuous Coring ecorded for dri to advance sa	ool Descriptio parrel tion Test (SPT) g ven samplers as umpler 12 inches	ns the number of (or distance noted).
B bi S "F	lows required ee exploratio P" indicates s	n log for hamn ampler pushed	ner weight and d d using the weigh	rop. It of the drill rig.

ADDITIONAL MATERIAL SYMBOLS

SYM	BOLS	TYPICAL					
GRAPH	LETTER	DESCRIPTIONS					
	AC	Asphalt Concrete					
	сс	Cement Concrete					
	CR	Crushed Rock/ Quarry Spalls					
	SOD	Sod/Forest Duff					
	TS	Topsoil					

TURES		Groundwater Contact
	<u> </u>	Measured groundwater level in exploration, well, or piezometer
R,	Ţ	Measured free product in well or piezometer
Y AYS,		Graphic Log Contact
SILTY		Distinct contact between soil strata
OR	/	Approximate contact between soil strata
		Material Description Contact
		Contact between geologic units
		Contact between soil of the same geologic unit
VITH		Laboratory / Field Tests
	%F %G AL CP CS DD DS HA MC MD SA HA PL PP SA TX US	Percent fines Percent gravel Atterberg limits Chemical analysis Laboratory compaction test Consolidation test Dry density Direct shear Hydrometer analysis Moisture content Moisture content and dry density Mohs hardness scale Organic content Permeability or hydraulic conductivity Plasticity index Point load test Pocket penetrometer Sieve analysis Triaxial compression Unconfined compression Vane shear
	NS SS MS HS	No Visible Sheen Slight Sheen Moderate Sheen Heavy Sheen

NOTE: The reader must refer to the discussion in the report text and the logs of explorations for a proper understanding of subsurface conditions. Descriptions on the logs apply only at the specific exploration locations and at the time the explorations were made; they are not warranted to be representative of subsurface conditions at other locations or times.



-												
Drilled	11/	<u>Start</u> 5/2020	<u> </u> 11/5	<u>End</u> 5/2020	D Total D Depth	(ft)	16.5	Logged By AB Checked By	Driller Dan Fischer Excava	ting		Drilling Method Solid-stem Auger
Surface Vertica	e Eleva Il Datu	ation (ft) m		I	180 NAVD88			Hammer Data 14	Manual Cathead 40 (lbs) / 30 (in) Drop	Drilling Equipn	nent	Trailer Drill Rig
Latitud Longitu	le ude			44 -12	4.970551 23.06486			System Datum	Decimal Degrees WGS84 (feet)	Ground	dwater	not observed at time of exploration
Notes	: D&N	/IN-value	s reduc	ed usi	ing Lacroix	Horn	Equation	to approximate SPT N-value	s.			
\equiv	FIELD DATA											
ion (feet)	(feet)	al ered (in)	/foot	ed Sample	le Name g	ic Log	fication	MATERIAL DESCRIPTION			it (%)	REMARKS
Elevat	Depth	Interv Recov	Blows	Collect	<u>Samp</u> Testir	Graph	Group Classi			Moistu Conter	Fines Conter	
Ļ	0-	-					ML	Gray-red mottled silt (ve	ery stiff, moist) (Alluvium)	_		
-	-		10		1			-		- 22		
-	-		10		ÂĹ			-		_ 32		AL (LL-44, PI-LS)
> ¹⁵ -	5—	18	8*		2			Becomes brown and sti	iff	_		DD = 81 pcf
-	-	18	5		3			 Becomes medium stiff 		_		
- 10	-	Р						-		_		
	-10	18	4*		4			-		_		
1	-									_		
	-	-						-		_		
->03	15 -	18	7		5			Increase in moisture co	ntent	_		
1												
1												
-												
Not	te: Sec	Figure A	-1 for e	xplana	ation of svn	ואט⊳						
Coc	ordinat	tes Data S	Source:	Horizo	ontal appro	isois. Dxima	ted based	l on GPS (Rec). Vertical appr	oximated based on GPS (Rec).			<u></u>

Log of Boring B-1



Project: Scott Martin Construction - Riverbend Phase 2 Project Location: Salem, Oregon Project Number: 23198-001-00

Drille	ed 11/	<u>Start</u> 5/2020	<u> </u> 11/5	<u>End</u> 5/2020	Total Depth	(ft)	21.5	Logged By AB Checked By	Driller Dan Fischer Excavatin	g		Drilling Method Solid-stem Auger	
Surfa Verti	ace Eleva cal Datu	ation (ft) m		1 NA	170 VD88			Hammer Data 14	Manual Cathead 0 (lbs) / 30 (in) Drop	Drilling Equipn	nent	Trailer Drill Rig	
Latiti Long	ude (itude			44.9 -123	970636 .06422			System Datum	Decimal Degrees WGS84 (feet)	See "Remarks" section for groundwater observed			
Note	Notes: D&M N-values reduced using Lacroix Horn Equation to approximate SPT N-values.												
			FIEL	D DA1	ΓA								
Elevation (feet)	Depth (feet)	Interval Recovered (in)	Blows/foot	Collected Sample	<u>Sample Name</u> Testing	Graphic Log	Group Classification	MA DES(ATERIAL CRIPTION	Moisture Content (%)	Fines Content (%)	REMARKS	
-	-0	-					ML	Brown-gray silt (very stiff –	, moist) (Alluvium)	-			
-	-	15	22		1 MC			-		- _ 27.4 -			
-^603 -	5-	18	20*		2			Becomes brown		-			
-	-	18	6		3			 Becomes medium stiff 		-			
ARD_%F_N0_GW	10 — -	18	5*		4			-		-			
	- - 15 -	18	4		5 %F		 SM	Brown silt (soft, moist) 			89.5		
	- 20 —	5	50/5.5'	1	6		 SP	Dark gray-blackish sand	(very dense, wet)	- -		Groundwater inferred by soil sample moisture content	
INGINEERS.COM/WAN/PROJECTS/23/33198001/GINT/2313800100.GPJ DBLIDrary/LIbrary/st-UENsine.	Note: See Figure A1 for explanation of symbols. Coordinates Data Source: Horizontal approximated based on GPS (Rec). Vertical approximated based on GPS (Rec).												
I://GEOEN								Log of E	Boring B-2				
Date:12/9/20 Pat	GEOENGINEERS Project: Scott Martin Construction - Riverbend Phase 2 Project Location: Salem, Oregon Figure A-3												

Project Number: 23198-001-00

Figure A-3 Sheet 1 of 1

<u>Start</u> Drilled 11/5/2020	<u>End</u> 11/5/2020	Total Depth (ft)	6.5	Logged By Checked By	AB	Driller Dan Fischer Excavatir	ng	Drilling Method Solid-stem Auger
Surface Elevation (ft) Vertical Datum	1 NAV	.70 /D88		Hammer Data	140	Manual Cathead 0 (lbs) / 30 (in) Drop	Drilling Equipment	Trailer Drill Rig
Latitude Longitude	44.9 ⁻ -123.0	70215 064588		System Datum		Decimal Degrees WGS84 (feet)	Groundwate	r not observed at time of exploration

Notes:

			FIEL	D D	ATA						~
Elevation (feet)	Depth (feet)	Interval Recovered (in)	Blows/foot	Collected Sample	<u>Sample Name</u> Testing	Graphic Log	Group Classification	MATERIAL DESCRIPTION		Fines Content (%)	REMARKS
_	0-	18	11		1		ML	Brown silt (stiff, moist) (Alluvium)			
-	-		20		2				-		
_\%^-	5—	18	14		3 MC			Becomes stiff	27.1		

NO GV STD_US_JUNE_2017.GLB/GEI8_GEOTECH_STANDARD_%F ECTS \23 \23198001 \GINT \2319800100.GPJ DBLIbrary / Library: GE0ENGIN RS.COM ite:12/9/20

Note: See Figure A-1 for explanation of symbols. Coordinates Data Source: Horizontal approximated based on GPS (Rec). Vertical approximated based on GPS (Rec).

Log of Boring B-3



Project: Scott Martin Construction - Riverbend Phase 2 Project Location: Salem, Oregon Project Number: 23198-001-00

Figure A-4 Sheet 1 of 1

Dri	illed	11/	<u>Start</u> 5/2020) 11	<u>End</u> /5/20	I Total	(ft)	16.5	Logged By AB Checked By	Driller	Dan Fischer Excavatir	ng		Drilling Method Solid-stem Auger
Su Ve	rface	e Eleva Datu	ntion (ft)		170 NAVD88	(14)		Hammer Data 14	Manual Ca 0 (lbs) / 30	athead) (in) Drop	Drilling Equipn	nent	Trailer Drill Rig
La	titud	e Ide			-	44.970237			System	Decimal D WGS84	egrees (feet)	Ground	dwater	not observed at time of exploration
N	otes:	D&N	1 N-valu	ues red	uced	using Lacroix	Horn	Equation	to approximate SPT N-values					
				FI	ELD	DATA								
Flevation (feet)	5000	o Depth (feet)	Interval Becovered (in)	Blows/foot	Collected Sample	Sample Name Testing	Graphic Log	Group Classification	MA DESC	TERIAI CRIPTI(_ DN	Moisture Content (%)	Fines Content (%)	REMARKS
-		-	1	5 16	i	1		ML	Gray-brown silt (very stiff	, moist) (A	lluvium)	-		
- - -	þ	- 5 — -		8 8*		2			Becomes brown and stif	f		-		DD = 80 pcf
		-	1	8 9		3			 Becomes medium stiff 			_		
DARD_%F_N0_GW	þ	10	1	8 7*		4			-			-		
	þ	- - 15 — -		8 5		5			- - -					
y/LibraryGE0ENGINEERS_DF_S1D_US_JUNE_201/	$5^{2} 15 + 18 5 5 + 11 + 18 + 14 + 14 + 14 + 14 + 14 + 14$													
98001/GINI/2319800100.GPJ DBLIDIA														
NGINEERS.COM/WAN/PHOJECIS/231:	Not Coc	e: See ordinat	e Figure es Dat	A-1 for a Sourc	expla e: Ho	anation of sym rizontal appro	nbols. ximat	ed based	d on GPS (Rec). Vertical appro	ximated b	ased on GPS (Rec).			
//deoe									Log of E	Boring	B-4			



Date:12/9/20 Path

Project: Scott Martin Construction - Riverbend Phase 2 Project Location: Salem, Oregon Project Number: 23198-001-00

<u>Start</u> Drilled 11/5/2020	<u>End</u> 11/5/2020	Total Depth (ft)	6.5	Logged By Checked By	AB	Driller Dan Fischer Excavatir	ng	Drilling Method Solid-stem Auger
Surface Elevation (ft) Vertical Datum	1 NAV	.70 VD88		Hammer Data	14	Manual Cathead 0 (lbs) / 30 (in) Drop	Drilling Equipment	Trailer Drill Rig
Latitude Longitude	44.9 ⁻ -123.0	70272 063356		System Datum		Decimal Degrees WGS84 (feet)	Groundwate	r not observed at time of exploration

Notes:

\square			FIEL	DD	ATA						
Elevation (feet)	Depth (feet)	Interval Recovered (in)	Blows/foot	Collected Sample	<u>Sample Name</u> Testing	Graphic Log	Group Classification	MATERIAL DESCRIPTION	Moisture Content (%)	Fines Content (%)	REMARKS
_	0-	12	12		1		ML	Brown sandy silt (stiff, moist) (Alluvium)			
_	-	Д									
-	-	18	13		<u>2</u> MC				27.9		
- న	-										
_^\ ⁰⁻	5 —	14	15		3			–			
t	-								1		

JECTSV23V23198001/GINTV2319800100.GPJ DBLibrary/LIbrary/GEOENGINEERS_DF_STD_US_JUNE_2017.GLB/GEI8_GEOTECH_STANDARD_%F_N0_GM RS.COM\WAN ate:12/9/20

Note: See Figure A-1 for explanation of symbols. Coordinates Data Source: Horizontal approximated based on GPS (Rec). Vertical approximated based on GPS (Rec).

Log of Boring B-5



Project: Scott Martin Construction - Riverbend Phase 2 Project Location: Salem, Oregon Project Number: 23198-001-00

Figure A-6 Sheet 1 of 1

ſ	Drilled	11/	<u>Start</u> 5/2020	 11/5	<u>End</u> 5/2020	Total Depth	(ft)	21.5		Logged By AB Checked By	Driller Dan Fischer Excav	ating			Drilling Method Solid-stem Auger
	Surface Vertical	e Eleva Datu	ation (ft) m		1 NA	170 VD88			Har Dat	mmer ta 140	Manual Cathead) (lbs) / 30 (in) Drop	E	Drilling Equipn	nent	Trailer Drill Rig
	Latitud Longitu	e ide			44.9 -123.	69998 065159			Sys Dat	stem I itum	Decimal Degrees WGS84 (feet)	ç	See "R	emark	s" section for groundwater observed
l	Notes:	D&N	1 N-valu	es reduc	ed using	Lacroix I	Horn	Equation	n to ap	pproximate SPT N-values.					
ſ				FIE	D DA	ΓA									
	Elevation (feet	o Depth (feet)	Interval Recovered (in)	Blows/foot	Collected Sample	<u>Sample Name</u> Testing	Graphic Log	Group Classification		MA DESC	TERIAL CRIPTION		Moisture Content (%)	Fines Content (%)	REMARKS
	-	-0	-					ML	_	Brown-grayish silty sand	(stiff, moist) (Alluvium)	_			
-	- - చు	-	15	15		1			-			-			
	->0	5-	18	15	,	2 VIC, AL			-	Becomes brown			33.6		AL (LL=43, PI=15)
-		-	18	8*		3			-	No sand content		-			
RD_%F_N0_GW	_%° -	10	18	12		4 MC			_			-	37.5		
2017.GLB/GEI8_GEOTECH_STANDAF	 	- - 15 — -	18	3*		5			-	Becomes soft		-			
ERS_DF_STD_US_JUNE	Groundwater inferred by soil sample moistur Content Becomes medium stiff with trace fine sand														
ENGINEERS.COM\WAN\PROJECTS\23\23198001\GINT\2319800100.GPJ DBLIbrary/Library.GEOENGINE	Note: See Figure A-1 for explanation of symbols.														
th://GEOEN										Log of E	oring B-6				
Date:12/9/20 Pa	G	E	οE	NG	INE	ERS	5/	D		Project: Scott N Project Location	Iartin Construction - n: Salem, Oregon	- Rive	erbe	nd P	hase 2 Figure A-7

Project Number: 23198-001-00

Figure A-7 Sheet 1 of 1

Drilled	<u>Start</u> 11/5/2020	<u>End</u> 11/5/2020	Total Depth (ft)	16.5	Logged By Checked By	AB	Driller Dan Fischer Excavatir	ıg	Drilling Method Solid-stem Auger
Surface Vertical	Elevation (ft) Datum	1 NA'	170 VD88		Hammer Data	14	Manual Cathead 0 (lbs) / 30 (in) Drop	Drilling Equipment	Trailer Drill Rig
Latitude Longitud	le	44.9 -123.0	69778 064245		System Datum		Decimal Degrees WGS84 (feet)	Groundwate	r not observed at time of exploration

Notes:

PR0JECTS\23\23198001\GINT\2319800100.GPJ DBLIbrary/Library.GE0ENGINEERS_DF_STD_US_UNE_2017.G

EERS.COM\WAN

ate:12/9/20

\equiv				_							
			FIEL	DD	AIA						
Elevation (feet)	Depth (feet)	Interval Recovered (in)	Blows/foot	Collected Sample	<u>Sample Name</u> Testing	Graphic Log	Group Classification	MATERIAL DESCRIPTION	Moisture Content (%)	Fines Content (%)	REMARKS
	0-						ML	Gray silt with trace sand (very stiff, moist) (Alluvium)			
	-										
\mathbf{F}	_	14	16		1						
- - - %	5		13		2			Becomes brown with no sand and stiff			
-	-		9		3						
	- 10 — -		5		4			Becomes medium stiff			Increase in moisture content
	-							 			
	15 —	18	6		5			With occasional fine sand			

Note: See Figure A-1 for explanation of symbols. Coordinates Data Source: Horizontal approximated based on GPS (Rec). Vertical approximated based on GPS (Rec).

Log of Boring B-7



Project: Scott Martin Construction - Riverbend Phase 2 Project Location: Salem, Oregon Project Number: 23198-001-00

Figure A-8 Sheet 1 of 1

/					_									
	Drilled	11/	<u>Start</u> 5/2020	<u> </u> 11/5	<u>End</u> 5/2020	D Total D Depth	(ft)	16.5	Logged By AB Checked By	Driller Dan Fischer Ex	xcavating			Drilling Method Solid-stem Auger
	Surface /ertical	Eleva Datu	ation (ft) m		١	170 NAVD88			Hammer Data 14	Manual Cathead 0 (lbs) / 30 (in) Drop		Drilling Equipn	nent	Trailer Drill Rig
	atitude ongitu	e de			44 -12	1.969961 3.063714			System Datum	Decimal Degrees WGS84 (feet)		Ground	dwater	not observed at time of exploration
l	Notes:	D&N	1 N-value	s reduc	ed usi	ng Lacroix I	Horn	Equation	to approximate SPT N-values					
ſ				FIEL	LD D/	ATA								
	tion (feet)	n (feet)	al vered (in)	s/foot	ted Sample	<u>ole Name</u> 1g	nic Log	o ification	MA DESC	TERIAL CRIPTION		ure nt (%)	nt (%)	REMARKS
	Eleva	bept	Inten Reco	Blow	Collec	<u>Sam</u> j Testi	Grap	Grou				Moisti Conte	Fines Conte	
-		- 0						ML	Brown silt (very stiff, moi –	st) (Alluvium)	-	-		
		-	5	21		1			-		-	-		
-	Ф	5 — -	18	10*		2			 Becomes stiff -		-	-		
-		-	18	7		<u>3</u> MC			 Becomes gray and medi 	um stiff	-	36.6		
%F_N0_GW	⁶⁰	10 —	18	3*		4			Becomes soft		-	-		
ECH_STANDARD		-							-		-	-		
LB/GEI8_GEOTE	(s ^o	15 —	18	10		5			 Becomes stiff -		-	-		
US_JUNE_201/.														
NEERS_DF_STD														
Library:GEOENG														
.GPJ DBLibrary/														
\2319800100														
3198001\GINT														
ROJECTS/23/2														
S.COM\WAN\P	Note	e: See	e Figure A	-1 for e	xplana	ition of svm	npols							
ENGINEERS	Coo	rdinat	es Data	Source:	Horizo	ontal appro	ximat	ted based	d on GPS (Rec). Vertical appro	ximated based on GPS (F	Rec).			
GEOE									l og of F	Poring R-8				

Log of Boring B-8



Project: Scott Martin Construction - Riverbend Phase 2 Project Location: Salem, Oregon Project Number: 23198-001-00

Figure A-9 Sheet 1 of 1

	Drilled	11/	<u>Start</u> 5/202	20	<u>E</u> 11/5	<u>End</u> 5/2020	Total Depth	(ft)	21.5		Logged By AB Checked By	Driller Dan Fischer Excavati	ng			Drilling Method Solid-stem Auger
	Surface Vertical	e Eleva Datu	ation (1 m	ft)		NA	170 AVD88			Ha Da	ammer ata 14	Manual Cathead 0 (lbs) / 30 (in) Drop	D E	rilling quipn	nent	Trailer Drill Rig
	Latitud Longitu	e ide				44.9 -123	969938 .063045			S <u>i</u> D	ystem atum	Decimal Degrees WGS84 (feet)	s	ee "R	emark	s" section for groundwater observed
	Notes:	D&N	1 N-va	lues	reduc	ed using	g Lacroix	Horn	Equation	to a	approximate SPT N-values					
ſ					FIEL	D DA	TA									
	Elevation (feet	b Depth (feet)	Interval	Recovered (In)	Blows/foot	Collected Sample	<u>Sample Name</u> Testing	Graphic Log	Group Classification		MA DES(TERIAL CRIPTION		Moisture Content (%)	Fines Content (%)	REMARKS
	-	-0	-						ML	_	Gray-brown silt with trace	e sand (stiff, moist) (Alluvium)	_			
-	-	-		18	14		1 MC			-			-	27.9		
-	_\ ⁶ - -	5 -		18	10*		2			_	Becomes brown with no	sand, very stiff				DD = 82 pcf
	-	-		18	6		<u>3</u> MC			-			-	43.4		
GW	_160	- 10 —		18	4*		4			_	Becomes medium stiff		_			
ARD_%F_NO_		-								-			_			
2017.GLB/GEI8_GEOTECH_STAND	- - - -	- - 15 - -		18	3		5		SM		Brown silt (soft, moist)		-			
RS_DF_STD_US_JUNE	- - _\\$ ⁰	- 20 —		18	31		6		 SP		Gray poorly graded sand	(dense, wet)				Groundwater inferred by soil sample moisture content
VEERS.COM\WAN\PROJECTS\23\23198001\GINT\2319800100.GPJ DBLIbrary/Library.GEOENGINE	Not Coc	e: See	: Figur	e A-1 ta So	L for ex Dource:	xplanatii Horizon	on of syn	nbols. ximat	red based	d on	1 GPS (Rec). Vertical appro	ximated based on GPS (Rec).				
GEOENGINI	_											Roring R.Q				
'20 Path: \\/											Project: Scott N	Martin Construction - R	live	erbe	nd P	hase 2
12/9/.	C		h	N			FR	5 /	,1		Project Locatio	n: Salem, Oregon				

Project Number: 23198-001-00

2017. JUNE S STD Ь Sa B GP ŝ 1980 ò ĕ Date:1

Figure A-10 Sheet 1 of 1

Drilled	<u>9</u> 11/5	<u>Start</u> 5/2020	<u> </u> 11/5	<u>End</u> 5/2020	Total Depth	ı (ft)	21.5		Logged By Checked By	AB	Driller Dan Fischer Excavati	ing			Drilling Method Solid-stem Auger
Surface Vertical	Eleva Datur	tion (ft) n		N	170 AVD88			Ha Da	ammer ata	14	Manual Cathead) (lbs) / 30 (in) Drop	D E	orilling iquipn	nent	Trailer Drill Rig
Latitude Longitue	e de			44. -123	.969914 3.062802	2		Sy: Da	rstem atum		Decimal Degrees WGS84 (feet)	Ģ	Ground	dwatei	r not observed at time of exploration
Notes:															
et)		(u	FIEL	_D DA	ATA ഇ										
Elevation (fe	Depth (feet)	Interval Recovered (i	Blows/foot	Collected Sam	<u>Sample Nam</u> Testing	Graphic Log	Group Classificatio			MA DES(TERIAL CRIPTION		Moisture Content (%)	Fines Content (%)	REMARKS
-	-						ML	_	Gray silt with tra	ice sand	(very stiff, moist) (Alluvium)	_			
-	-	14	16		<u>1</u> AL							-	24		AL (LL=41, PI=15)
_% -	5 —	18	16		<u>2</u> MC			_	Becomes brown	iish with	no sand	_	32.9		
-	-	18	5		3			-	Becomes mediu	ım stiff		-			
_160	10 -	18	4		4			_				_			Increase in moisture content
- - -	- - 15 -	18	7		5		SM	- - -	 Brown-gray silt (r	medium	stiff, moist)	- - -		90.7	
	- - 20 -	∑ 10	41		6		 GP	-	Gray poorly grad	ed grave	I with sand (dense, wet)	- - -			Groundwater inferred by soil sample moisture content
Note Coor	- :: See	Figure A es Data S	1 for e Source:	xplanat Horizo:	ion of syr ntal appro	nbols	ted based	t on	GPS (Rec). Vertic	al appro	kimated based on GPS (Rec).				
	,	-							Project: S	Scott N	Aartin Construction - R	Rive	erbe	nd F	hase 2
G	EC	DEN	١G	INE	ER	S /			Project Lo	ocatio umbe	n: Salem, Oregon				Figure A-11

Project Number: 23198-001-00

\\GEOENGINEERS.COM\WAN\PROJECTS\23\23198001\GINT\2319800100.GPJ DBLIbrary/LIbrary.GEOENGINEERS_DF_STD_US_JUNE_2017.GLB/GEI8_GEOTECH_STANDARD_%F_NO_GW Date:12/9/20 Path:

Figure A-11 Sheet 1 of 1

(Start		F	nd	Tetal								Drilling
	Drilled	11/	5/202	0 1	.1/5/	/2020	Depth	(ft)	16.5	Checked By	Driller	Dan Fischer Excavati	ng		Method Solid-stem Auger
	Surface Vertica	e Eleva I Datu	ation (fi m	:)		N	180 AVD88			Hammer Data 14	Manual Ca O (lbs) / 30	athead) (in) Drop	Drilling Equipn	nent	Trailer Drill Rig
	Latitud Longitu	e ide				44. -123	969914 3.062802			System Datum	Decimal D WGS84	egrees (feet)	Ground	dwater	not observed at time of exploration
	Notes:	D&N	1 N-val	ues re	duce	ed usin	ig Lacroix I	Horn I	Equation	n to approximate SPT N-values					
ſ				F	IEL	d da	TA								
	Elevation (feet)	Depth (feet)	Interval		BIOWS/ IOOL	Collected Sample	<u>Sample Name</u> Testing	Graphic Log	Group Classification	MA DESC	TERIAI CRIPTIC	L DN	Moisture Content (%)	Fines Content (%)	REMARKS
		- 0							ML	Brown silt with sand (ver - -	y stiff, moi	ist) (Alluvium)	-		
	175	-	1 	6 1	.6		1			-			-		
		-		6 1	.6		<u>2</u> MC			-			26.3 - -		
	,10	-	1	8 2	1		3			 With no sand content 			-		
ARD_%F_N0_GW	_ /	- 10	1	8 1	.4		4			Becomes grayish-brown 	and stiff		-		
3LB/GEI8_GEOTECH_STAND	<u>,</u> 69	- - 15 — -		8 5	*		5			- - Becomes medium stiff -			-		
irary:GEOENGINEERS_DF_STD_US_JUNE_2017	$\begin{array}{c c c c c c c c c c c c c c c c c c c $														
19800100.GPJ DBLibrary/Li															
/23/23198001/GINT/231															
INEERS.COM\WAN\PROJECTS	Not Coc	e: See	e Figure es Dat	e A-1 fo a Sou	or exp rce: H	planat Horizoi	ion of sym	bols. ximat	ed based	d on GPS (Rec). Vertical appro	ximated b	ased on GPS (Rec).			
GEOENGI										Log of B	oring	B-11			

Log of Boring B-11



Project: Scott Martin Construction - Riverbend Phase 2 Project Location: Salem, Oregon Project Number: 23198-001-00

Figure A-12 Sheet 1 of 1

		Start	1	End	Total			Logged Bv AR				Drilling
Drilleo	d 11/	(5/2020	11/5	5/2020	Depth	(ft)	16.5	Checked By	Driller Dan Fischer Excava	ating		Method Solid-stem Auger
Surface Vertic	ce Eleva al Datu	ation (ft) m		Ν	170 NAVD88			Hammer I Data 140	Manual Cathead) (lbs) / 30 (in) Drop	Equipn	nent	Trailer Drill Rig
Latitu Longi	ide tude			44 -12	1.969634 3.063522			System [Datum	Decimal Degrees WGS84 (feet)	Ground	dwater	not observed at time of exploration
Notes	s: D&N	/I N-value	es reduc	ed usir	ng Lacroix	Horn	Equation	to approximate SPT N-values.				
\bigcap			FIE	LD D/	ATA							
ation (feet)	th (feet)	rval overed (in)	/s/foot	cted Sample	<u>iple Name</u> ing	ohic Log	up sification	MA DESC	TERIAL CRIPTION	ture ent (%)	s ent (%)	REMARKS
Elev	o Dep	Intei Reco	Blov	Colle	<u>Sam</u> Test	Grap	Grou Clas			Mois Cont	Fines	
-		-					ML	Gray-brown silt with trace	e sand (stiff, moist) (Alluvium)	-		
	-	15	13		1 MC			-		- _ 24 -		
- ~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~	5-	15	19		2			Becomes very stiff with n	o sand	_		
-	-	18	8*		3			– Becomes stiff –		-		
	10 -	18	20		$\frac{4}{MC}$			Becomes brown and very	/ stiff	41.6		
		-						_		-		
	15 -	18	5		5			 Becomes medium stiff 		_		
ysedemaineers_DF_su_us_												
ט. טארוטומוץ/ בווטומ												
NOTOO86157\INH												
9\T0086T52\52												
AN (PROJECTION)												
No No	ote: See	e Figure A	-1 for e	xplana	ition of sym	nbols.	od baso	ton CPS (Poc) Vortical approx	vimated based on GPS (Rec)			

Log of Boring B-12



Project: Scott Martin Construction - Riverbend Phase 2 Project Location: Salem, Oregon Project Number: 23198-001-00

Figure A-13 Sheet 1 of 1

Depth to bottom	n: 61	152.5	Dimension:	2"			Test Method	: Dynamic Cone	e Penetration								
Tester's Name	e: John Lawes						GeoEngineers Job	: 23198-001-00)								
Tester's Company	y: GeoEngineers, Inc.		Tester's Contact No:	971-409-7390			Project Name	e Riverbend Ph	.2					100			T
Notes	s: Driven from base of 2	24-inch sampler							-								
	Depth, feet					Soil Texture			4								\vdash
	0-6.5	Brown to gray-brow	'n silt			Medium stiff			4					50			
									4					40			
									-								
									1					30			
		1	Depth below base of I	Penetration per	Cumulative	I Cummulative	Penetration per	Penetration	Hammer blow	1	1	1		1			
Test increment	Number of blows	Cumulative blows	S-1	increment	penetration	Penetration	blow set	per blow	factor	DCP Index	DCP Index	CBR	M₀	20		_	
									1 for 8-kg 2 for					ູ 15			+
#	#	#	(in)	(mm)	(mm)	(in)	(in)	(in)	1 101 8-kg 2 101	in/blow	mm/blow	%	nci	, m			1
1	7	6	0.6	15.0	15.0	0.6	0.6	0.30	2	0.59	15.00	14	5967	- <u> </u>			<u> </u>
2	2	8	11	13.0	29.0	11	0.6	0.28	2	0.55	14.00	15	6130	1 0			<u>+</u>
3	2	10	1.6	12.0	41.0	1.6	0.5	0.24	2	0.47	12.00	18	6510				
4	2	12	2.4	21.0	62.0	2.4	0.8	0.41	2	0.83	21.00	10	5234	5			+
5	2	14	3.1	17.0	79.0	3.1	0.7	0.33	2	0.67	17.00	12	5683	4			
6	2	16	3.6	13.0	92.0	3.6	0.5	0.26	2	0.51	13.00	17	6310	1 .			
7	2	18	4.6	24.0	116.0	4.6	0.9	0.47	2	0.94	24.00	8	4968	1 3			
8	2	20	5.3	18.0	134.0	5.3	0.7	0.35	2	0.71	18.00	11	5558	1,			
9	2	22	6.0	18.0	152.0	6.0	0.7	0.35	2	0.71	18.00	11	5558				
10	2	24	6.7	19.0	171.0	6.7	0.7	0.37	2	0.75	19.00	11	5442	1			
11	2	26	7.4	18.0	189.0	7.4	0.7	0.35	2	0.71	18.00	11	5558	1.			
12	2	28	8.1	17.0	206.0	8.1	0.7	0.33	2	0.67	17.00	12	5683	1 1	4		
13	2	30	8.8	17.0	223.0	8.8	0.7	0.33	2	0.67	17.00	12	5683		1	2 ;	3
14	2	32	9.5	19.0	242.0	9.5	0.7	0.37	2	0.75	19.00	11	5442				
15	2	34	10.3	19.0	261.0	10.3	0.7	0.37	2	0.75	19.00	11	5442				
16	2	36	11.0	19.0	280.0	11.0	0.7	0.37	2	0.75	19.00	11	5442		(after Webster	et al., 1992)
17	2	38	11.7	17.0	297.0	11.7	0.7	0.33	2	0.67	17.00	12	5683		Webster, S. L.,	Grau, R. H.,	and V
18	2	40	12.4	17.0	314.0	12.4	0.7	0.33	2	0.67	17.00	12	5683		penetrometer.	Department	t of th
19	2	42	13.1	19.0	333.0	13.1	0.7	0.37	2	0.75	19.00	11	5442				
20	2	44	13.7	16.0	349.0	13.7	0.6	0.31	2	0.63	16.00	13	5819				
21	2	46	14.4	16.0	365.0	14.4	0.6	0.31	2	0.63	16.00	13	5819		0 10	20	30
22	2	48	15.0	17.0	382.0	15.0	0.7	0.33	2	0.67	17.00	12	5683		0		
23	2	50	15.7	17.0	399.0	15.7	0.7	0.33	2	0.67	17.00	12	5683				
24	2	52	16.4	17.0	416.0	16.4	0.7	0.33	2	0.67	17.00	12	5683				_
25	2	54	17.1	19.0	435.0	17.1	0.7	0.37	2	0.75	19.00	11	5442	41	5		-
26	2	56	17.9	19.0	454.0	17.9	0.7	0.37	2	0.75	19.00	11	5442	41			·•
27	2	58	18.6	19.0	473.0	18.6	0.7	0.37	2	0.75	19.00	11	5442	l (se	10		
28	2	60	19.4	21.0	494.0	19.4	0.8	0.41	2	0.83	21.00	10	5234				_
29	2	62	20.1	17.0	511.0	20.1	0.7	0.33	2	0.67	17.00	12	5683	<u> </u>	<u>+</u>		
30	2	64	20.9	19.0	530.0	20.9	0.7	0.37	2	0.75	19.00	11	5442	- E	15		_
31	2	66	21.6	19.0	549.0	21.6	0.7	0.37	2	0.75	19.00	11	5442	ti i			_
32	2	68	22.4	19.0	568.0	22.4	0.7	0.37	2	0.75	19.00	11	5442	it i	20		
33	2	70	23.0	15.0	583.0	23.0	0.6	0.30	2	0.59	15.00	14	5967	- l	20		_
25	2	72	23.7	24.0	625.0	23.7	0.7	0.35	2	0.71	24.00	0	3338	- -			
	2	74	24.0	24.0	645.0	24.0	0.9	0.47	2	0.34	24.00	10	5224	<u>s</u>	25		_
37	2	70	25.4	20.0	665.0	26.2	0.8	0.39	2	0.79	20.00	10	5334	ati			_
38	2	80	26.2	18.0	683.0	26.9	0.0	0.35	2	0.75	18.00	11	5558	1 2			_
39	2	82	27.7	21.0	704.0	27.7	0.8	0.33	2	0.83	21.00	10	5234		30		_
40	2	84	28.5	20.0	724.0	28.5	0.8	0.39	2	0.79	20.00	10	5334	11 0			
41	2	86	29.3	19.0	743.0	29.3	0.7	0.37	2	0.75	19.00	11	5442		35		
42	2	88	30.1	21.0	764.0	30.1	0.8	0.41	2	0.83	21.00	10	5234	1	55		
43	2	90	30.9	20.0	784.0	30.9	0.8	0.39	2	0.79	20.00	10	5334				_
44	2	92	31.7	21.0	805.0	31.7	0.8	0.41	2	0.83	21.00	10	5234		40		
45	2	94	32.5	20.0	825.0	32.5	0.8	0.39	2	0.79	20.00	10	5334	1			
46	2	96	33.3	21.0	846.0	33.3	0.8	0.41	2	0.83	21.00	10	5234				
47	2	98	34.1	20.0	866.0	34.1	0.8	0.39	2	0.79	20.00	10	5334	1			
48	2	100	35.0	22.0	888.0	35.0	0.9	0.43	2	0.87	22.00	9	5140				
49	2	102	35.8	21.0	909.0	35.8	0.8	0.41	2	0.83	21.00	10	5234				
50	2	104	36.3	14.0	923.0	36.3	0.6	0.28	2	0.55	14.00	15	6130				
51	2	106	37.0	18.0	941.0	37.0	0.7	0.35	2	0.71	18.00	11	5558				

Test Hole Number: B-3 (DCP-1)

11/5/2020

Date:

Location: Riverbend Ph. 2 - River Road, Salem



, R. H., and Williams, T. P. (1992). Description and application of dual mass dynamic cone artment of the Army Waterways Equipment Station, No. GL-92-3.



	Location Depth to bottom Tester's Name	: Riverbend Ph. 2 - Riv : 61 : John Lawes	er Road, Salem 152.5	Date: Dimension:	11/5/2020 2"	Test Hole Number: B-5 (DCP-2) Test Method: Dynamic Cone Penetration GeoEngineers Job: 23198-001-00													
Tester's Company: GeoEngineers, Inc.			Tester's Contact No: 971-409-7390 Project Name Riverbend Ph.2											10	0 _			Ţ	
	Notes	Driven from base of a	24-inch sampler				Coll Touture			Г								+	4
-			Drown to grow brown	ailt			Son rexture			-						F			7
		0-6.5	Brown to gray-brown	SIIt			iviedium stiff			-					5/	<u>_</u>	<u> </u>		4
										-						š L			
										4					40	<u>ا</u> ۲			Τ
															30	0 -		+	+
																1			
				Depth below base of	Penetration per	Cumulative	Cummulative	Penetration per	Penetration	Hammer blow					20	0 -			+
	Test increment	Number of blows	Cumulative blows	S-1	increment	penetration	Penetration	blow set	per blow	factor	DCP Index	DCP Index	CBR	M _R		-			
										1 for 8-kg 2 for					8 1	5			
	#	#	#	(in)	(mm)	(mm)	(in)	(in)	(in)	4.6-kg hammer	in/blow	mm/blow	%	psi	<u> </u>	۸L			
	1	1	6	0.6	15.0	15.0	0.6	0.6	0.59	2	1.18	30.00	6	4554	. ซ "	• –		+	+
	2	1	7	0.8	5.0	20.0	0.8	0.2	0.20	2	0.39	10.00	22	6990					Ţ
	3	2	9	1.2	10.0	30.0	1.2	0.4	0.20	2	0.39	10.00	22	6990		-		+	+
	4	2	11	1.8	16.0	46.0	1.8	0.6	0.31	2	0.63	16.00	13	5819	. !	5 -			+
	5	2	13	2.2	10.0	56.0	2.2	0.4	0.20	2	0.39	10.00	22	6990		4 -			+
	6	3	16	2.9	18.0	74.0	2.9	0.7	0.24	2	0.47	12.00	18	6510		~			
	7	3	19	3.7	19.0	93.0	3.7	0.7	0.25	2	0.50	12.67	17	6374	•	3			T
	8	3	22	4 4	20.0	113.0	4 4	0.8	0.26	2	0.52	13 33	16	6248					
-	9	3	25	53	21.0	134.0	53	0.8	0.28	2	0.55	14.00	15	6130	, i	2		-	T
	10	3	25	5.9	17.0	151.0	5.9	0.7	0.20	2	0.35	11 33	19	6657					
-	10	2	28	5.9	17.0	169.0	6.7	0.7	0.22	2	0.43	12.00	19	6510					
-	12	2	24	7.2	17.0	105.0	7.2	0.7	0.24	2	0.47	11.00	10	6657		1 -			1
	12	2	27	7.5	17.0	204.0	7.3	0.7	0.22	2	0.45	12.00	19	6510		1		2	3
-	13	3	37	8.0 9.7	18.0	204.0	0.0	0.7	0.24	2	0.47	12.00	18	6510					
_	14	3	40	0.7	18.0	222.0	0.7	0.7	0.24	2	0.47	12.00	18	0510					
-	15	3	43	9.4	18.0	240.0	9.4	0.7	0.24	2	0.47	12.00	18	6510		1.4		at al 100'	21
	16	3	46	10.0	14.0	254.0	10.0	0.6	0.18	2	0.37	9.33	24	/180		(an W/c	abstor S I G	31 al., 1992 Srau R. H	.) э
_	1/	3	49	10.9	22.0	276.0	10.9	0.9	0.29	2	0.58	14.67	14	6020		ner	netrometer [Denartme	nt a
_	18	3	52	11.6	19.0	295.0	11.6	0.7	0.25	2	0.50	12.67	1/	6374		P			
	19	3	55	12.4	19.0	314.0	12.4	0.7	0.25	2	0.50	12.6/	1/	6374					
	20	3	58	13.1	20.0	334.0	13.1	0.8	0.26	2	0.52	13.33	16	6248					
	21	3	61	13.9	19.0	353.0	13.9	0.7	0.25	2	0.50	12.6/	1/	6374			0 10	20	
	22	3	64	14.6	17.0	370.0	14.6	0.7	0.22	2	0.45	11.33	19	6657		0			_
	23	3	67	15.4	22.0	392.0	15.4	0.9	0.29	2	0.58	14.67	14	6020					_
	24	3	70	16.4	24.0	416.0	16.4	0.9	0.31	2	0.63	16.00	13	5819		-	+		_
	25	3	73	17.2	20.0	436.0	17.2	0.8	0.26	2	0.52	13.33	16	6248		5			-
	26	3	76	17.8	16.0	452.0	17.8	0.6	0.21	2	0.42	10.67	21	6816					_
	27	3	79	18.6	21.0	473.0	18.6	0.8	0.28	2	0.55	14.00	15	6130	(se	10			
	28	3	82	19.3	17.0	490.0	19.3	0.7	0.22	2	0.45	11.33	19	6657	, š				_
	29	3	85	20.0	17.0	507.0	20.0	0.7	0.22	2	0.45	11.33	19	6657	i,				
	30	3	88	20.7	18.0	525.0	20.7	0.7	0.24	2	0.47	12.00	18	6510		15			_
	31	3	91	21.4	18.0	543.0	21.4	0.7	0.24	2	0.47	12.00	18	6510	tio		I		_
	32	3	94	22.0	17.0	560.0	22.0	0.7	0.22	2	0.45	11.33	19	6657	La la				_
	33	3	97	22.8	20.0	580.0	22.8	0.8	0.26	2	0.52	13.33	16	6248	net	20	+		_
	34	3	100	23.7	22.0	602.0	23.7	0.9	0.29	2	0.58	14.67	14	6020	- Be		+		_
	35	3	103	24.6	22.0	624.0	24.6	0.9	0.29	2	0.58	14.67	14	6020	e e	25			_
	36	3	106	25.5	24.0	648.0	25.5	0.9	0.31	2	0.63	16.00	13	5819	È	25			_
	37	3	109	26.4	22.0	670.0	26.4	0.9	0.29	2	0.58	14.67	14	6020	ula		1		_
	38	3	112	27.5	28.0	698.0	27.5	1.1	0.37	2	0.73	18.67	11	5480	Ē	30			-
	39	3	115	28.4	23.0	721.0	28.4	0.9	0.30	2	0.60	15.33	14	5917	C	50	+		_
	40	3	118	29.3	23.0	744.0	29.3	0.9	0.30	2	0.60	15.33	14	5917			I		_
	41	3	121	30.3	25.0	769.0	30.3	1.0	0.33	2	0.66	16.67	13	5727		35	+		_
	42	3	124	31.4	28.0	797.0	31.4	1.1	0.37	2	0.73	18.67	11	5480			1		_
	43	3	127	32.3	24.0	821.0	32.3	0.9	0.31	2	0.63	16.00	13	5819					
	44	3	130	33.9	40.0	861.0	33.9	1.6	0.52	2	1.05	26.67	7	4768		40			
	45	3	133	35.3	35.0	896.0	35.3	1.4	0.46	2	0.92	23.33	9	5023					
	46	3	136	36.6	34.0	930.0	36.6	1.3	0.45	2	0.89	22.67	9	5080					
	47	1	137	37.0	10.0	940.0	37.0	0.4	0.39	2	0.79	20.00	10	5334					



992) . H., and Williams, T. P. (1992). Description and application of dual mass dynamic cone ment of the Army Waterways Equipment Station, No. GL-92-3.









APPENDIX B Report Limitations and Guidelines for Use

APPENDIX B REPORT LIMITATIONS AND GUIDELINES FOR USE¹

This appendix provides information to help you manage your risks with respect to the use of this report.

Read These Provisions Closely

It is important to recognize that the geoscience practices (geotechnical engineering, geology and environmental science) rely on professional judgment and opinion to a greater extent than other engineering and natural science disciplines, where more precise and/or readily observable data may exist. To help clients better understand how this difference pertains to our services, GeoEngineers includes the following explanatory "limitations" provisions in its reports. Please confer with GeoEngineers if you need to know more how these "Report Limitations and Guidelines for Use" apply to your project or site.

Geotechnical Services Are Performed for Specific Purposes, Persons and Projects

This report has been prepared for Scott Martin Construction, Inc., and their agents for the Project specifically identified in the report. The information contained herein is not applicable to other sites or projects.

GeoEngineers structures its services to meet the specific needs of its clients. No party other than the party to whom this report is addressed may rely on the product of our services unless we agree to such reliance in advance and in writing. Within the limitations of the agreed scope of services for the Project, and its schedule and budget, our services have been executed in accordance with our Agreement with Scott Martin Construction, Inc. dated October 12, 2020, and generally accepted geotechnical practices in this area at the time this report was prepared. We do not authorize, and will not be responsible for, the use of this report for any purposes or projects other than those identified in the report.

A Geotechnical Engineering or Geologic Report is Based on a Unique Set of Project-Specific Factors

This report has been prepared for the proposed Riverbend Phase 2 Development Project in Salem, Oregon. GeoEngineers considered a number of unique, project-specific factors when establishing the scope of services for this project and report. Unless GeoEngineers specifically indicates otherwise, it is important not to rely on this report if it was:

- not prepared for you,
- not prepared for your project,
- not prepared for the specific site explored, or
- completed before important project changes were made.

¹ Developed based on material provided by ASFE, Professional Firms Practicing in the Geosciences; <u>www.asfe.org</u>.

For example, changes that can affect the applicability of this report include those that affect:

- the function of the proposed structure;
- elevation, configuration, location, orientation or weight of the proposed structure;

If changes occur after the date of this report, GeoEngineers cannot be responsible for any consequences of such changes in relation to this report unless we have been given the opportunity to review our interpretations and recommendations. Based on that review, we can provide written modifications or confirmation, as appropriate.

Environmental Concerns Are Not Covered

Unless environmental services were specifically included in our scope of services, this report does not provide any environmental findings, conclusions, or recommendations, including but not limited to, the likelihood of encountering underground storage tanks or regulated contaminants.

Subsurface Conditions Can Change

This geotechnical or geologic report is based on conditions that existed at the time the study was performed. The findings and conclusions of this report may be affected by the passage of time, by man-made events such as construction on or adjacent to the site, new information or technology that becomes available subsequent to the report date, or by natural events such as floods, earthquakes, slope instability or groundwater fluctuations. If more than a few months have passed since issuance of our report or work product, or if any of the described events may have occurred, please contact GeoEngineers before applying this report for its intended purpose so that we may evaluate whether changed conditions affect the continued reliability or applicability of our conclusions and recommendations.

Geotechnical and Geologic Findings Are Professional Opinions

Our interpretations of subsurface conditions are based on field observations from widely spaced sampling locations at the site. Site exploration identifies the specific subsurface conditions only at those points where subsurface tests are conducted, or samples are taken. GeoEngineers reviewed field and laboratory data and then applied its professional judgment to render an informed opinion about subsurface conditions at other locations. Actual subsurface conditions may differ, sometimes significantly, from the opinions presented in this report. Our report, conclusions and interpretations are not a warranty of the actual subsurface conditions.

Geotechnical Engineering Report Recommendations Are Not Final

We have developed the following recommendations based on data gathered from subsurface investigation(s). These investigations sample just a small percentage of a site to create a snapshot of the subsurface conditions elsewhere on the site. Such sampling on its own cannot provide a complete and accurate view of subsurface conditions for the entire site. Therefore, the recommendations included in this report are preliminary and should not be considered final. GeoEngineers' recommendations can be finalized only by observing actual subsurface conditions revealed during construction. GeoEngineers cannot assume responsibility or liability for the recommendations in this report if we do not perform construction observation.

We recommend that you allow sufficient monitoring, testing and consultation during construction by GeoEngineers to confirm that the conditions encountered are consistent with those indicated by the



explorations, to provide recommendations for design changes if the conditions revealed during the work differ from those anticipated, and to evaluate whether earthwork activities are completed in accordance with our recommendations. Retaining GeoEngineers for construction observation for this project is the most effective means of managing the risks associated with unanticipated conditions. If another party performs field observation and confirms our expectations, the other party must take full responsibility for both the observations and recommendations. Please note, however, that another party would lack our project-specific knowledge and resources.

A Geotechnical Engineering or Geologic Report Could Be Subject to Misinterpretation

Misinterpretation of this report by members of the design team or by contractors can result in costly problems. GeoEngineers can help reduce the risks of misinterpretation by conferring with appropriate members of the design team after submitting the report, reviewing pertinent elements of the design team's plans and specifications, participating in pre-bid and preconstruction conferences, and providing construction observation.

Do Not Redraw the Exploration Logs

Geotechnical engineers and geologists prepare final boring and testing logs based upon their interpretation of field logs and laboratory data. The logs included in a geotechnical engineering or geologic report should never be redrawn for inclusion in architectural or other design drawings. Photographic or electronic reproduction is acceptable, but separating logs from the report can create a risk of misinterpretation.

Give Contractors a Complete Report and Guidance

To help reduce the risk of problems associated with unanticipated subsurface conditions, GeoEngineers recommends giving contractors the complete geotechnical engineering or geologic report, including these "Report Limitations and Guidelines for Use." When providing the report, you should preface it with a clearly written letter of transmittal that:

- advises contractors that the report was not prepared for purposes of bid development and that its accuracy is limited; and
- encourages contractors to confer with GeoEngineers and/or to conduct additional study to obtain the specific types of information they need or prefer.

Contractors Are Responsible for Site Safety on Their Own Construction Projects

Our geotechnical recommendations are not intended to direct the contractor's procedures, methods, schedule or management of the work site. The contractor is solely responsible for job site safety and for managing construction operations to minimize risks to on-site personnel and adjacent properties.

Biological Pollutants

GeoEngineers' Scope of Work specifically excludes the investigation, detection, prevention or assessment of the presence of Biological Pollutants. Accordingly, this report does not include any interpretations, recommendations, findings or conclusions regarding the detecting, assessing, preventing or abating of Biological Pollutants, and no conclusions or inferences should be drawn regarding Biological Pollutants as they may relate to this project. The term "Biological Pollutants" includes, but is not limited to, molds, fungi, spores, bacteria and viruses, and/or any of their byproducts.

A Client that desires these specialized services is advised to obtain them from a consultant who offers services in this specialized field.



