





# SKSD LANCASTER PROFESSIONAL CENTER

## 2018 BOND: CONSTRUCTION, RENOVATION, REPAIR 2021 RENOVATION AND REPAIR PROJECTS

### SYMBOLS / LEGEND



### MATERIAL REFERENCE



### ABBREVIATIONS

AB	ANCHOR BOLT	DF	DRINKING FOUNTAIN	GA	GAGE	MATL	MATERIAL	PAF	POWDER ACTUATED	S	SOUTH	VCT	VINYL COMPOSITION TILE
ACST	ACOUSTIC	DIA	DIAMETER	GALV	GALVANIZED	MAX	MAXIMUM	RC	RESILIENT CHANNEL	SC	SOLID CORE	VERT	VERTICAL
ADJ	ADJUSTABLE, ADJUST	DIM	DIMENSION	GB	GRAB BAR	MB	MACHINE BOLT	RD	ROOF DRAIN	SCR	SCREW	VNR	VEENER
AFF	ABOVE FINISHED FLOOR	DIV	DIVIDE, DIVIDED, DIVISION	GL	GLASS	MECH	MECHANICAL	RECEP	RECEPTACLE	SD	SOAP DISPENSER, SMOKE DETECTOR, STORM DRAIN	VTR	VENT THROUGH ROOF
ALUM	ALUMINUM	DR	DOOR	GLB	GLU-LAM BEAM	MFR	MANUFACTURER	REF	REFERENCE, REFRIGERATOR	SH	SHED	W	WAINSCOT
ANOD	ANODIZED	DS	DOWNSPOUT	GYP BD	GYPSUM BOARD	MH	MANHOLE	REIN	REINFORCE, REINFORCEMENT	SHG	SHED	WB	WEST, WIDE, WIDTH
APPROX	APPROXIMATELY	DTL	DETAIL	HB	HOSE BIBB	MI	MIRROR	REQD	REQUIRED	SHT	SHEET	WC	WATER CLOSET
ASPH	ASPHALT	DWG	DRAWING	HCP	HANDICAP, HOLLOW CORE	MIN	MINIMUM	REV	REVISION, REVISED	SIM	SIMILAR	WD	WOOD
BD	BOARD	E	EAST	HDR	HEADER	MISC	MISCELLANEOUS	R	RADIUS, RISER	SQ	SQUARE	WDW	WINDOW
BLDG	BUILDING	EA	EACH	HDW	HARDWARE	MO	MOUNT	RC	ROOF CATCHER	SST	STAINLESS STEEL	WH	WATER HEATER
BLKG	BLOCKING	EF	EXHAUST FAN	HC	HOLLOW CORE	MT	MOUNT	RD	ROOF DRAIN	STD	STANDARD	W/O	WITHOUT
BM	BENCH MARK, BEAM	EJ	EXPANSION JOINT	HORIZ	HORIZONTAL	MTL	METAL	REF	REFERENCE, REFRIGERATOR	STL	STEEL	WP	WATERPROOFING
BOT	BOTTOM	EL	ELEVATION	HS	HOLLOW STEEL	N	NORTH	REF	REFERENCE, REFRIGERATOR	STR	STRUCTURE, STRUCTURAL	WRB	WEATHER RESISTIVE
BUR	BUILT-UP ROOFING	ELEC	ELECTRIC, ELECTRICAL	HT	HIGH STRENGTH	NIC	NOT IN CONTRACT	REIN	REINFORCE, REINFORCEMENT	STRUC	STRUCTURE, STRUCTURAL	WT	WEIGHT
CAB	CABINET	ELEV	ELEVATOR	HT	HEIGHT	NL	NIGHT LIGHT	REQD	REQUIRED	SUSP	SUSPENDED	WWF	WELDED WIRE FABRIC
CB	CATCH BASIN, CORNER BEAD	ENCL	ENCLOSURE	HVAC	HEATING VENTILATING	NO	NUMBER	REV	REVISION, REVISED	T	TEMPERED, TREAD		
CG	CORNER GUARD	EQ	EQUIPMENT	HW	HOT WATER	NTS	NOT TO SCALE	RHWS	ROUND HEAD WOOD SCREW	T&G	TONGUE & GROOVE		
CHBD	CHALKBOARD	EW	EACH WAY	INSUL	INSULATE, INSULATED, INSULATION	OA	OVERALL OUTSIDE AIR	RO	ROUGH OPENING	THK	THICK, THICKNESS, THICKENED		
CI	CAST IRON	EXIST	EXISTING	INT	INTERIOR	OBS	OBSCURE	ROW	RIGHT OF WAY	TOC	TOP OF CURB		
CJ	CONTROL JOINT	EXP B	EXPANSION BOLT	INV	INVERT	OC	ON CENTER			TPD	TOILET PAPER DISPENSER		
CLG	CEILING	EXT	EXTERIOR	JAN	JANITOR	OCEW	ON CENTER EACH WAY			TYP	TYPICAL		
CLR	CLEAR, CLEARANCE			JST	JOINT BOX	OD	OUTSIDE DIAMETER						
CMU	CONCRETE MASONRY UNIT			JOINT	JOINT	OFCI	OWNER FURNISHED- CONTRACTOR INSTALLED						
COL	COLUMN	FD	FLOOR DRAIN	KD	KNOCKED DOWN	OH	OWNER FURNISHED- OWNER INSTALLED						
CONC	CONCRETE	FDN	FOUNDATION	LAM	LAMINATE	OPG	OWNER PROVIDED						
CONSTR	CONSTRUCTION	FE	FIRE EXTINGUISHER	LAV	LAVATORY	OPF	OWNER PROVIDED						
CONT	CONTINUOUS, CONTINUE	FEC	FIRE EXTINGUISHER CABINET	LS	LANDSCAPING								
CONTR	CONTRACTOR	FH	FIRE HYDRANT	LT	LIGHT								
CNTR	COUNTER	FHWS	FLATHEAD WOOD SCREW										
CRS	COURSE, COURSES	FIN	FINISH, FINISHED										
CSK	COUNTERSINK, COUNTERSUNK	FIN FLR	FINISHED FLOOR										
CW	COLD WATER	FL	FLOOR										
		FLASH	FLASHING										
		FTG	FOOTING										
		FOS	FACE OF STUD										

### CODE SUMMARY

GOVERNING BUILDING CODE: OSSC 2019 (IBC 2018)

THIS PROJECT COMPRISES INTERIOR REMODEL TO SELECT AREAS, ENTRY REMODEL FOR IMPROVED SECURITY, EXTERIOR SEAL IMPROVEMENTS, INTERIOR FINISH UPGRADES, SITE REPAIRS, LOW VOLTAGE IMPROVEMENTS, AND HVAC SYSTEM REPLACEMENT.

ZONING CODE	CO - COMMERCIAL OFFICE
PLANNING ZONE	
LOT COVERAGE	81,022 SF
LOT AREA	60%
MAX BUILDING LOT COVERAGE ALLOWED	18,810 SF = 23%<60%
BUILDING AREA FOOTPRINT	
PARKING	
MINIMUM REQUIRED:	100
MAXIMUM ALLOWED:	175
TOTAL PROVIDED:	110
ACCESSIBLE REQUIRED:	5
ACCESSIBLE PROVIDED:	5
BICYCLE REQUIRED:	10
BICYCLE PROVIDED:	9 (EXISTING TO REMAIN)
LANDSCAPING	
LANDSCAPING REQUIRED:	12,160 SF (15%)
LANDSCAPING PROVIDED:	16,891 SF
PLANTING REQUIRED:	1 PU PER 20 SF = 844 PU
EXISTING PLANTING:	514 PU
TOTAL NEW PLANTING PROVIDED:	564 PU


BUILDING CODE	
OCCUPANCY GROUP	B
CONSTRUCTION TYPE	V-B
REMODEL	NON FIRE-SPRINKLERED
ALLOWABLE BUILDING AREA	
(B OCC) BASIC ALLOWABLE	= 9,000 SF
FRONTAGE INCREASE (I)	= # SF
(B OCC) FIRST FLOOR ACTUAL AREA	= 18,600 SF
(B OCC) SECOND FLOOR ACTUAL AREA	= 16,557 SF
EXISTING NON-CONFORMING	
OCCUPANT LOAD	
FIRST FLOOR	
BUSINESS: 11394 SF/150 SF PER OCC	= 76
UNCONCENTRATED: 1172 SF/15 SF PER OCC	= 78
CONCENTRATED: 151 SF/7 SF PER OCC	= 22
STORAGE: 1000 SF/300 SF PER OCC	= 3
SECOND FLOOR	
BUSINESS: 11214 SF/150 SF PER OCC	= 75
UNCONCENTRATED: 2206 SF/15 SF PER OCC	= 147
STORAGE: 480 SF/300 SF PER OCC	= 2
TOTAL BUILDING OCCUPANT LOAD:	= 403
MEANS OF EGRESS	
EXITS REQUIRED:	2
EXITS PROVIDED:	2
EXIT WIDTH REQUIRED: 0.2FACTORxTOTAL OC	= 80.6 IN
EXIT WIDTH PROVIDED: # EXITSxWIDTH	= 108 IN
PLUMBING FIXTURES	
OCCUPANCY GROUP B:	
WATER CLOSETS REQUIRED:	10
WATER CLOSETS PROVIDED:	13
LAVATORIES REQUIRED:	7
LAVATORIES PROVIDED:	8

### PROJECT DIRECTORY

OWNER:	SALEM-KEIZER PUBLIC SCHOOLS 3530 STATE STREET SALEM, OREGON 97301 CONTACT: JOEL SMALLWOOD MANAGER CONSTRUCTION SERVICES PHONE: (503) 391-1133
ARCHITECT:	CARLSON VEIT JUNGE ARCHITECTS PC 3095 RIVER ROAD N SALEM, OREGON 97303 PHONE: (503) 390-0281 FAX: (503) 390-2459
STRUCTURAL ENGINEER:	MSC ENGINEERS, INC. 3470 PIPEBEND PLACE NE SUITE 120 SALEM, OREGON 97301 PHONE: (503) 399-1399 FAX: (503) 399-8259
MECHANICAL ENGINEER:	MIFA INC, CONSULTING ENGINEERS 2007 SE ASH STREET PORTLAND, OREGON 97214 PHONE: (503) 234-0548 FAX: (503) 234-0677
ELECTRICAL ENGINEER:	MLC ENGINEERING, LLC 1515 SW FIFTH AVENUE #1028 PORTLAND, OREGON 97201 PHONE: (503) 220-0168
CIVIL ENGINEER:	WESTTECH ENGINEERING, INC. 3841 FAIRVIEW INDUSTRIAL DRIVE SE, SUITE 100 SALEM, OREGON 97302 PHONE: (503) 585-3986 FAX: (503) 585-3986

### INDEX OF DRAWINGS

GENERAL	TITLE SHEET
G-001	
CIVIL	
C0.0	COVER SHEET
C002	EXISTING CONDITIONS PLAN
C1.0	PRE-DEVELOPED EROSION CONTROL PLAN
C1.1	POST-DEVELOPED EROSION CONTROL PLAN
C1.2	EROSION CONTROL NOTES
C1.3	EROSION CONTROL NOTES
C1.4	EROSION CONTROL DETAILS
C2.0	GRADING AND SURFACING PLAN
C3.0	CONSTRUCTION NOTES
C4.0	CONSTRUCTION DETAILS
STRUCTURAL	
SEE SEPARATE STRUCTURAL CALCULATIONS PACKAGE FOR DETAILS S1 THROUGH S.7	
ARCHITECTURAL	
A-100	EXISTING SITE PLAN
A-101	SITE PLAN - NEW WORK
A-102	FIRST FLOOR DEMOLITION PLAN
A-103	SECOND FLOOR DEMOLITION PLAN
A-104	FIRST FLOOR NEW WORK PLAN
A-105	SECOND FLOOR NEW WORK PLAN
A-106	FIRST FLOOR REFLECTED CEILING PLAN
A-107	SECOND FLOOR REFLECTED CEILING PLAN
A-108	ROOF PLAN
A-201	EXTERIOR ELEVATIONS
A-202	INTERIOR ELEVATIONS
A-501	DETAILS
A-502	DETAILS
A-701	FIRST FLOOR FINISH PLAN
A-702	SECOND FLOOR FINISH PLAN
MECHANICAL	
M-101	FIRST FLOOR MECHANICAL DEMO PLANS
M-102	SECOND FLOOR MECHANICAL DEMO PLANS
M-103	ROOF MECHANICAL DEMO PLANS
M-201	FIRST FLOOR MECHANICAL NEW PLANS
M-202	SECOND FLOOR MECHANICAL NEW PLANS
M-203	ROOF MECHANICAL NEW PLANS
M-600	MECHANICAL SCHEDULES
M-601	MECHANICAL SCHEDULES
M-602	MECHANICAL SCHEDULES
M-603	MECHANICAL SCHEDULES
M-610	MECHANICAL DETAILS
M-611	MECHANICAL DETAILS
ELECTRICAL	
E-001	ELECTRICAL SYMBOLS AND ONE-LINE DIAGRAM
E-002	ELECTRICAL SCHEDULES
E-101D	FIRST FLOOR ELECTRICAL DEMOLITION
E-102D	SECOND FLOOR ELECTRICAL DEMOLITION
E-103D	ROOF PLAN ELECTRICAL DEMOLITION
E-110	ELECTRICAL SITE PLAN
E-201	FIRST FLOOR LIGHTING
E-202	SECOND FLOOR LIGHTING
E-301	FIRST FLOOR POWER AND COMMUNICATIONS
E-302	SECOND FLOOR POWER AND COMMUNICATIONS
E-303	ROOF PLAN POWER AND COMMUNICATIONS



project: SKSD LANCASTER PROFESSIONAL CENTER  
2018 BOND: CONSTRUCTION, RENOVATION, REPAIR  
2021 RENOVATION AND REPAIR PROJECTS  
2450 LANCASTER DRIVE NE, SALEM, OREGON 97305  
consultants:

revisions:	
1	04-22-2021 BID SET
4	09-17-21 SPR REVISIONS

date: 04-01-2021  
project: 05420  
dwg file: A-101-X-05420  
drawn by: KG  
checked by: AMF  
copyright © 2020  
Carlson Veit Junge Architects PC

### TITLE SHEET

sheet: G-001  
of:


PERMIT SET



DRAWINGS FOR:  
SKSD LANCASTER PROFESSIONAL CENTER


FOR:  
CARLSON VEIT JUNGE ARCHITECTS PC  
3095 RIVER RD N,  
SALEM, OREGON 97303

PROJECT LOCATION



VICINITY MAP

PROJECT LOCATION



NOTES:

1. STORM SYSTEM UTILITIES SHOWN ARE BASED ON UNDERGROUND UTILITY LOCATE MARKINGS PROVIDED PER UTILITY LOCATE TICKET NUMBERS 21040470, 21040473 AND 21040475 AND PRIVATE LOCATES. THE SURVEYOR MAKES NO GUARANTEE THAT THE UNDERGROUND LOCATES REPRESENT THE ONLY STORM UTILITIES IN THE AREA. OTHER UTILITY LOCATES WERE NOT INCLUDED AS A PART OF THIS SURVEY. CONTRACTORS ARE RESPONSIBLE FOR VERIFYING ALL EXISTING CONDITIONS PRIOR TO BEGINNING CONSTRUCTION.
2. FIELD WORK WAS CONDUCTED FEBRUARY 16 AND 24, 2021.
3. VERTICAL DATUM: ELEVATIONS ARE BASED ON NGS BENCHMARK QE0364, LOCATED 25 FEET SOUTH OF THE CENTERLINE OF MCGILCHRIST STREET SE AND 10 FEET WEST OF THE WEST RAIL OF A RAILROAD TRACK, IN A CONCRETE HEADWALL. ELEVATION = 185.16 FEET (NAVD88) THEN ADJUSTED TO NGVD29 WITH A VERTCON SHIFT OF -3.37 FEET, SETTING THE NGVD29 ELEVATION AT 181.79 FEET.
4. HORIZONTAL DATUM: A LOCAL DATUM PLANE DERIVED FROM STATE PLANE OREGON NORTH 3601 NAD83 (2011) EPOCH 2010.0000 BY MULTIPLYING BY A PROJECT MEAN GROUND COMBINED SCALE FACTOR OF 1.0001164613 AT A CENTRAL PROJECT POINT WITH INTERNATIONAL FEET STATE PLANE GRID COORDINATES N: 455068.835 E: 7534008.170 AND A MERIDIAN CONVERGENCE ANGLE OF -149.42". STATE PLANE COORDINATES WERE DERIVED FROM GPS OBSERVATIONS USING THE TRIMBLE VRS NOW NETWORK. DISTANCES SHOWN ARE INTERNATIONAL FEET GROUND VALUES.
4. THIS IS NOT A PROPERTY BOUNDARY SURVEY TO BE RECORDED WITH THE COUNTY SURVEYOR. BOUNDARIES MAY BE PRELIMINARY AND SHOULD BE CONFIRMED WITH THE STAMPING SURVEYOR PRIOR TO RELYING ON FOR DETAILED DESIGN OR CONSTRUCTION.
5. BUILDING FOOTPRINTS ARE MEASURED TO SIDING UNLESS NOTED OTHERWISE. CONTACT SURVEYOR WITH QUESTIONS REGARDING BUILDING TIES.
6. CONTOUR INTERVAL IS 1 FOOT.
7. TREES WITH DIAMETER OF 6" AND GREATER ARE SHOWN. TREE DIAMETERS WERE DETERMINED BY VISUAL INSPECTION. TREE INFORMATION IS SUBJECT TO CHANGE UPON ARBORIST INSPECTION.
8. UNDERGROUND UTILITY LINES FOR THIS STRUCTURE WERE NOT INCLUDED IN THE SCOPE OF THIS SURVEY. UTILITY LINES MAY EXIST IN THIS AREA.
9. THIS AREA IS IDENTIFIED AS A STORM STORAGE BASIN PER CITY OF SALEM GIS.



Know what's below.  
Call before you dig.


SHEET SET

SHT NO	DESCRIPTION
C0.0	COVER SHEET, INDEX, & VICINITY MAP
C1.0	PRE-DEVELOPED EROSION CONTROL PLAN
C1.1	POST-DEVELOPED EROSION CONTROL PLAN
C1.2	EROSION CONTROL NOTES
C1.3	EROSION CONTROL NOTES
C1.4	EROSION CONTROL DETAILS
C2.0	GRADING AND SURFACING PLAN
C3.0	CONSTRUCTION NOTES
C4.0	CONSTRUCTION DETAILS




3841 Fairview Industrial Dr. S.E., Suite 100, Salem, OR 97302  
Phone: (503) 585-2474 Fax: (503) 585-3986  
E-mail: westech@westech-eng.com

CARLSON  
VEIT  
JUNGE  
ARCHITECTS PC



ARCHITECTURE • INTERIOR DESIGN  
3095 RIVER RD N. SALEM, OREGON 97303  
WWW.CARLSONVEIT.COM • 503-390-0281



project:  
SKSD LANCASTER PROFESSIONAL CENTER  
2018 BOND: CONSTRUCTION, RENOVATION, REPAIR  
2021 RENOVATION AND REPAIR PROJECTS  
2450 LANCASTER DRIVE NE, SALEM, OREGON 97305

revisions:  
1 04/22/2021

date: 04-01-2021  
project: 05420  
dwg file: A-101-X-05420  
drawn by: IH  
checked by: JW  
copyright © 2020  
Carlson Veit Junge Architects PC

COVER SHEET

sheet:

C0.0

of:

BID SET



LANCASTER DRIVE

48'

TAX LOT 900  
TAX MAP 07 2W 18CA


S88°12'12"E 384.69'

VARIABLE WIDTH EASEMENT FOR  
RIGHT-OF-WAY PER REEL 303 PAGE 118

LANCASTER DEVELOPMENT  
CENTER BUILDING

TAX LOT 300  
TAX MAP 07 2W 18CD

TAX LOT 100  
TAX MAP 07 2W 18CD



NOTES:

1. STORM SYSTEM UTILITIES SHOWN ARE BASED ON UNDERGROUND UTILITY LOCATE MARKINGS PROVIDED PER UTILITY LOCATE TICKET NUMBERS 21040470, 21040473 AND 21040475 AND PRIVATE LOCATES. THE SURVEYOR MAKES NO GUARANTEE THAT THE UNDERGROUND LOCATES REPRESENT THE ONLY STORM UTILITIES IN THE AREA. OTHER UTILITY LOCATES WERE NOT INCLUDED AS A PART OF THIS SURVEY. CONTRACTORS ARE RESPONSIBLE FOR VERIFYING ALL EXISTING CONDITIONS PRIOR TO BEGINNING CONSTRUCTION.
2. FIELD WORK WAS CONDUCTED FEBRUARY 16 AND 24, 2021.
3. VERTICAL DATUM: ELEVATIONS ARE BASED ON NGS BENCHMARK QEO364, LOCATED 25 FEET SOUTH OF THE CENTERLINE OF MCGILCHRIST STREET SE AND 10 FEET WEST OF THE WEST RAIL OF A RAILROAD TRACK, IN A CONCRETE HEADWALL. ELEVATION = 185.16 FEET (NAVD88) THEN ADJUSTED TO NGVD29 WITH A VERTCON SHIFT OF -3.37 FEET, SETTING THE NGVD29 ELEVATION AT 181.79 FEET.
4. HORIZONTAL DATUM: A LOCAL DATUM PLANE DERIVED FROM STATE PLANE OREGON NORTH 3601 NAD83 (2011) EPOCH 2010.0000 BY MULTIPLYING BY A PROJECT MEAN GROUND COMBINED SCALE FACTOR OF 1.0001164613 AT A CENTRAL PROJECT POINT WITH INTERNATIONAL FEET STATE PLANE GRID COORDINATES N:455068.835 E:7534008.170 AND A MERIDIAN CONVERGENCE ANGLE OF -1°49'42". STATE PLANE COORDINATES WERE DERIVED FROM GPS OBSERVATIONS USING THE TRIMBLE VRS NOW NETWORK. DISTANCES SHOWN ARE INTERNATIONAL FEET GROUND VALUES.
4. THIS IS NOT A PROPERTY BOUNDARY SURVEY TO BE RECORDED WITH THE COUNTY SURVEYOR. BOUNDARIES MAY BE PRELIMINARY AND SHOULD BE CONFIRMED WITH THE STAMPING SURVEYOR PRIOR TO RELYING ON FOR DETAILED DESIGN OR CONSTRUCTION.
5. BUILDING FOOTPRINTS ARE MEASURED TO SIDING UNLESS NOTED OTHERWISE. CONTACT SURVEYOR WITH QUESTIONS REGARDING BUILDING TIES.
6. CONTOUR INTERVAL IS 1 FOOT.
7. TREES WITH DIAMETER OF 6" AND GREATER ARE SHOWN. TREE DIAMETERS WERE DETERMINED BY VISUAL INSPECTION. TREE INFORMATION IS SUBJECT TO CHANGE UPON ARBORIST INSPECTION.
8. UNDERGROUND UTILITY LINES FOR THIS STRUCTURE WERE NOT INCLUDED IN THE SCOPE OF THIS SURVEY. UTILITY LINES MAY EXIST IN THIS AREA.
9. THIS AREA IS IDENTIFIED AS A STORM STORAGE BASIN PER CITY OF SALEM GIS.

CURVE TABLE				
CURVE	RADIUS	DELTA	LENGTH	CHORD
C1	29.00'	60°06'05"	30.42'	S27°42'34"E 29.04'

TREE TABLE		
TREE NUMBER	TYPE	DBH (IN.)
100006	DECIDUOUS	12 12
100007	DECIDUOUS	11 15
100008	DECIDUOUS	6 9 11
100009	DECIDUOUS	10 12

LEGEND

EXISTING

DECIDUOUS TREE  
CONIFEROUS TREE  
FIRE HYDRANT  
WATER METER  
WATER VALVE  
WATER IRRIGATION VALVE  
SANITARY SEWER CLEAN OUT  
SANITARY SEWER MANHOLE  
SIGN  
STREET LIGHT  
MAILBOX



EXISTING


STORM DRAIN CLEAN OUT  
STORM DRAIN CATCH BASIN  
STORM DRAIN AREA DRAIN  
STORM DRAIN MANHOLE  
STORM DRAIN DOWNSPOUT  
GAS METER  
GAS VALVE  
GUY WIRE ANCHOR  
UTILITY POLE  
TRAFFIC SIGNAL POLE  
POWER VAULT  
POWER JUNCTION BOX





RIGHT-OF-WAY LINE  
BOUNDARY LINE  
PROPERTY LINE  
HISTORIC PROPERTY LINE  
CENTERLINE  
DITCH  
CURB  
EDGE OF PAVEMENT  
EASEMENT  
STORM DRAIN LINE



EXISTING








consultants:



**consultants:**

PRE-DEVELOPED  
EROSION CONTROL  
PLAN

sheet: **C1.0**







CARLSON  
VEIT  
JUNGE  
ARCHITECTS PC  
• INTERIOR DESIGN

3095 RIVER RD N, SALEM, OREGON 97303  
WWW.CARLSONVEIT.COM • 503-390-02



RENEWS: 6/30/2022




# BID SET

project: **SKS LANCASTER PROFESSIONAL CENTER**  
2018 BOND: CONSTRUCTION, RENOVATION, REPAIR  
2021 RENOVATION AND REPAIR PROJECTS  
042450 LANCASTER DRIVE NE, SALEM, OREGON 97305

**consultants:**

revisions:  
1 04/22/2021



date: 04-01-2021

project: 05420

dwg file: A-101-X-05420

drawn by: IH

checked by: JW

copyright © 2020  
Carlson Veit Junge Architects PC

## POST-DEVELOPED EROSION CONTROL PLAN

sheet:

## C1.1

of:



**WESTECH ENGINEERING, INC.**  
CONSULTING ENGINEERS AND PLANNERS

3841 Fairview Industrial Dr. S.E., Suite 100, Salem, OR 97302  
Phone: (503) 585-2474 Fax: (503) 585-3986  
E-mail: [westech@westech-eng.com](mailto:westech@westech-eng.com)



DEQ EROSION CONTROL STANDARD NOTES:

1. Hold a pre-construction meeting of project construction personnel that includes the inspector to discuss erosion and sediment control measures and construction limits. (Schedule A.8.c.i.(3))
2. All inspections must be made in accordance with DEQ 1200–C permit requirements. (Schedule A.12.b and Schedule B.1)
3. Inspection logs must be kept in accordance with DEQ’s 1200–C permit requirements. (Schedule B.1.c and B.2)
4. Retain a copy of the ESCP and all revisions on site and make it available on request to DEQ, Agent, or the local municipality. During inactive periods of greater than seven (7) consecutive calendar days, the above records must be retained by the permit registrant but do not need to be at the construction site. (Schedule B.2.c)
5. All permit registrants must implement the ESCP. Failure to implement any of the control measures or practices described in the ESCP is a violation of the permit. (Schedule A 8.a)
6. The ESCP must be accurate and reflect site conditions. (Schedule A.12.c.i)
7. Submission of all ESCP revisions is not required. Submittal of the ESCP revisions is only under specific conditions. Submit all necessary revision to DEQ or Agent within 10 days. (Schedule A.12.c.iv. and v)
8. Phase clearing and grading to the maximum extent practical to prevent exposed inactive areas from becoming a source of erosion. (Schedule A.7.a.iii)
9. Identify, mark, and protect (by construction fencing or other means) critical riparian areas and vegetation including important trees and associated rooting zones, and vegetation areas to be preserved. Identify vegetative buffer zones between the site and sensitive areas (e.g., wetlands), and other areas to be preserved, especially in perimeter areas. (Schedule A.8.c.i.(1) and (2))
10. Preserve existing vegetation when practical and re-vegetate open areas. Re-vegetate open areas when practicable before and after grading or construction. Identify the type of vegetative seed mix used. (Schedule A.7.a.v)
11. Maintain and delineate any existing natural buffer within the 50–feet of waters of the state. (Schedule A.7.b.i.and (2)(a)(b))
12. Install perimeter sediment control, including storm drain inlet protection as well as all sediment basins, traps, and barriers prior to land disturbance. (Schedule A.8.c.i.(5))
13. Control both peak flow rates and total stormwater volume, to minimize erosion at outlets and downstream channels and streambanks. (Schedule A.7.c)
14. Control sediment as needed along the site perimeter and at all operational internal storm drain inlets at all times during construction, both internally and at the site boundary. (Schedule A.7.d.i)
15. Establish concrete truck and other concrete equipment washout areas before beginning concrete work. (Schedule A.8.c.i.(6))
16. Apply temporary and/or permanent soil stabilization measures immediately on all disturbed areas as grading progresses. Temporary or permanent stabilizations measures are not required for areas that are intended to be left unvegetated, such as dirt access roads or utility pole pads.(Schedule A.8.c.ii.(3))
17. Establish material and waste storage areas, and other non–stormwater controls. (Schedule A.8.c.i.(7))
18. Prevent tracking of sediment onto public or private roads using BMPs such as: construction entrance, graveled (or paved) exits and parking areas, gravel all unpaved roads located onsite, or use an exit tire wash. These BMPs must be in place prior to land–disturbing activities. (Schedule A 7.d.ii and A.8.c.i.(4))
19. When trucking saturated soils from the site, either use water–tight trucks or drain loads on site. (Schedule A.7.d.ii.(5))
20. Control prohibited discharges from leaving the construction site, i.e., concrete wash–out, wastewater from cleanout of stucco, paint and curing compounds. (Schedule A.6)
21. Use BMPs to prevent or minimize stormwater exposure to pollutants from spills; vehicle and equipment fueling, maintenance, and storage; other cleaning and maintenance activities; and waste handling activities. These pollutants include fuel, hydraulic fluid, and other oils from vehicles and machinery, as well as debris, fertilizer, pesticides and herbicides, paints, solvents, curing compounds and adhesives from construction operations. (Schedule A.7.e.i.(2))
22. Implement the following BMPs when applicable: written spill prevention and response procedures, employee training on spill prevention and proper disposal procedures, spill kits in all vehicles, regular maintenance schedule for vehicles and machinery, material delivery and storage controls, training and signage, and covered storage areas for waste and supplies. (Schedule A 7.e.iii.)
23. Use water, soil–binding agent or other dust control technique as needed to avoid wind–blown soil. (Schedule A 7.a.iv)
24. The application rate of fertilizers used to reestablish vegetation must follow manufacturer’s recommendations to minimize nutrient releases to surface waters. Exercise caution when using time–release fertilizers within any waterway riparian zone. (Schedule A.9.b.iii)
25. If an active treatment system (for example, electro–coagulation, flocculation, filtration, etc.) for sediment or other pollutant removal is employed, submit an operation and maintenance plan (including system schematic, location of system, location of inlet, location of discharge, discharge dispersion device design, and a sampling plan and frequency) before operating the treatment system. Obtain plan approval before operating the treatment system. Operate and maintain the treatment system according to manufacturer’s specifications. (Schedule A.9.d)
26. Temporarily stabilize soils at the end of the shift before holidays and weekends, if needed. The registrant is responsible for ensuring that soils are stable during rain events at all times of the year. (Schedule A 7.b)
27. As needed based on weather conditions, at the end of each workday soil stockpiles must be stabilized or covered, or other BMPs must be implemented to prevent discharges to surface waters or conveyance systems leading to surface waters. (Schedule A 7.e.ii.(2))
28. Construction activities must avoid or minimize excavation and bare ground activities during wet weather. (Schedule A.7.a.i)
29. Sediment fence: remove trapped sediment before it reaches one third of the above ground fence height and before fence removal. (Schedule A.9.c.i)
30. Other sediment barriers (such as biobags): remove sediment before it reaches two inches depth above ground height and before BMP removal. (Schedule A.9.c.i)
31. Catch basins: clean before retention capacity has been reduced by fifty percent. Sediment basins and sediment traps: remove trapped sediments before design capacity has been reduced by fifty percent and at completion of project. (Schedule A.9.c.iii& iv)
32. Within 24 hours, significant sediment that has left the construction site, must be remediated. Investigate the cause of the sediment release and implement steps to prevent a recurrence of the discharge within the same 24 hours. Any in–stream clean–up of sediment shall be performed according to the Oregon Division of State Lands required timeframe. (Schedule A.9.b.i)
33. The intentional washing of sediment into storm sewers or drainage ways must not occur. Vacuuming or dry sweeping and material pickup must be used to cleanup released sediments. (Schedule A.9.b.ii)
34. The entire site must be temporarily stabilized using vegetation or a heavy mulch layer, temporary seeding, or other method should all construction activities cease for 30 days or more. (Schedule A.7.f.i)
35. Provide temporary stabilization for that portion of the site where construction activities cease for 14 days or more with a covering of blown straw and a tackifier, loose straw, or an adequate covering of compost mulch until work resumes on that portion of the site. (Schedule A.7.f.ii)
36. Do not remove temporary sediment control practices until permanent vegetation or other cover of exposed areas is established. Once construction is complete and the site is stabilized, all temporary erosion controls and retained soils must be removed and disposed of properly, unless doing so conflicts with local requirements. (Schedule A.8.c.iii(1) and D.3.c.ii and iii)

Rev. 12/15/15 By: Krista Rotlifff

YEAR: MONTH:	'21 05	'21 06	'21 07	'21 08	'21 09	'21 10	'21 11	'21 12	'22 01	'22 02	'22 03	'22 04
CLEARING	X	X	X									
EXCAVATION	X	X	X	X								
GRADING	X	X	X	X	X							
CONSTRUCTION	X	X	X	X	X	X	X	X	X	X	X	
SEDIMENT CONTROLS:												
Silt Fencing	X	X	X	X	X	X	X	X	X	X	X	
Sediment Traps	X	X	X	X	X	X	X	X	X	X	X	
Sediment Basins	X											
Storm Inlet Protection	X	X	X	X	X	X	X	X	X	X	X	
Drainage Swales												
Check Dams												
Contour Furrows												
Terracing												
Pipe Slope Drains												
Rock Outlet Protection												
Gravel Construction Entrance												
Grass–lined Channel (Turf Reinforcement Mats)												
Protection of trees with construction fences												
Temporary Seeding and Planting												
Permanent Seeding and Planting	X	X	X	X	X	X	X	X	X	X	X	X
Other:												

CONTROL MEASURE	PHASE 1	PHASE 2	PHASE 3	PHASE 4	PHASE 5
Silt Fencing	X	X	X	X	
Construction Entrance	X	X			
Sediment Traps	X	X	X	X	
Storm Inlet Protection	X	X	X	X	
Concrete Washout					
Rock Outlet Protection			X	X	
Permanent Seeding and Planting					X
Phase 1: Prior to Ground Disturbance Phase 2: After Completion of Rough Grading Phase 3: After Installation of Storm Facilities Phase 4: After Paving & Construction Phase 5: After Project Completion and Cleanup					

INSPECTION FREQUENCY FOR BMP

Site Condition	Minimum Frequency
1. Active period	Daily when stormwater runoff, including runoff from snowmelt, is occurring.  At least once every 14 days, regardless of whether stormwater runoff is occurring.
2. Prior to the site becoming inactive or in anticipation of site inaccessibility.	Once to ensure that erosion and sediment control measures are in working order. Any necessary maintenance and repair must be made prior to leaving the site.
3. Inactive periods greater than seven (14) consecutive calendar days	Once every month.
4. Periods during which the site is inaccessible due to inclement weather	If practical, inspections must occur daily at a relevant and accessible discharge point or downstream location.
5. Periods during which discharge is unlikely due to frozen conditions	Monthly. Resume monitoring immediately upon melt, or when weather conditions make discharge likely.


BMP Rationale

A comprehensive list of available Best Management Practices (BMP) options based on DEQ’s 1200–C Permit Application and ESCP Guidance Document has been reviewed to complete this Erosion and Sediment Control Plan. Some of the above listed BMPs were not chosen because they were determined to not effectively manage erosion prevention and sediment control for this project based on specific site conditions, including soil conditions, topographic constraints, accessibility to the site, and other related conditions. As the project progresses and there is a need to revise the ESCP, an Action Plan will be submitted.


SOIL TYPE(S):	PER MARION CO. SOIL SURVEY THE SITE SOILS INCLUDE *CONCORD SILT LOAM AND WOODBURN SILT LOAM, 0 TO 3 PERCENT SLOPES*
EROSION HAZARD:	PER MARION CO. SOIL SURVEY EROSION HAZARD IS "SLIGHT"
SITE AREA:	1.86 AC
DISTURBANCE AREA:	0.21 AC

SUPPLEMENTAL WESTECH NOTES:

1. Erosion control measures shall be maintained in such a manner as to ensure that sediment and sediment–laden water does not enter the drainage system, roadways, or violate applicable water quality standards.
2. The erosion control construction, maintenance, replacement and upgrading of the erosion control facilities is the responsibility of the Contractor until all construction is completed and approved, and permanent erosion control (i.e. vegetation/landscaping) is established on all disturbed areas.
3. All recommended erosion control procedures are dependent on construction methods, staging, site conditions, weather and scheduling. During the construction period, erosion control facilities shall be upgraded as necessary due to unexpected storm events and to ensure that sediment and sediment laden water does not leave the site.
4. The Contractor is responsible for control of sediment transport within project limits. If an installed erosion control system does not adequately contain sediment on site, then the erosion control measures shall be adjusted or supplemented by the Contractor as necessary to ensure that sediment laden water does not leave the site. Additional measures shall be provided as required to ensure that all paved areas are kept clean for the duration of the project. Additional interim measures will include, at a minimum, installation of silt fences in accordance with the details shown on the drawings. These measures shall be installed along all exposed embankments and cut slopes to prevent sediment transport.
5. All existing and newly constructed storm inlets and drains shall be protected until pavement surfaces are completed and/or vegetation is established.
6. Erosion control facilities and sediment fences on active sites shall be inspected by the Contractor at least daily during any period with measurable precipitation. Any required repairs or maintenance shall be completed immediately. The erosion control facilities on inactive sites shall be inspected and maintained by the Contractor a minimum of once a month or within 24 hours following the start of a storm event.
7. All catch basins and conveyance lines shall be cleaned prior to paving. The cleaning operation shall not flush sediment–laden water into the downstream system. The Contractor shall remove all accumulated sediment from all impacted catch basins and storm pipes prior to acceptance by the Owner.
8. The Contractor is solely responsible for protection of all adjacent property and downstream facilities from erosion and siltation during project construction. Any damage resulting from such erosion and siltation shall be corrected at the sole expense of the Contractor.
9. The Contractor shall provide site watering as necessary to prevent wind erosion of fine–grained soils.
10. Unless otherwise indicated on the drawings, all temporary erosion control facilities, including sediment fences, silt sacks, bio–bags, etc. shall be removed by the Contractor within 30 days after permanent landscaping/vegetation is established.
11. Sediment fences shall be constructed of continuous filter fabric to avoid use of joints. When joints are necessary, filter cloth shall be spliced together only at a support post, with a minimum 6–inch overlap, and both ends securely fastened to a post.
12. Sediment fence shall be installed per drawing details. Sediment fences shall have adequate support to contain all silt and sediment captured.
13. The standard strength filter fabric shall be fastened securely to stitched loops installed on the upslope side of the posts, and 6 inches of the fabric shall be extended into the trench. The fabric shall not extend more than 30 inches above the original ground surface. Filter fabric shall not be stapled to existing trees.
14. Bio–filter bags shall be clean 100 percent wood product waste. Bags shall be 18–inch x 18–inch x 30–inch, weigh approximately 45 lbs., and be contained in a bag made of 1/2–inch plastic mesh.
15. Sediment barriers shall be maintained until the up–slope area has been permanently stabilized. At no time shall more than 10–inches of sediment be allowed to accumulate behind sediment fences. No more than 2 inches of sediment shall be allowed to accumulate behind bio–filter bags. Sediment shall be removed prior to reaching the above stated depths. New sediment barriers shall be installed uphill as required to control sediment transport.
16. Stabilized construction entrances shall be installed at the beginning of construction and maintained for the duration of the project. Additional measures may be required to ensure that all paved areas are kept clean for the duration of the project.
17. The Contractor shall verify that all trucks are well sealed when transporting saturated soils from the site. Water drippage from trucks transporting saturated soils must be reduced to less than 1 gallon per hour prior to leaving the site.
18. The entrance shall be maintained in a condition that will prevent tracking or flow of mud onto the public right–of–way or approved access point. The entrance may require periodic top dressing as conditions demand, and repair and/or cleanout of any structures used to trap sediment.
19. All materials spilled, dropped, washed, or tracked from vehicles onto roadways or into storm drains must be removed immediately, and the Contractor shall provide protection of downstream inlets and catch basins to ensure sediment laden water does not enter the storm drain system.
20. Temporary grass cover measures must be fully established by October 15th, or other cover measures (ie. erosion control blankets with anchors, 3–inches minimum of straw mulch, 6 mil HDPE plastic sheet, etc.) shall be in place over all disturbed soil areas until April 30th. Grass protection shall be established on adequate grass stand for controlling erosion by October 15th, it is recommended that seeding and mulching occur by September 1st. Straw mulch, if used, shall not leave any bare ground visible through the straw.
21. Minimum wet weather slope protection. For slopes steeper than 3H:1V but less than 2H:1V, use Tensar/North American Green Type S150 erosion control blanket. For slopes 2H:1V or steeper, use Tensar/North American Green Type SC150 erosion control blanket. Use a minimum of 2–inches straw mulch or Tensar/North American Green Type S150 for slopes steeper than 3H:1V. Slope protection shall be placed on all disturbed areas immediately after completion of each section of construction activity, until the erosion control seeding has been established. As an option during temporary or seasonal work stoppages, a 6–mil HDPE plastic sheet may be placed on exposed slopes. The plastic sheet shall be provided with an anchor trench at the top and bottom of the slope, and shall be sandbagged on the slopes as required to prevent damage or displacement by wind.
22. Permanent erosion control vegetation on all embankments and disturbed areas shall be re–established as soon as construction is completed.
23. Soil preparation. Topsoil should be prepared according to landscape plans, if available, or recommendations of grass seed supplier. It is recommended that slopes be textured before seeding by rack walking (ie. driving a crawling tractor up and down the slopes to leave a pattern of cleat imprints parallel to slope contours) or other method to provide stable areas for seeds to rest.
24. When used, hydromulch shall be applied with grass seed at a rate of 2000 lbs. per acre between April 30 and June 10, or between September 1 and October 1. On slopes steeper than 10 percent, hydroseed and mulch shall be applied with a bonding agent (tackifier). Application rate and methodology to be in accordance with seed supplier recommendations.
25. When used in lieu of hydromulch, dry, loose, weed free straw used as mulch shall be applied at a rate of 4000 lbs. per acre (double the hydromulch application requirement). Anchor straw by working in by hand or with equipment (rollers, cleat trackers, etc.). Mulch shall be spread uniformly immediately following seeding.
26. When conditions are not favorable to germination and establishment of the grass seed, the Contractor shall irrigate the seeded and mulched areas as required to establish the grass cover.
27. Seeding. Recommended erosion control grass seed mix is as follows. Dwarf grass mix (low height, low maintenance) consisting of dwarf perennial ryegrass (80 % by weight), creeping red fescue (20 % by weight). Application rate shall be 100 lbs. per acre minimum.
28. Grass seed shall be fertilized at a rate of 10 lbs. per 1000 S.F with 16– 16–16 slow release type fertilizer. Development areas within 50 feet of water bodies and wetlands must use a non–phosphorous fertilizer.
29. Prior to starting construction contractor shall acquire the services of a DEQ Certified Erosion and Sediment Control Inspector and shall submit an "Action Plan" to DEQ indentifying their names, contact information, training and experience as required in Schedule A.6.b.i–iii of the 1200–C Permit
30. Contractor shall submit "Notice of Termination" to DEQ to end the 1200–C permit coverage once all soil disturbance activities have been completed and final stabilization of exposed soils has occurred.




3841 Fairview Industrial Dr. S.E., Suite 100, Salem, OR 97302  
Phone: (503) 585–2474 Fax: (503) 585–3986  
E–mail: westech@westech–eng.com



project: SKSD LANCASTER PROFESSIONAL CENTER  
2018 BOND: CONSTRUCTION, RENOVATION, REPAIR  
2021 RENOVATION AND REPAIR PROJECTS  
2450 LANCASTER DRIVE NE, SALEM, OREGON 97305

revisions:



date: 04-01-2021  
project: 05420  
dwg file: A-101-X-05420  
drawn by: IH  
checked by: JW  
copyright © 2020  
Carlson Veit Junge Architects PC  
EROSION CONTROL NOTES

sheet:

C1.2

of:

BID SET



CITY OF SALEM PUBLIC WORKS DESIGN  
STANDARDS:

Division 007 Appendix A—EPSC Plan Standard  
Notes

(a) PRE—CONSTRUCTION

- (1). Prior to any land disturbing activities, the boundaries of the clearing and grading limits, vegetated buffers, and any sensitive areas shown on this plan shall be clearly delineated in the field. Unless otherwise approved, no disturbance is permitted beyond the clearing limits. The Contractor must maintain the delineation for the duration of the project. Note: vegetated corridors to be delineated with orange construction fence or approved equal.
- (2). BMPs that must be installed prior to land disturbing activities are construction entrance, perimeter sediment control, and inlet protection.
- (3). Hold a preconstruction conference to review the EPSCP and with the City's Project Manager and Inspector.

(b) CONSTRUCTION

- (1). All sediment is required to stay on site. Sediment amounts greater than 1/2—cubic foot which leave the site must be cleaned up within 24 hours and placed back on the site and stabilized or properly disposed. Vacuuming or dry sweeping must be used to clean up released sediment and it must not be swept or washed into storm sewers, drainage ways, or water bodies. The cause of the sediment release must be found and prevented from causing a recurrence of the discharge within thesame 24 hours. Any in—stream clean up of sediment shall be performed according to the DSL required time frame.
- (2). Construction, maintenance, replacement, and upgrading of erosion prevention and sediment control facilities is the sole responsibility of the Contractor until all construction is completed, approved, and permanent erosion control (i.e., vegetation/landscaping) is established on all disturbed areas.
- (3). All recommended erosion prevention and sediment control procedures are dependent on construction methods, staging, site conditions, weather, and scheduling. During the construction period, erosion control facilities shall be revised, upgraded, replaced, or added, to comply with SRC and State and Federal regulatory requirements.
- (4). The Contractor is solely responsible for protection of all adjacent property and downstream facilities from erosion and siltation during project construction. Any damage resulting from such erosion and siltation shall be corrected at the sole expense of the Contractor.
- (5). When saturated soil is present, water—tight trucks must be used to transport saturated soils from the construction site. Soil may be drained on site at a designated location, using appropriate BMPs. Soil must be drained sufficiently to drip less than one gallon per hour prior to leaving the site.
- (6). All materials spilled, dropped, or washed into storm drains must be removed immediately, and the Contractor shall provide protection of downstream inlets and catch basins to ensure sediment—laden water does not enter the storm drain system.
- (7). All discharge of sediment—laden water must be treated with an appropriate BMP to remove sediment from discharge waters and to comply with SRC and State and Federal Regulatory Permits.
- (8). In areas subject to wind erosion, appropriate BMPs must be used which may include the application of fine water spraying, plastic sheeting, mulching, or other approved measures.
- (9). The EPSC measures and BMPs shown on this plan are the minimum requirements for anticipated site conditions. During the construction period, these measures shall be upgraded as needed to maintain compliance with all regulations.
- (10). The contractor shall provide onsite water or other appropriate BMPs to prevent dust and wind erosion of fine grain soils.
- (11). Disturbed areas must be stabilized after 14 days of inactivity, or immediately if rain is forecasted. See Subsection 7A.1(d)—Wet Weather Period.

- (12). During the wet weather work period or when rain is forecasted, all active and inactive soil stock piles must be covered with appropriate plastic sheeting. Plastic sheeting must cover the entire stock pile and be sufficiently anchored.

(c) POLLUTANTS, SOLID WASTE AND HAZARDOUS MATERIALS MANAGEMENT

- (1). Any use of toxic or other hazardous materials must include proper storage, application, and disposal.
- (2). The contractor is solely responsible to properly manage pollutants, hazardous wastes, used oils, contaminated soils, concrete waste, sanitary waste, liquid waste, or other toxic substances discovered or generated during construction to prevent leakage, spills or release of pollutants to the environment and surface waters.
- (3). Contractor shall develop a project specific written spill prevention and response procedures that includes employee training on spill prevention and proper disposal procedures; regular maintenance schedule for vehicles andmachinery; and material delivery and storage controls, signage, material use, and use of covered storage areas for waste and supplies. The plan shall comply with SRC and Federal and State requirements, and shall be available on site at all times.

(d) WET WEATHER PERIOD (OCTOBER 15 THROUGH APRIL 30)

- (1). Construction activities must avoid or minimize the duration of disturbed areas.
- (2). Temporary stabilization of the site including covering of bare soils with approved BMPs, must be installed at the end of the shift before a holiday or weekend, or at the end of each workday if rainfall is forecast in the next 24 hours.
- (3). Temporary stabilization or covering of soil stockpiles and protection of stockpiles located away from construction activity must occur at the end of each workday.

(e) MAINTENANCE

- (1). Erosion control measures shall be maintained in such a manner as to ensure that erosion is prevented and sediment—laden water does not enter a drainage system, roadway, or violate applicable water quality standards.
- (2). Sediment shall not be washed or swept into storm sewers, drainage ways, or water bodies.
- (3). Sediment must be removed from behind all sediment control measures when it has reached a height of 1/3 the barrier height, and prior to the control measures removal.
- (4). Removal of trapped sediment in a sediment basin or sediment trap or catch basins must occur when the sediment retention capacity has been reduced by 50 percent; is not functioning properly and/or at the completion of project.
- (5). Cleaning of all structures, inlet protection BMPs, and sump pumps must be completed regularly and as required to ensure structures and inlets function properly and flow freely.
- (6). Construction site exits shall be maintained in a condition that will prevent tracking or flow of mud onto the ROW or approved access point. The entrance may require periodic top dressing as conditions demand, and repair and/or cleanout of any structures used to trap sediment. Wheel washing shall be required to prevent sediment and material tracking on road surfaces if passive BMPs are not effective.

(f) INSPECTION

- (1). The EPSCP must be kept onsite at all times. All measures shown on the plan must be installed properly to ensure compliance with SRC and State and Regulatory permits, and that sediment does not enter a surface water system, roadway, or other properties.
- (2). Written EPSC inspection logs shall be maintained onsite and available to City inspectors upon request.
- (3). All BMPs shall be inspected at least every week. When a rainfall event exceeds 1/2—inch in a 24—hour period, daily inspection of the erosion controls, sediment controls, and discharge outfalls must be conducted and documented. Inspections shall be done by a representative of the permit registrant who is knowledgeable and experienced in the principles, practices, installation, and maintenance of erosion and sediment controls.

(g) INACTIVE CONSTRUCTION PERIODS AND POST—CONSTRUCTION

- (1). Should work cease in any area for 14 days, the inactive area must be stabilized with appropriate soil stabilization BMPs. If all construction activity ceases the entire site must be temporarily stabilized using vegetation, heavy mulch layer, temporary seeding, or other method.
- (2). All temporary erosion prevention and sediment control facilities shall be removed by the contractor within 30 days after permanent landscaping/vegetation is established and the threat of erosion and sediment transport has been mitigated.
- (3). Temporary grass cover measures must be fully established by October 15 or other cover measures (i.e., erosion control blankets with anchors, one—inch of straw mulch, six mil HDPE plastic sheet, etc.) shall be in place over all disturbed soil areas until April 30. To establish an adequate grass stand for controlling erosion by October 15, it is recommended that seeding and mulching occur by September 1.
- (4). Permanent erosion control vegetation on all embankments and disturbed areas shall be re—established as soon as construction is completed.

(h) SPECIFICATIONS

- (1). Soil preparation. Topsoil should be prepared according to the landscape plans, if available, or recommendations of the grass seed supplier. Slopes shall be textured before seeding by rack walking (i.e., driving a crawling tractor up and down the slopes to leave a pattern of cleat imprints parallel to slope contours) or other method to provide stable areas for seeds to rest.
- (2). Seeding. Erosion control grass seed mix shall be as follows: Dwarf grass mix (low height, low maintenance) consisting of dwarf perennial ryegrass (80 percent by weight), creeping red fescue (20 percent by weight). Application rate shall be 100 pounds per acre minimum.
- (3). Grass seed shall be fertilized at a rate of ten pounds per 1,000 square feet with 16—16—16 slow release type fertilizer. Disturbed areas within 50 feet of water bodies and wetlands must use a non—phosphorous fertilizer.
- (4). The application rate of fertilizers used to reestablish vegetation shall follow manufacturer's recommendations. Nutrient releases from fertilizers to surface waters shall be minimized. Time release fertilizers shall be used. Care shall be made in the application of fertilizers within any waterway riparian zone to prevent leaching into the waterway.
- (5). When used, hydromulch shall be applied with grass seed at a rate of 2,000 pounds per acre between April 30 and June 10, or between September 1 and October 1. On slopes steeper than ten percent, hydroseed and mulch shall be applied with a bonding agent (tackifier). Application rate and methodology shall be in accordance with seed supplier recommendations.

CARLSON  
VEIT  
JUNGE  
ARCHITECTS PC  
ARCHITECTURE • INTERIOR DESIGN  
3095 RIVER RD N. SALEM, OREGON 97303  
WWW.CARLSONVEIT.COM • 503-390-0281

REGISTERED PROFESSIONAL  
ENGINEER  
NOV. 12, 2005  
WILLIAM J. WELLS  
RENEWS: 6/30/2022  
**REVIEW**



project: SKSD LANCASTER PROFESSIONAL CENTER  
2018 BOND: CONSTRUCTION, RENOVATION, REPAIR  
2021 RENOVATION AND REPAIR PROJECTS  
2450 LANCASTER DRIVE NE, SALEM, OREGON 97305  
consultants:

revisions:



date: 04-01-2021  
project: 05420  
dwg file: A-101-X-05420  
drawn by: IH  
checked by: JW  
copyright © 2020  
Carlson Veit Junge Architects PC

EROSION CONTROL  
NOTES

sheet:





C1.3

of:

BID SET



9/20/2021 12:50:03 PM  
E:\DWGSet\Carl-\'SKSD - Lancaster DC\Civil\Plots\C1.2-C1.4 - EROSION CONTROL NOTES AND DETAILS.dwg,  
(C1.4 tab)



3841 Fairview Industrial Dr. S.E., Suite 100, Salem, OR 97302  
Phone: (503) 585-2474 Fax: (503) 585-3986  
E-mail: westech@westech-eng.com

**CARLSON VEIT JUNGE ARCHITECTS PC**

ARCHITECTURE • INTERIOR DESIGN

3095 RIVER RD N. SALEM, OREGON 97303  
WWW.CARLSONVEIT.COM • 503-390-0281

**REGISTERED PROFESSIONAL ENGINEER**


NOV. 12, 2005

**WILLIAM J. WELLS**

RENEW: 6/30/2022



project: **SKSD LANCASTER PROFESSIONAL CENTER**  
2018 BOND: CONSTRUCTION, RENOVATION, REPAIR  
2021 RENOVATION AND REPAIR PROJECTS  
2450 LANCASTER DRIVE NE, SALEM, OREGON 97305



date: 04-01-2021  
project: 05420  
dwg file: A-101-X-05420  
drawn by: IH  
checked by: JW  
copyright © 2020  
Carlson Veit Junge Architects PC

**EROSION CONTROL DETAILS**

sheet: **C1.4**  
of:

**BID SET**



9/20/2021 12:50:56 PM  
E:\DWG3\Carl-\SKSD - Lancaster DC\Civil\Plots\C2.0 - GRADING AND SURFACING PLAN.dwg, (C2.0 1nb)

40'

48'

LANCASTER DRIVE

40'

40'

30'

TAX LOT 900  
TAX MAP 07 2W 18CA

S88°12'12"E 384.69'

LANCASTER DEVELOPMENT  
CENTER BUILDING

TAX LOT 300  
TAX MAP 07 2W 18CD

REMOVE AND  
REPLACE TREE

WOLVERINE STREET

TAX LOT 601  
TAX MAP 07 2W 18CD



0 10 20 40  
FEET

### SURFACING LEGEND

	3" GRIND AND INLAY, 1/2" LEVEL 2 HMAC.
	3" GRIND PROTECT EXISTING ROCK. INSTALL 1/2" LEVEL 2 HMAC IN MAX 3" LIFTS TO RAISE GRADE TO DESIGN ELEVATIONS. INSTALL 3" OVERLAY WITH THE INLAY TO THE EAST.
	REMOVE AND REPLACE SIDEWALK.
	MONOLITHIC CURB AND SIDEWALK.
	TYPE "C" CURB.
	RESTRIPE LOADING AREA.
	RESTRIPE DIVIDER STRIPE.
	RESTRIPE ADA AS REQUIRED.
	RESTRIPE.

EX STM MH  
\*FLOW CONTROL  
W/DETACHED PIPE\*  
RIM: 198.94  
IE IN: 196.52 (6"E)  
IE OUT: 196.36 (6"S)  
SUMP: 193.42

EX STM CB  
RIM: 198.34  
IE IN: 196.40 (10"N)  
IE OUT: 196.48 (8"SW)  
SUMP: 195.46

EX STM CB  
RIM: 197.88  
IE IN: 196.62 (6"N)  
IE OUT: 196.44 (6"W)  
SUMP: 195.79

FG=199.70  
S4

FG=199.85±  
(MATCH EXTG)  
TC=FG=199.65±  
(MATCH EXTG)  
TC=FG=199.54

FG=199.84±  
(MATCH EXTG)  
TC=199.53

GRIND AND INLAY  
MATCH EXISTING GRADES

EX STM MH  
RIM: 199.06  
IE IN: 196.34 (6"NW)  
IE OUT: 195.56 (6"S)  
SUMP: 192.42

EX STM CI  
\*SOUTHERLY FLOW OBSERVED\*  
RIM: 196.53  
IE IN: 193.59 (6"N)  
IE OUT: 193.91 (10"S)  
SUMP: 192.73



WESTECH ENGINEERING, INC.  
CONSULTING ENGINEERS AND PLANNERS

3841 Fairview Industrial Dr. S.E., Suite 100, Salem, OR 97302  
Phone: (503) 585-2474 Fax: (503) 585-3986  
E-mail: westech@westech-eng.com

CARLSON  
VEIT  
JUNGE  
ARCHITECTS PC

ARCHITECTURE • INTERIOR DESIGN  
3095 RIVER RD N. SALEM, OREGON 97303  
WWW.CARLSONVEIT.COM • 503-390-0281

REGISTERED PROFESSIONAL  
ENGINEER  
REVIEW  
NOV. 12, 2020  
WILLIAM J. WELLS  
RENEWS: 6/30/2022



project: SKSD LANCASTER PROFESSIONAL CENTER  
2018 BOND: CONSTRUCTION, RENOVATION, REPAIR  
2021 RENOVATION AND REPAIR PROJECTS  
2450 LANCASTER DRIVE NE, SALEM, OREGON 97305  
consultants:

revisions:  
1 04/22/2021

date: 04-01-2021  
project: 05420  
dwg file: A-101-X-05420  
drawn by: IH  
checked by: JW  
copyright © 2020  
Carlson Veit Junge Architects PC

GRADING AND  
SURFACING PLAN

sheet:  
C2.0  
of:

BID SET



GENERAL NOTES

1. Contractor shall procure and conform to all construction permits required by the City of Salem and Marion County.
2. Owner to pay all project permit costs, including but not limited to utility tapping, TV, and chlorination costs. The Contractor shall coordinate with the Approving Agency to determine appropriate fees and provide the Owner with 48 hours notice prior to the required payment of fees or costs.
3. Oregon law requires the Contractor to follow rules adopted by the Oregon Utility Notification Center. Those rules are set forth in OAR 952–001–0010 through OAR 952–001–0090. Obtain copies of the rules by calling the center. (Note: the telephone number for the Oregon Utility Notification Center is 503–232–1987).
4. Contractor to notify City, County and all utility companies a minimum of 48 business hours (2 business days) prior to start of construction, and comply with all other notification requirements of the Approving Agency with jurisdiction over the work.
5. Contractor shall provide all bonds and insurance required by public and/or private agencies having jurisdiction. Where required by public and/or private agencies having jurisdiction, the Contractor shall submit a suitable maintenance bond prior to final payment.
6. For City Construction Permits, contact Salem Public Works Engineering Construction Management at 503–588–6211. For City Building Permits, contact Salem Permit Application Center at 503–588–6256.
7. Contractor to apply for services at the Permit Application Center (PAC office) for work to be done by City forces on public mains.
8. All materials and workmanship for facilities in street right–of–way or easements shall conform to Approving Agencies' construction specifications wherein each has jurisdiction, including but not limited to the City, County, Oregon Health Division (OHD) and the Oregon Department of Environmental Quality (DEQ).
9. Unless otherwise approved by the Public Works Director, construction of all public facilities shall be done between 7:00 a.m. and 6:00 p.m., Monday through Saturday.
10. The Contractor shall perform all work necessary to complete the project in accordance with the approved construction drawings including such incidentals as may be necessary to meet the Approving Agencies' requirements and provide a completed project.
11. Any inspection by the City, County or other Approving Agency shall not, in any way, relieve the Contractor from any obligation to perform the work in strict compliance with the contract documents, applicable codes, and Approving Agency requirements.
12. Contractor shall maintain one complete set of approved drawings on the construction site at all times whereon he will record all approved deviations in construction from the approved drawings, as well as the station locations and depths of all existing utilities encountered. These field record drawings shall be kept up to date at all times and shall be available for inspection by the Approving Agency or Owner's Representative upon request. Failure to conform to this requirement may result in delay in payment and/or final acceptance of the project.
13. Upon completion of construction of all new facilities, Contractor shall submit a clean set of field record drawings containing all as–built information to the Engineer. All information shown on the Contractor's field record drawings shall be subject to verification. If significant errors or deviations are noted, an as–built survey prepared and stamped by a registered professional Land Surveyor shall be completed at the Contractor's expense.
14. The contractor shall retain and pay for the services of a registered Civil Engineer and/or Land Surveyor licensed in the State of Oregon to establish construction control and perform initial construction surveys to establish the lines and grades of improvements as indicated on the drawings. Staking for buildings, structures, curbs, gravity drainage pipes/structures and other critical improvements shall be completed using equipment accurate to 0.04 feet horizontally and 0.02 feet vertically, or better. Use of GPS equipment for final construction staking of these critical improvements is prohibited. The registered professional surveyor shall provide the design engineer with copies of all grade sheets for construction staking performed for the project.
15. See architectural drawings for site lighting, site dimensioning, and continuation of all utilities.
- TRAFFIC CONTROL
16. Contractor shall erect and maintain barricades, warning signs, traffic cones (and all other traffic control devices required) per City, County and ODOT requirements in accordance with the current MUTCD (including Oregon amendments). Access to driveways shall be maintained at all times. All traffic control measures shall be approved and in place prior to any construction activity. Prior to any work in the existing public right–of–way, Contractor shall submit final traffic control plan to the Approving Agency for review and issuance of a Lane Closure or Work in Right–of–Way Permit.
- TESTING AND INSPECTION:
17. For public and private improvements, the Contractor shall be responsible to ensure that all required or necessary inspections are completed by authorized inspectors prior to proceeding with subsequent work which covers or that is dependent on the work to be inspected. Failure to obtain necessary inspection(s) and approval(s) shall result in the Contractor being fully responsible for all problems and/or corrective measures arising from uninspected work.
18. Unless otherwise specified, the attached "Required Testing and Frequency" table outlines the minimum testing schedule for private improvements on the project. This testing schedule is not complete, and does not relieve the Contractor of the responsibility of obtaining all necessary inspections or observations for all work performed, regardless of who is responsible for payment. Cost for retesting shall be borne by the Contractor.
- EXISTING UTILITIES & FACILITIES:
19. The location and descriptions of existing utilities shown on the drawings are

- compiled from available records and/or field surveys. The Engineer or utility companies do not guarantee the accuracy or the completeness of such records. Contractor shall field verify locations and sizes of all existing utilities prior to construction.
20. Utility locations are based on record information and should be field–verified. Call 1–800–332–2344 at least 48 hours prior to construction for on–site locating of utilities.
21. Contractor shall field verify location and depth of all existing utilities where new facilities cross. All utility crossings marked or shown on the drawings shall be potholed using hand tools or other non–invasive methods prior to excavating or boring. Contractor shall be responsible for exposing potential utility conflicts far enough ahead of construction to make necessary grade or alignment modifications without delaying the work. If grade or alignment modification is necessary, Contractor shall notify the Design Engineer, and the Design Engineer or the Owner's Representative shall obtain approval from the Approving Agency prior to construction.
22. The Contractor shall be responsible for locating and marking all existing survey monuments of record (including but not limited to property and street monuments) prior to construction. If any survey monuments are removed, disturbed or destroyed during construction of the project, the Contractor shall retain and pay for the services of a Registered Professional Surveyor licensed in the State of Oregon to reference and replace all such monuments prior to final payment. The monuments shall be replaced within a maximum of 90 days, and the County Surveyor shall be notified in writing as required by per ORS 209.150.
23. All facilities shall be maintained in–place by the Contractor unless otherwise shown or directed. Contractor shall take all precautions necessary to support, maintain, or otherwise protect existing utilities and other facilities at all times during construction. Contractor to leave existing facilities in an equal or better–than–original condition and to the satisfaction of the Approving Agency and Owner's Representative.
24. Utilities or interfering portions of utilities that are abandoned in place shall be removed by the Contractor to the extent necessary to accomplish the work. The Contractor shall plug the remaining exposed ends of abandoned utilities after appropriate verification procedures have taken place.
25. Contractor shall remove all existing signs, mailboxes, fences, landscaping, etc., as required to avoid damage during construction and replace them to existing or better condition.
26. The Contractor shall be responsible for managing construction activities to ensure that public streets and right–of–ways are kept clean of mud, dust or debris. Dust abatement shall be maintained by adequate watering of the site by the Contractor.
- GRADING, PAVING & DRAINAGE:
27. Unless otherwise noted, all grading, rocking and paving to conform to Oregon Standard Specifications for Construction (OSSC/ODOT/APWA), 2021 edition.
28. Clear and grub within work limits all surface vegetation, trees, stumps, brush, roots, etc. Do not damage or remove trees except as approved by the Owner's Representative or as shown on the drawings. Protect all roots two inches in diameter or larger.
29. Strip work limits, removing all organic matter, which cannot be compacted into a stable mass. All trees, brush, and debris associated with clearing, stripping or grading shall be removed and disposed of off–site.
30. Immediately following stripping and grading operations, compact subgrade to 92% of the maximum dry density per AASHTO T–180 test method (Modified Proctor). Subgrade must be inspected and approved by the Owner's authorized representative before placing, engineered fills or fine grading for base rock.
31. Engineered fills shall be constructed and compacted in 6" lifts over approved subgrade. All fills shall be engineered and comply with the Oregon Structural Specialty Code, with each lift compacted to 92% of the maximum dry density per AASHTO T–180 test method (Modified Proctor).
32. Granular baserock shall conform to the requirements of OSSC (ODOT/APWA) 02630.10 (Dense Graded Base Aggregate), with no more than 10% passing the #40 sieve and no more than 5% passing the #200 sieve.
33. Compact granular baserock to 92% of the maximum dry density per AASHTO T–180 test method (Modified Proctor). Written baserock compaction test results from an independent testing laboratory must be received by the Owner's authorized representative before placing AC pavement, and a finished rock grade proof–roll (witnessed by the Owners authorized representative) must be performed.
34. A.C. pavement shall conform to OSSC (ODOT/APWA) 00745 (Hot Mixed Asphalt Concrete Pavement) for standard duty mix. Unless otherwise specified or shown on the drawings, base lifts shall be 3/4" dense graded mix, while wearing courses shall be 1/2" dense graded mix. Unless otherwise specified or shown on the drawings, A.C. pavement for parking lots and streets shall be Level 2 mix (50 blow Marshall) per OSSC (ODOT/APWA) 00744.13. A.C. Pavement shall be compacted to a minimum of 91% of maximum density as determined by the Rice standard method. Written AC pavement compaction test results from an independent testing laboratory must be received by the Owner's authorized representative before final payment.
35. Pavement surface shall be a smooth, well–sealed, tight mat without depressions or bird baths. Bony or open graded pavement surfaces shall be repaired to the satisfaction of the Owner's authorized representative, prior to final acceptance of the work.
36. HMAC mixtures shall be placed only when the surface is dry and weather conditions are such that proper handling, finishing and compaction can be accomplished. In no case shall bituminous mixtures be placed when the surface temperature is below the minimum established under 2021 OSSC (ODOT/APWA) 00744.40 (AC – Season and Temperature Limitations) or the project specifications, whichever is more stringent.
37. Contractor shall protect new pavement against traffic as required, until it has cooled sufficiently to avoid tracking.
38. For parking lots or private access drives, the final lift of AC pavement shall not be placed until after the building is fully enclosed and

- weatherproof, unless otherwise approved by the Owner's authorized representative.
39. Unless otherwise shown on the drawings or details, straight grades shall be run between all finish grade elevations and/or finish contour lines shown (exception: where grades are shown across sidewalks, slopes shall be adjusted to ensure that maximum allowable sidewalk cross slopes are not exceeded).
40. Finish pavement grades at transition to existing pavement shall match existing pavement grades or be feathered past joints with existing pavement as required to provide a smooth, free draining surface.
41. All existing or constructed manholes, cleanouts, monument boxes, gas valves, water valves and similar structures shall be adjusted to match finish grade of the pavement, sidewalk, landscaped area or median strip wherein they lie. Verify that all valve boxes and risers are clean and centered over the operating nut.
42. Unless otherwise shown on the drawings, no cut or fill slopes shall be constructed steeper than 3H:1V.
43. Unless otherwise shown on the landscape plans, all planter areas, shall be backfilled with approved topsoil minimum 8" thick. Stripping materials shall not be used for planter backfill.
44. Contractor shall seed and mulch (uniformly by hand or hydroseed) all exposed slopes and disturbed areas which are not scheduled to be landscaped, including trench restoration areas. If the Contractor fails to apply seed and mulch in a timely manner during periods favorable for germination, or if the seeded areas fail to germinate, the Owner's Representative may (at his discretion) require the Contractor to install sod to cover such disturbed areas.
- CURBS & SIDEWALKS:
45. Unless otherwise shown or indicated on the drawings, 6–inches nominal curb exposure used for design of all parking lot and street grades.
46. Where new curbing connects to existing curbing or is installed along existing streets or pavement, the gutter grade shall match the existing street grades so as to allow drainage from the street to the gutter and through any transitions. The Contractor shall notify the Owner's Representative in writing of any grade discrepancies or problems prior to curb placement.
47. Contractor shall construct all handicap access ramps in accordance with current ADA requirements.
48. Sidewalks shall be a minimum of 4–inches thick and standard residential driveways shall be a minimum of 6–inches thick. Commercial use driveways and alley approaches shall be minimum 8–inches thick. All curbs, sidewalks and driveways shall be constructed using 3500–psi district (standard) concrete, and shall be cured with Type 1 or Type 10 clear curing compound. All sidewalks shall be ADA compliant.
49. Curb & sidewalk concrete shall be placed only during periods when it will not be damaged by rain (protect unhardened concrete from precipitation). Concrete shall not be placed on frozen baserock. Do not begin concrete placement until temperature in the shade is a minimum of 35F and rising, and stop placement if air temperature falls below 35F. Protect concrete from freezing for a minimum of 5 days after placement per OSSC (ODOT/APWA) 00440.40.d & 00756.40 or the project specifications, whichever is more stringent.
50. Contraction joints shall be installed directly over any pipes that cross under the sidewalk, to control cracking. In general, cracks in new curbs or sidewalks (at locations other than contraction joints) are not acceptable, and cracked panels shall be removed & replaced unless otherwise approved by the Approving Agency and the design engineer.
51. All sidewalks shall be ADA compliant. Direction of sidewalk cross slope shall conform with the slope direction shown on the grading plan. Sidewalk cross slopes shall not exceed 1:67 (1.5%) nor be less than 1%. Longitudinal slope shall not exceed 1:20 (5%).
52. Where trench excavation requires removal of PCC curbs and/or sidewalks, the curbs and/or sidewalks shall be sawcut and removed at a tooled joint unless otherwise authorized in writing by the Approving Agency. The sawcut lines shown on the drawings are schematic and not intended to show the exact alignment of such cuts.
53. Contractor is responsible for damage/vandalism of cone for first 24 hours of each pour.
54. Unless otherwise shown on the drawings, areas along curbs and sidewalks shall be backfilled with approved topsoil, as well as being seeded and mulched (or hydroseed).

REQUIRED TESTING AND FREQUENCY TABLE		Party Responsible for payment	
		Contractor	Others (see note 1)
Streets, Fire Lanes, Common Driveways, Parking Lots, Pads, Fills, etc.			
Subgrade	1 Test/4000 S.F./Lift (4 min), locations acceptable to approving agency (typically alternate sides of road or access aisles)	✓	See note 2 & note 3
Engineered Fills	1 Test/4000 S.F./Lift (4 min), locations acceptable to approving agency	✓	See note 2 & note 5
Baserock	1 Test/4000 S.F./Lift (4 min), locations acceptable to approving agency (typically alternate sides of road or access aisles)	✓	See note 2 & note 3
Asphalt	1 Test/6000 S.F./Lift (4 min), locations acceptable to AA (typ. alternate as above)	✓	See note 2
Piped Utilities, All			
Trench Backfill	1 Test/200 Foot Trench/Lift (4 min)	✓	See note 2
Trench AC Restoration	1 Test/300 Foot Trench (4 min)	✓	See note 2
Concrete, Block, etc.			
Slump, Air & Cylinders for structural & reinforced concrete, equipment slabs, curbs, sidewalks & PCC pavements. Unless otherwise specified, one set of cylinders per 100 cubic yards (or portion thereof) of each class of concrete placed per day. Slump & air tests required on same load as cylinders.		✓	See note 2
Note 1: "Others" refers to Owner's authorized Representative or Approving Agency as applicable. Contractor responsible for scheduling testing. All testing must be completed prior to performing subsequent work.			
Note 2: Testing must be performed by an approved independent testing laboratory.			
Note 3: In addition to in–place density testing, the subgrade and base rock shall be proof–rolled with a loaded 10 yard dump truck provided by the Contractor. Baserock proofroll shall take place immediately prior to (within 24 hours of) paving, and shall be witnessed by the Owner's authorized Representative or approving agency. Location and pattern of testing and proofroll to be as approved or directed by said Owner's authorized Representative or approving agency.			
Note 4: To be witnessed by the Owner's Representative or approving agency. The Contractor shall perform pretests prior to scheduling witnessed wateline or sanitary sewer pressure tests, or pipeline mandrel test.			
Note 5: The approved independent laboratory retained by the Contractor shall provide a certification (stamped by an engineer licensed in the State of Oregon) that the subgrade was prepared and all engineered fills were placed in accordance with the provisions of the construction drawings and the contract documents.			

9/20/2021 12:50:59 PM  
E:\DWGS\Carl–\SKSD – Lancaster DC\Civil\Plots\C3.0–C4.0 CONSTRUCTION NOTES AND DETAILS.dwg (C3.0 tab)

WE

WESTECH ENGINEERING, INC.  
CONSULTING ENGINEERS AND PLANNERS

3841 Fairview Industrial Dr. S.E., Suite 100, Salem, OR 97302  
Phone: (503) 585–2474 Fax: (503) 585–3986  
E–mail: westech@westech–eng.com

CARLSON  
VEIT  
JUNGE  
ARCHITECTS PC

ARCHITECTURE • INTERIOR DESIGN  
3095 RIVER RD. N. SALEM, OREGON 97303  
WWW.CARLSONVEIT.COM • 503-390-0281

REGISTERED PROFESSIONAL  
ENGINEER  
NOV. 12, 2005  
WILLIAM J. WELLS

RENEW: 6/30/2022

WORK & LEARN TIME  
SALESMAN  
PUBLIC SCHOOLS

BID SET

project:  
SKSD LANCASTER PROFESSIONAL CENTER  
2018 BOND: CONSTRUCTION, RENOVATION, REPAIR  
2021 RENOVATION AND REPAIR PROJECTS  
2450 LANCASTER DRIVE NE, SALEM, OREGON 97305

consultants:

revisions:  
1 04/22/2021  
2  
3  
4



date: 04-01-2021  
project: 05420  
dwg file: A-101-X-05420  
drawn by: IH  
checked by: JW  
copyright © 2020  
Carlson Veit Junge Architects PC

CONSTRUCTION NOTES

sheet:  
C3.0  
of:




9/20/2021 12:51:00 PM  
E:\DWGSET\Carl-X\SKSD - Lancaster DC\SKSD - Lancaster DC\Civil\Plots\C30-C40 CONSTRUCTION NOTES AND DETAILS.dwg (C4.0  
tab)




WESTECH ENGINEERING, INC.  
CONSULTING ENGINEERS AND PLANNERS

3841 Fairview Industrial Dr. S.E., Suite 100, Salem, OR 97302  
Phone: (503) 585-2474 Fax: (503) 585-3986  
E-mail: westech@westech-eng.com

CARLSON  
VEIT  
JUNGE  
ARCHITECTS PC




ARCHITECTURE • INTERIOR DESIGN  
3095 RIVER RD N. SALEM, OREGON 97303  
WWW.CARLSONVEIT.COM • 503-390-0281



project: SKSD LANCASTER PROFESSIONAL CENTER  
2018 BOND: CONSTRUCTION, RENOVATION, REPAIR  
2021 RENOVATION AND REPAIR PROJECTS  
2450 LANCASTER DRIVE NE, SALEM, OREGON 97305

consultants:

revisions:



date: 04-01-2021

project: 05420

dwg file: A-101-X-05420

drawn by: IH

checked by: JW

copyright © 2020  
Carlson Veit Junge Architects PC

CONSTRUCTION DETAILS

sheet:

C4.0

of:

BID SET




4 2 1



EXISTING SITE PLAN

1" = 20'-0"




EXISTING SITE SUMMARY

MAP 07 2W 18CD  
LOT 300 AREA: 81,022 SF, 1.86 AC

PARKING SUMMARY	
EXISTING PARKING:	
ACCESSIBLE SPACES	= 4
STANDARD SPACES	= 109
TOTAL PARKING SHOWN	= 113

CARLSON  
VEIT  
JUNGE  
ARCHITECTS PC



ARCHITECTURE • INTERIOR DESIGN  
3095 RIVER RD N. SALEM, OREGON 97303  
WWW.CARLSONVEIT.COM • 503-390-0281



project:  
**SKSD LANCASTER PROFESSIONAL CENTER**  
2018 BOND: CONSTRUCTION, RENOVATION, REPAIR  
2021 RENOVATION AND REPAIR PROJECTS  
2450 LANCASTER DRIVE NE, SALEM, OREGON 97305  
consultants:

revisions:	
1	04-22-2021 BID SET
2	06-10-2021 ADDENDUM #1
4	09-17-21 SPR REVISIONS

date: 04-01-2021  
project: 05420  
dwg file: A-101-X-05420  
drawn by: KG  
checked by: AMF  
copyright © 2020  
Carlson Veit Junge Architects PC

EXISTING SITE  
PLAN

sheet:  
**A-100**  
of:

PERMIT SET





- 1 REMOVE & REPLACE PORTION OF CONCRETE WALK & CURB, PROVIDE EXPANSION JOINT WHERE NEW CONC ABUTS EXIST CONC
- 2 REMOVE & REPLACE EXIST TREE & LANDSCAPE BED W/ LIKE MATERIALS
- 3 ASPHALT PAVING INLAY & OVERLAY, PROVIDE NEW STRIPING TO MATCH EXIST. PROTECT EXIST CURBS, UON. REMOVE & REINSTALL WHEEL STOPS
- 4 CONTROL JOINT
- 5 6" HIGH CHAIN LINK FENCING TRASH ENCLOSURE W/ PRIVACY SLATS, SEE DTL 1 / A-101
- 6 EMERGENCY GENERATOR ON EXIST CONC PAD, PROVIDE 36" CLR ON ALL SIDES
- 7 4" WIDE PAINTED STRIPE
- 8 PAINTED SYMBOL
- 9 ADA PARKING SIGN, MOUNT ON BUILDING
- 10 1,000 GALLON PROPANE TANK ON 6" CONC PAD W/ #4 REBAR 18" OC EA WAY. PROVIDE FENCING ALL SIDES, 4" W GATE, SEE DTLS 3 & 4 / A-101. PROVIDE (2) BOLLARDS, SEE DTL 15 / A-501.

- 11 NEW SPEED BUMP  
12 NEW SHADE TREE  
13 NEW 5' W SIDEWALK

revisions:	
1	04-22-2021 BID SET
2	06-10-2021 ADDENDUM #1
3	06-18-2021 ADDENDUM #2
4	09-17-21 SPR REVISIONS

## SITE PLAN - NEW WORK

sheet: **A-101**