

**PRELIMINARY DRAINAGE REPORT
FOR**

**Oak Grove Subdivision
Salem, Oregon**

**Prepared For:
R & S Kaminen
2500 Gleneagles Road
Lake Oswego, Oregon 97034**

April 21, 2022



1155 13th Street SE
Salem OR 97302

PHONE: (503) 363-9227
FAX: (503) 364-1260
EMAIL: mhendrick@mtengineering.net



Contents

Introduction	1
Existing Conditions.....	1
Soils	2
Infiltration	2
Water Quality Methodology	2
Water Quality Analysis.....	2
Water Quality Design	2
Stormwater Quantity Analysis	2
Detention System.....	4
Stormwater Quality Analysis.....	5
Conclusion.....	6

Appendix A	Maps
Appendix B	Soils Report
Appendix C	Time of Concentration
Appendix D	Stormwater Quantity & Quality Analysis

INTRODUCTION

The Oak Grove Subdivision is a proposed 54-lot subdivision located east of Lone Oak Road SE and south of La Cresta Drive SE. The parcel of land to be developed is Tax Lots 1900 through 2200 of Marion County Assessor's Map 08 3W 15CB. A vicinity map and supporting maps are in Appendix A of this report. An aerial image is below.




Project Site

Green Stormwater Infrastructure (GSI) to the Maximum Extent Feasible (MEF) is being used for the new developed areas per City of Salem Administrative Rules, Chapter 109, Division 004, Stormwater System, Appendix 4E and Ordinance No. 8-20 (Standards). All facilities will be constructed to meet the City of Salem Standards.

EXISTING CONDITIONS

The 12.5-acre site is irregular in the shape. Surface conditions consist of grassy meadow and Wooded areas. There are no identified wetlands or sensitive areas located on the property. A topographical high point ridge is located on the southerly property line near the terminus of the existing Sarah Renee Avenue SE. Drainage from this high point flows north, east, and west. The maximum relief is approximately 65.5-feet with a high point elevation of 561.5-feet. The abutting properties are zoned



single family residential with public improvements that include storm water conveyance systems. Appendix A contains multiple maps of the site.

Soils

The Natural Resources Conservation Service (NRCS) Soil Resource Report for Marion County was used to determine the Hydrological Soil Group classifications for runoff calculations. The report identifies the site soils to be Jory and Nekia soils. All the soils are in the hydrologic soil group C. The report is in Appendix B.

Infiltration

Infiltration testing will be performed at the site to determine percolation rates of the soils. It is anticipated that test results will indicate rates below 0.5 inches.

WATER QUALITY METHODOLOGY

Because of anticipated poor percolation rates of the soils and natural steep slopes that dominate the site, green stormwater facilities will be designed as combination facilities.

WATER QUALITY ANALYSIS

Water quality flow rates will be calculated with HydroCAD 10.00. The SCS TR-20 Unit Hydrograph method will be used to generate the hydrographs. A Type 1A storm and a 24-hour rainfall depth of 1.38 inches per hour will be used to determine the water quality flow rate.

WATER QUALITY DESIGN

The multiple combination facilities will provide water quality treatment by allowing for the removal of pollutants through sedimentation, adsorption onto surrounding vegetation, filtration, and biological uptake. The facilities will be designed per the City of Salem designed standards.

STORMWATER QUANTITY ANALYSIS

Stormwater quantity (Flow Control) is proposed to be handled by on-site detention from multiple facilities. The site was broken into four basins identified as B1-B4. Runoff from the developed basins will be routed to the facilities that ultimately controls runoff to pre-developed flow rates. Approximately 12.5-acres of land are being disturbed and developed. A basin map is in Appendix A.

Per Subsection 4.2(p)(3)(A) of the standards, one-half of the post development peak runoff rate of the two-year storm must be equal to or less than one-half of the peak runoff rate of the pre-developed two-year, 24-hour storm. This also applies to the 10, 25 and 100-year, 24-hour storm events.

The pre-developed flow rates were calculated using HydroCAD 10.00. Table 1 below lists the 24-hour rainfall depths used for the analysis of each storm event. Please note that the 2-year event was halved and then analyzed.

Table 1

Storm Event	24-hour Rainfall Depth (in)
2	2.2
10	3.2
25	3.6
100	4.4

For the pre-developed conditions, a time of concentration of 62 minutes was calculated for the site. The time of concentration data is in Appendix C. The calculations are incorporated in the HydroCAD output located in Appendix D. The entire area was classified as "City of Salem Pre-Development, HSG C" with a Curve Number (CN) of 72. A pre-developed basin map is in Appendix A.

The SCS TR-20 Unit Hydrograph method was used to generate the hydrographs. A Type 1A rainfall distribution was used with the above rainfall depths. Table 2 below identifies the allowable pre-developed release rate for each storm event for the entire site.

Table 2

Storm Event	Total Allowable Release Rate (cfs)
Half of 2-year	0.04
10-year	1.25
25-year	1.79
100-year	2.99

The post-developed flow rates were calculated using HydroCAD 10.00. A time of concentration of 10 minutes was assumed for the developed site. The calculations are incorporated in the HydroCAD output located in Appendix D. Because of existing surrounding streets and large lot areas, the site was classified as 40 percent "Impervious, HSG C" with a CN of 98 and 60 percent "> 75% Grass cover, HSG C" with a CN of 74. Table 3 below lists the CN values for the developed basin areas that will contribute storm water runoff to the detention systems. A developed basin map is in Appendix A.

Table 3

Basin	Impervious Area (Ac) CN = 98	Landscape Area (Ac) CN = 74	TOTAL Area (Ac)	Composite CN
B1	0.64	0.95	1.59	84
B2	1.72	2.57	4.29	84
B3	1.27	1.91	3.18	84
B4	1.39	2.09	3.48	84

The proposed four detention systems will be located near the lowest corners to maximize the capture of runoff. A basin map has been provided in Appendix A showing the location of the detention ponds/combination facilities.

DETENTION SYSTEM

In the detention analysis, was considered independent and draining into a combination facility. Each facility has been sized for full buildout conditions and are identified as B1 through B4. A basin map is in Appendix A. Site grading and conveyance pipe will direct stormwater runoff to each facility.

Based on the above design parameters, runoff from developed conditions will be controlled to or below half of the 2-year, 10-year, 25-year, and 100-year pre-developed release rates. The release rates and detention requirements were generated from the HydroCAD software, which can be seen in Appendix D. Tables 4 through 7 below summarizes the requirements for each storm event.

Table 4

Storm Event	Allowable Release Rate (cfs)	Required Detention Volume (ft ³)	Provided Detention Volume (ft ³)
Half of 2-year	0.01	995	8,000
10-year	0.16	4,344	8,000
25-year	0.23	4,823	8,000
100-year	0.38	5,656	8,000

(Basin 1 Allowable Release Rate and Detention Summary)

Table 5

Storm Event	Allowable Release Rate (cfs)	Required Detention Volume (ft ³)	Provided Detention Volume (ft ³)
Half of 2-year	0.01	2,685	17,000
10-year	0.43	11,721	17,000
25-year	0.61	13,012	17,000
100-year	1.02	15,260	17,000

(Basin 2 Allowable Release Rate and Detention Summary)

Table 6

Storm Event	Allowable Release Rate (cfs)	Required Detention Volume (ft ³)	Provided Detention Volume (ft ³)
Half of 2-year	0.01	1,990	12,000
10-year	0.32	8,689	12,000
25-year	0.45	9,645	12,000
100-year	0.76	11,312	12,000

(Basin 3 Allowable Release Rate and Detention Summary)

Table 7

Storm Event	Allowable Release Rate (cfs)	Required Detention Volume (ft ³)	Provided Detention Volume (ft ³)
Half of 2-year	0.01	2,178	13,000
10-year	0.35	9,508	13,000
25-year	0.50	10,555	13,000
100-year	0.83	12,379	13,000

(Basin 4 Allowable Release Rate and Detention Summary)

Flow control will be achieved with multiple orifices in a standard City of Salem control structure. The sizing of the orifice uses the standard orifice equation provided in the City of Salem Stormwater Management Manual.

STORMWATER QUALITY ANALYSIS

Water quality flow rates will be calculated using HydroCAD 10.00. The SCS TR-20 Unit Hydrograph method will be used to generate the hydrographs using a Type 1A rainfall distribution was used with a 1.38 rainfall depth. The detention facilities will incorporate combination facility sections to treat runoff and will be constructed per City of Salem standards.



CONCLUSION

Based on the presented information, the proposed design will meet the water quality and quantity standards. If there are any questions regarding this analysis or the design, please contact Matthew Hendrick at Multi/Tech Engineering by phone at (503) 363-9227 or via e-mail at mhendrick@mtengineering.net.



Appendix A

OAK GROVE

SEC. 15, T. 8 S., R. 3 W., W.M.
CITY OF SALEM
MARION COUNTY, OREGON

Owner / Developer:

Dr. Raghu Kamineni

2500 GLENEAGLES RD.

LAKE OSWEGO, OREGON 97034




ABBREVIATIONS

A.C.	ASPHALTIC CONCRETE	L.P.	LIGHT POLE
ACMP	ALUMINIZED CMP	M	METER, MAIN
ASSY.	ASSEMBLY	M.H.	MANHOLE
B.O.	BLOW OFF	MTL	METAL
B.F.V.	BUTTERFLY VALVE	O.H.	OVERHEAD
C & G	CURB & GUTTER	PC	POINT OF CURVE
CATV	CABLE TELEVISION	PCC	POINT OF CONTINUING CURVE
C.B.	CATCH BASIN	PED.	PEDESTAL
C.B.C.O.	CATCH BASIN CLEANOUT	PRC	POINT OF REVERSE CURVE
C.B.I.	CATCH BASIN INLET	PROP.	PROPOSED
C.L.	CENTERLINE	PT	POINT OF TANGENCY
CMP	CORRUGATED METAL PIPE	PUB.	PUBLIC
C.O.	CLEANOUT	PUE	PUBLIC UTILITY EASMT.
CONC.	CONCRETE	PVC	POLYVINYL CHLORIDE
CONST.	CONSTRUCT	PVT.	PRIVATE
CPP	CORRUGATED PLASTIC PIPE	P.P.	POWER POLE
D.I.	DUCTILE IRON	P.L.	PROPERTY LINE
DIA.	DIAMETER	R	RADIUS
DWG.	DRAWING	R-	RIM
EASMT.	EASEMENT	RD	ROOF DRAIN
E.G.	EXIST. GRADE / GROUND	R.O.W.	RIGHT-OF-WAY
EOP, E.P.	EDGE OF PAVEMENT	SAN.S. or S.S.	SANITARY SEWER
ELEC.	ELECTRIC	S	SLOPE
ELEV. or EL.	ELEVATION	S.Q.F.	STORMWATER QUALITY FACILITY
EX. or EXIST.	EXISTING	STA.	STATION
FT.	FEET	STD.	STANDARD
F.F.	FINISH FLOOR	STL.	STEEL
F.G.	FINISH GRADE	STM.DRN. or S.D.	STORM DRAIN
F.H.	FIRE HYDRANT	SVC.	SERVICE
F.M.	FORCE MAIN	SW	SIDEWALK
GUT. or GTR.	GUTTER	T.C.	TOP OF CURB
G.V.	GATE VALVE	TEL.	TELEPHONE
IMP.	IMPROVEMENT	TYP.	TYPICAL
INST.	INSERT	U.G.	UNDERGROUND
INV. or I-	INVERT	VL.	VAULT
L	LENGTH, LINE	W.M.	WATER MAIN

SYMBOLS

EXIST. PROP.	EXIST. PROP.


Drawing is NOT to scale



PARCEL SIZE:
DEVELOPABLE AREA — 12.158 Ac.
NUMBER OF UNITS — 58
DENSITY — 4.77 UNITS/AC.
LARGEST LOT — 13,268 S.F.
SMALLEST LOT — 5,039 S.F.
AVERAGE — 7,526 S.F.

EXISTING ZONE — RA & RS
COMPREHENSIVE DESG. — RS

UTILITIES:
CABLE — COMCAST CABLE SERVICES
ELECTRIC — P.G.E.
PHONE — FRONTIER COMMUNICATIONS
GAS — N.W. NATURAL
STORM DRAIN,
SANITARY SEWER,
WATER — CITY OF SALEM



B.M. 541.24
CITY OF SALEM BENCHMARK. A 2 INCH
ALUMINUM DISK SET IN CURB AT THE S.E.
CORNER OF MILDRED LN. S.E. & SAWGRASS
LN. S.E. (DATUM: NGVD 29)

SHEET INDEX

SHEET P1	COVER SHEET
SHEET P2	EXISTING CONDITIONS PLAN
SHEET P3	UTILITY PLAN
SHEET P4	STREET PLAN — KODA ST.
SHEET P5	STREET PLAN — RED OAK AV.
SHEET P6	STREET PLAN — OAK GROVE ST. 0+00 TO 6+50
SHEET P6	STREET PLAN — OAK GROVE ST. 6+00 TO 12+50
SHEET P8	STREET PLAN — SARAH RENEE AV.
SHEET P9	STREET PLAN — LONE OAK RD.
SHEET P10	LOT GRADING PLAN
SHEET P11	LOT LAYOUT PLAN
SHEET P12	TREE CONSERVATION OVERALL PLAN
SHEET P13	TREE CONSERVATION N.W. QUADRANT
SHEET P14	TREE CONSERVATION N.E. QUADRANT
SHEET P15	TREE CONSERVATION S.W. QUADRANT
SHEET P16	TREE CONSERVATION S.E. QUADRANT




COVER SHEET


OAK GROVE

NO CHANGES, MODIFICATIONS
OR REVISIONS TO BE
MADE WITHOUT WRITTEN
AUTHORIZATION FROM THE
DESIGN ENGINEER.
DIMENSIONS & NOTES TAKE
PRECEDENCE OVER
GRAPHICAL REPRESENTATION.

Design:	M.D.G.
Drawn:	D.G.G.
Checked:	J.J.G.
Date:	JUNE 2021
Scale:	AS SHOWN
As-Built:	---



08 3W 15CB



08 3W 15CB

08 3W 15CB
SALEM



MARION COUNTY, OREGON
NW1/4 SW1/4 SEC15 T8S R3W W.M.
SCALE 1" = 100'

LEGEND

- LINE TYPES
- Taxlot Boundary
 - Road Right-of-Way
 - Railroad Right-of-Way
 - Private Road ROW
 - Subdivision/Plat Bndry
 - Waterline - Taxlot Bndry
 - Historical Boundary
 - Easement
 - Railroad Centerline
 - Taxcode Line
 - Map Boundary
 - Waterline - Non Bndry

CORNER TYPES

- + 1/16TH Section Cor.
- ⊙ DLC Corner
- ⊕ 1/4 Section Cor.
- ⊕ 16, 15 Section Corner
- ⊕ 21, 22

NUMBERS


Tax Code Number
00 00 0

Acreage
0.25 AC

All acres listed are Net Acres, excluding any portions of the taxlot within public ROWs

NOTES

Tick Marks: A tick mark in the road indicates that the labeled dimension extends into the public ROW



CANCELLED NUMBERS

800			
-----	--	--	--

DISCLAIMER: THIS MAP WAS PREPARED FOR ASSESSMENT PURPOSES ONLY



Assessors Office
Cartography Dept

FOR ADDITIONAL MAPS VISIT OUR WEBSITE AT
www.co.marion.or.us

PLOT DATE: 10/16/2020

SALEM
08 3W 15CB

Drawing is NOT to scale



MULTI/TECH

ENGINEERING SERVICES, INC.
1155 13TH ST. S.E. SALEM, OR. 97302
PH. (503) 363-9227 FAX (503) 364-1260
www.mtengr.com office@mtengr.com

EXISTING
CONDITIONS
PLAN


OAK GROVE


NO CHANGES, MODIFICATIONS
OR REVISIONS TO BE
MADE WITHOUT WRITTEN
AUTHORIZATION FROM THE
DESIGN ENGINEER.
DIMENSIONS & NOTES TAKE
PRECEDENCE OVER
GRAPHICAL REPRESENTATION.

Design:	M.D.G.
Drawn:	D.G.G.
Checked:	J.J.G.
Date:	JUNE 2021
Scale:	AS SHOWN
As-Built:	----




EXPIRES: 06-30-2021
JOB # 7154





Facility Capacity
W.Q.F. #1 = 8,000 CF
W.Q.F. #2 = 17,000 CF
W.Q.F. #3 = 12,000 CF
W.Q.F. #4 = 13,000 CF



N.T.S.

B1


B2

B3

B4

Developed Conditions
7.56-acres (60%) >75% Grass cover, Good, HSG C, CN = 74
5.02-acres (40%), Impervious, HSG C, CN = 98

DRAINAGE BASINS	
BASIN	AREA (AC)
B1	1.59
B2	4.29
B3	3.18
B4	3.48
TOTAL	12.54



ENGINEERING SERVICES, INC.
1155 13TH ST. S.E. SALEM, OR. 97302
PH. (503) 363-9227 FAX (503) 366-1260
www.multi-tech-engineering.com


BASIN MAP

OAK GROVE

NO CHANGES, MODIFICATIONS OR REVISIONS TO BE MADE WITHOUT WRITTEN AUTHORIZATION FROM THE DESIGN ENGINEER.
DIMENSIONS & NOTES TAKE PRECEDENCE OVER GRAPHICAL REPRESENTATION.

71540 1 OF 1

Design:	M.D.G.
Drawn:	D.G.G.
Checked:	J.J.G.
Date:	JUNE 2021
Scale:	AS SHOWN
As-Built:	----



EXPIRES: 06-30-2021
JOB # 7154

1 OF 1



Appendix B



United States
Department of
Agriculture

NRCS

Natural
Resources
Conservation
Service

A product of the National
Cooperative Soil Survey,
a joint effort of the United
States Department of
Agriculture and other
Federal agencies, State
agencies including the
Agricultural Experiment
Stations, and local
participants


Custom Soil Resource Report for **Marion County Area, Oregon**

Oak Grove




December 2, 2021

Hydrologic Soil Group—Marion County Area, Oregon (Oak Grove)



MAP LEGEND

Area of Interest (AOI)









 Area of Interest (AOI)

Soils

Soil Rating Polygons





 A
 A/D
 B
 B/D
 C
 C/D
 D
 Not rated or not available

Soil Rating Lines

 A
 A/D
 B
 B/D
 C
 C/D
 D
 Not rated or not available

Soil Rating Points




 A
 A/D
 B
 B/D

 C
 C/D
 D
 Not rated or not available


Water Features

 Streams and Canals

Transportation

 Rails
 Interstate Highways
 US Routes
 Major Roads
 Local Roads

Background

 Aerial Photography

MAP INFORMATION

The soil surveys that comprise your AOI were mapped at 1:20,000.

Warning: Soil Map may not be valid at this scale.

Enlargement of maps beyond the scale of mapping can cause misunderstanding of the detail of mapping and accuracy of soil line placement. The maps do not show the small areas of contrasting soils that could have been shown at a more detailed scale.

Please rely on the bar scale on each map sheet for map measurements.

Source of Map: Natural Resources Conservation Service
 Web Soil Survey URL:
 Coordinate System: Web Mercator (EPSG:3857)

Maps from the Web Soil Survey are based on the Web Mercator projection, which preserves direction and shape but distorts distance and area. A projection that preserves area, such as the Albers equal-area conic projection, should be used if more accurate calculations of distance or area are required.

This product is generated from the USDA-NRCS certified data as of the version date(s) listed below.

Soil Survey Area: Marion County Area, Oregon
 Survey Area Data: Version 19, Oct 27, 2021

Soil map units are labeled (as space allows) for map scales 1:50,000 or larger.

Date(s) aerial images were photographed: Aug 1, 2018—Aug 31, 2018

The orthophoto or other base map on which the soil lines were compiled and digitized probably differs from the background imagery displayed on these maps. As a result, some minor shifting of map unit boundaries may be evident.

Hydrologic Soil Group

Map unit symbol	Map unit name	Rating	Acres in AOI	Percent of AOI
JoD	Jory silty clay loam, 12 to 20 percent slopes	C	6.0	49.6%
JoE	Jory silty clay loam, 20 to 30 percent slopes	C	4.2	34.4%
NeB	Nekia silty clay loam, 2 to 7 percent slopes	C	1.9	16.0%
Totals for Area of Interest			12.1	100.0%

Description

Hydrologic soil groups are based on estimates of runoff potential. Soils are assigned to one of four groups according to the rate of water infiltration when the soils are not protected by vegetation, are thoroughly wet, and receive precipitation from long-duration storms.

The soils in the United States are assigned to four groups (A, B, C, and D) and three dual classes (A/D, B/D, and C/D). The groups are defined as follows:

Group A. Soils having a high infiltration rate (low runoff potential) when thoroughly wet. These consist mainly of deep, well drained to excessively drained sands or gravelly sands. These soils have a high rate of water transmission.

Group B. Soils having a moderate infiltration rate when thoroughly wet. These consist chiefly of moderately deep or deep, moderately well drained or well drained soils that have moderately fine texture to moderately coarse texture. These soils have a moderate rate of water transmission.

Group C. Soils having a slow infiltration rate when thoroughly wet. These consist chiefly of soils having a layer that impedes the downward movement of water or soils of moderately fine texture or fine texture. These soils have a slow rate of water transmission.

Group D. Soils having a very slow infiltration rate (high runoff potential) when thoroughly wet. These consist chiefly of clays that have a high shrink-swell potential, soils that have a high water table, soils that have a claypan or clay layer at or near the surface, and soils that are shallow over nearly impervious material. These soils have a very slow rate of water transmission.


If a soil is assigned to a dual hydrologic group (A/D, B/D, or C/D), the first letter is for drained areas and the second is for undrained areas. Only the soils that in their natural condition are in group D are assigned to dual classes.



Appendix C

Time of Concentration Map

Drawing is NOT to scale



ENGINEERING SERVICES, INC.
1155 13TH ST. S.E. SALEM, OR. 97302
PH. (503) 363-9227 FAX (503) 364-1260
www.mtengr.com office@mtengr.com

EXISTING
CONDITIONS
PLAN

OAK GROVE

NO CHANGES, MODIFICATIONS
OR REDESIGNATIONS TO BE
MADE WITHOUT WRITTEN
AUTHORIZATION FROM THE
DESIGN ENGINEER.

DIMENSIONS & NOTES TAKE
PRECEDENCE OVER
GRAPHICAL REPRESENTATION.

Design: M.D.G.
Drawn: D.G.G.
Checked: J.J.G.
Date: JUNE 2021
Scale: AS SHOWN
As-Built: _____

EXPIRES: 06-30-2021
JOB # 7154

P2

Worksheet 3: Time of Concentration (T_c) or travel time (T_t)

Project Oak Grove	By M. Hendrick	Date 12/2021
Location Salem, Oregon	Checked	Date

Check one: ☒ Present ☐ Developed

Check one: ☒ T_c ☒ T_t through subarea

Notes: Space for as many as two segments per flow type can be used for each worksheet.
Include a map, schematic, or description of flow segments.

Sheet flow (Applicable to T_c only)

Segment ID	A-B	
1. Surface description (Table 4D-4)	Mixed	
2. Manning's roughness coefficient, n (Table 4D-4)	0.30	
3. Flow length, L (total L \geq 300 ft) ft	300	
4. Two-year 24-hour rainfall, P_2 in	2.2	
5. Land slope, s ft/ft	0.018	
6. $T_t = \frac{0.007 (nL)^{0.8}}{P_2^{0.5} s^{0.4}}$ Compute T_t hr	0.861	+
		= 0.861

Shallow concentrated flow

Segment ID	B-C	
7. Surface description (paved or unpaved)	Forest	
8. Flow length, Lft	510	
9. Watercourse slope, s ft/ft	0.118	
10. Average velocity, V (figure 3-1) ft/s	0.8	
11. $T_t = \frac{L}{3600 V}$ Compute T_t hr	0.177	+
		= 0.177

Channel flow

Segment ID		
12. Cross sectional flow area, a ft ²		
13. Wetted perimeter, p_w ft		
14. Hydraulic radius, $r = \frac{a}{p_w}$ Compute r ft		
15. Channel slope, s ft/ft		
16. Manning's roughness coefficient, n		
17. $V = \frac{1.49 r^{2/3} s^{1/2}}{n}$ Compute Vft/s		
18. Flow length, L ft		
19. $T_t = \frac{L}{3600 V}$ Compute T_t hr		+
20. Watershed or subarea T_c or T_t (add T_t in steps 6, 11, and 19) Hr		= 1.04

1.04 Hrs = 62 Minutes

Manning's Roughness Coefficients for Overland Sheet Flow	
Surface Types:	n
Impervious Areas	0.014
Gravel Pavement	0.02
Developed: Landscape Areas (Except Lawns)	0.08
Undeveloped: Meadow, Pasture, or Farm	0.15
Developed: Lawns	0.24
Pre-developed: Mixed	0.30
Pre-developed: Woodland and Forest	0.40
Development Types:	n
Commercial Development	0.015
Industrial Development, Heavy	0.04
Industrial Development, Light	0.05
Dense Residential (over 6 units/acre)	0.08
Normal Residential (3 to 6 units/acre)	0.20
Light Residential (1 to 3 units/acre)	0.30
Parks	0.40

Table 4D-4. Manning's Roughness Coefficients for Overland Sheet Flow




Figure 4D-2. Average Velocity of Shallow Concentrated Flow




Appendix D




Existing Conditions




Existing Conditions



Developed Conditions




Existing Conditions



Developed Conditions



Existing Conditions





Developed Conditions



Existing Conditions



Developed Conditions



Routing Diagram for 20220420 Hydrology Master

Prepared by {enter your company name here}, Printed 4/21/2022
HydroCAD® 10.10-7a s/n 09412 © 2021 HydroCAD Software Solutions LLC

20220420 Hydrology Master

Prepared by {enter your company name here}

HydroCAD® 10.10-7a s/n 09412 © 2021 HydroCAD Software Solutions LLC

Type IA 24-hr Half of 2-yr Rainfall=1.10"

Printed 4/21/2022

Summary for Subcatchment Ex: Existing Conditions

Runoff = 0.04 cfs @ 23.49 hrs, Volume= 1,122 cf, Depth= 0.02"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-52.00 hrs, dt= 0.02 hrs
Type IA 24-hr Half of 2-yr Rainfall=1.10"

Area (ac)	CN	Description
* 12.540	72	City of Salem Pre-developed, HSG C
12.540		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
62.0					Direct Entry, TR-55 Worksheet

Subcatchment Ex: Existing Conditions

Hydrograph



20220420 Hydrology Master

Prepared by {enter your company name here}

HydroCAD® 10.10-7a s/n 09412 © 2021 HydroCAD Software Solutions LLC

Type IA 24-hr Half of 2-yr Rainfall=1.10"

Printed 4/21/2022

Summary for Subcatchment B1: Existing Conditions

Runoff = 0.00 cfs @ 23.49 hrs, Volume= 142 cf, Depth= 0.02"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-52.00 hrs, dt= 0.02 hrs
Type IA 24-hr Half of 2-yr Rainfall=1.10"

Area (ac)	CN	Description
* 1.590	72	City of Salem Pre-developed, HSG C
1.590		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
62.0					Direct Entry, TR-55 Worksheet

Subcatchment B1: Existing Conditions

Hydrograph



Summary for Subcatchment 1B: Developed Conditions

Runoff = 0.03 cfs @ 8.10 hrs, Volume= 1,137 cf, Depth= 0.20"
 Routed to nonexistent node CMH


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-52.00 hrs, dt= 0.02 hrs
 Type IA 24-hr Half of 2-yr Rainfall=1.10"

Area (ac)	CN	Description
0.640	98	Paved parking, HSG C
0.950	74	>75% Grass cover, Good, HSG C
1.590	84	Weighted Average
0.950		59.75% Pervious Area
0.640		40.25% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
10.0					Direct Entry, Assumed

Subcatchment 1B: Developed Conditions

Hydrograph



20220420 Hydrology Master

Prepared by {enter your company name here}

HydroCAD® 10.10-7a s/n 09412 © 2021 HydroCAD Software Solutions LLC

Type IA 24-hr Half of 2-yr Rainfall=1.10"

Printed 4/21/2022

Summary for Subcatchment B2: Existing Conditions

Runoff = 0.01 cfs @ 23.49 hrs, Volume= 384 cf, Depth= 0.02"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-52.00 hrs, dt= 0.02 hrs
Type IA 24-hr Half of 2-yr Rainfall=1.10"

Area (ac)	CN	Description
* 4.290	72	City of Salem Pre-developed, HSG C
4.290		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
62.0					Direct Entry, TR-55 Worksheet

Subcatchment B2: Existing Conditions

Hydrograph



20220420 Hydrology Master

Prepared by {enter your company name here}

HydroCAD® 10.10-7a s/n 09412 © 2021 HydroCAD Software Solutions LLC

Type IA 24-hr Half of 2-yr Rainfall=1.10"

Printed 4/21/2022

Summary for Subcatchment 2B: Developed Conditions

Runoff = 0.07 cfs @ 8.10 hrs, Volume= 3,069 cf, Depth= 0.20"
Routed to nonexistent node CMH


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-52.00 hrs, dt= 0.02 hrs
Type IA 24-hr Half of 2-yr Rainfall=1.10"

Area (ac)	CN	Description
1.720	98	Paved parking, HSG C
2.570	74	>75% Grass cover, Good, HSG C
4.290	84	Weighted Average
2.570		59.91% Pervious Area
1.720		40.09% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
10.0					Direct Entry, Assumed

Subcatchment 2B: Developed Conditions

Hydrograph



Summary for Subcatchment B3: Existing Conditions

Runoff = 0.01 cfs @ 23.49 hrs, Volume= 285 cf, Depth= 0.02"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-52.00 hrs, dt= 0.02 hrs
Type IA 24-hr Half of 2-yr Rainfall=1.10"

Area (ac)	CN	Description
* 3.180	72	City of Salem Pre-developed, HSG C
3.180		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
62.0					Direct Entry, TR-55 Worksheet

Subcatchment B3: Existing Conditions

Hydrograph



Summary for Subcatchment 3B: Developed Conditions

Runoff = 0.05 cfs @ 8.10 hrs, Volume= 2,275 cf, Depth= 0.20"
 Routed to nonexistent node CMH


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-52.00 hrs, dt= 0.02 hrs
 Type IA 24-hr Half of 2-yr Rainfall=1.10"

Area (ac)	CN	Description
1.270	98	Paved parking, HSG C
1.910	74	>75% Grass cover, Good, HSG C
3.180	84	Weighted Average
1.910		60.06% Pervious Area
1.270		39.94% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
10.0					Direct Entry, Assumed

Subcatchment 3B: Developed Conditions

Hydrograph



20220420 Hydrology Master

Prepared by {enter your company name here}

HydroCAD® 10.10-7a s/n 09412 © 2021 HydroCAD Software Solutions LLC

Type IA 24-hr Half of 2-yr Rainfall=1.10"

Printed 4/21/2022

Summary for Subcatchment B4: Existing Conditions

Runoff = 0.01 cfs @ 23.49 hrs, Volume= 311 cf, Depth= 0.02"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-52.00 hrs, dt= 0.02 hrs
Type IA 24-hr Half of 2-yr Rainfall=1.10"

Area (ac)	CN	Description
* 3.480	72	City of Salem Pre-developed, HSG C
3.480		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
62.0					Direct Entry, TR-55 Worksheet

Subcatchment B4: Existing Conditions

Hydrograph



Summary for Subcatchment 4B: Developed Conditions

Runoff = 0.06 cfs @ 8.10 hrs, Volume= 2,489 cf, Depth= 0.20"
 Routed to nonexistent node CMH


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-52.00 hrs, dt= 0.02 hrs
 Type IA 24-hr Half of 2-yr Rainfall=1.10"

Area (ac)	CN	Description
1.390	98	Paved parking, HSG C
2.090	74	>75% Grass cover, Good, HSG C
3.480	84	Weighted Average
2.090		60.06% Pervious Area
1.390		39.94% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
10.0					Direct Entry, Assumed

Subcatchment 4B: Developed Conditions

Hydrograph



20220420 Hydrology Master

Prepared by {enter your company name here}

HydroCAD® 10.10-7a s/n 09412 © 2021 HydroCAD Software Solutions LLC

Type IA 24-hr 10-yr Rainfall=3.20"

Printed 4/21/2022

Summary for Subcatchment Ex: Existing Conditions

Runoff = 1.25 cfs @ 8.85 hrs, Volume= 42,318 cf, Depth= 0.93"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-52.00 hrs, dt= 0.02 hrs
Type IA 24-hr 10-yr Rainfall=3.20"

Area (ac)	CN	Description
* 12.540	72	City of Salem Pre-developed, HSG C
12.540		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
62.0					Direct Entry, TR-55 Worksheet

Subcatchment Ex: Existing Conditions

Hydrograph



20220420 Hydrology Master

Prepared by {enter your company name here}

HydroCAD® 10.10-7a s/n 09412 © 2021 HydroCAD Software Solutions LLC

Type IA 24-hr 10-yr Rainfall=3.20"

Printed 4/21/2022

Summary for Subcatchment B1: Existing Conditions

Runoff = 0.16 cfs @ 8.85 hrs, Volume= 5,366 cf, Depth= 0.93"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-52.00 hrs, dt= 0.02 hrs
Type IA 24-hr 10-yr Rainfall=3.20"

Area (ac)	CN	Description
* 1.590	72	City of Salem Pre-developed, HSG C
1.590		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
62.0					Direct Entry, TR-55 Worksheet

Subcatchment B1: Existing Conditions

Hydrograph



20220420 Hydrology Master

Prepared by {enter your company name here}

HydroCAD® 10.10-7a s/n 09412 © 2021 HydroCAD Software Solutions LLC

Type IA 24-hr 10-yr Rainfall=3.20"

Printed 4/21/2022

Summary for Subcatchment 1B: Developed Conditions

Runoff = 0.64 cfs @ 8.02 hrs, Volume= 9,710 cf, Depth= 1.68"
Routed to nonexistent node CMH


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-52.00 hrs, dt= 0.02 hrs
Type IA 24-hr 10-yr Rainfall=3.20"

Area (ac)	CN	Description
0.640	98	Paved parking, HSG C
0.950	74	>75% Grass cover, Good, HSG C
1.590	84	Weighted Average
0.950		59.75% Pervious Area
0.640		40.25% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
10.0					Direct Entry, Assumed

Subcatchment 1B: Developed Conditions

Hydrograph



20220420 Hydrology Master

Prepared by {enter your company name here}

HydroCAD® 10.10-7a s/n 09412 © 2021 HydroCAD Software Solutions LLC

Type IA 24-hr 10-yr Rainfall=3.20"

Printed 4/21/2022

Summary for Subcatchment B2: Existing Conditions

Runoff = 0.43 cfs @ 8.85 hrs, Volume= 14,477 cf, Depth= 0.93"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-52.00 hrs, dt= 0.02 hrs
Type IA 24-hr 10-yr Rainfall=3.20"

Area (ac)	CN	Description
* 4.290	72	City of Salem Pre-developed, HSG C
4.290		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
62.0					Direct Entry, TR-55 Worksheet

Subcatchment B2: Existing Conditions

Hydrograph



20220420 Hydrology Master

Prepared by {enter your company name here}

HydroCAD® 10.10-7a s/n 09412 © 2021 HydroCAD Software Solutions LLC

Type IA 24-hr 10-yr Rainfall=3.20"

Printed 4/21/2022


Summary for Subcatchment 2B: Developed Conditions

Runoff = 1.72 cfs @ 8.02 hrs, Volume= 26,198 cf, Depth= 1.68"
Routed to nonexistent node CMH

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-52.00 hrs, dt= 0.02 hrs
Type IA 24-hr 10-yr Rainfall=3.20"

Area (ac)	CN	Description
1.720	98	Paved parking, HSG C
2.570	74	>75% Grass cover, Good, HSG C
4.290	84	Weighted Average
2.570		59.91% Pervious Area
1.720		40.09% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
10.0					Direct Entry, Assumed

Subcatchment 2B: Developed Conditions

20220420 Hydrology Master

Prepared by {enter your company name here}

HydroCAD® 10.10-7a s/n 09412 © 2021 HydroCAD Software Solutions LLC

Type IA 24-hr 10-yr Rainfall=3.20"

Printed 4/21/2022

Summary for Subcatchment B3: Existing Conditions

Runoff = 0.32 cfs @ 8.85 hrs, Volume= 10,731 cf, Depth= 0.93"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-52.00 hrs, dt= 0.02 hrs
Type IA 24-hr 10-yr Rainfall=3.20"

Area (ac)	CN	Description
* 3.180	72	City of Salem Pre-developed, HSG C
3.180		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
62.0					Direct Entry, TR-55 Worksheet

Subcatchment B3: Existing Conditions

Hydrograph



20220420 Hydrology Master

Prepared by {enter your company name here}

HydroCAD® 10.10-7a s/n 09412 © 2021 HydroCAD Software Solutions LLC

Type IA 24-hr 10-yr Rainfall=3.20"

Printed 4/21/2022

Summary for Subcatchment 3B: Developed Conditions

Runoff = 1.28 cfs @ 8.02 hrs, Volume= 19,420 cf, Depth= 1.68"
Routed to nonexistent node CMH


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-52.00 hrs, dt= 0.02 hrs
Type IA 24-hr 10-yr Rainfall=3.20"

Area (ac)	CN	Description
1.270	98	Paved parking, HSG C
1.910	74	>75% Grass cover, Good, HSG C
3.180	84	Weighted Average
1.910		60.06% Pervious Area
1.270		39.94% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
10.0					Direct Entry, Assumed

Subcatchment 3B: Developed Conditions

Hydrograph



20220420 Hydrology Master

Prepared by {enter your company name here}

HydroCAD® 10.10-7a s/n 09412 © 2021 HydroCAD Software Solutions LLC

Type IA 24-hr 10-yr Rainfall=3.20"

Printed 4/21/2022

Summary for Subcatchment B4: Existing Conditions

Runoff = 0.35 cfs @ 8.85 hrs, Volume= 11,744 cf, Depth= 0.93"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-52.00 hrs, dt= 0.02 hrs
Type IA 24-hr 10-yr Rainfall=3.20"

Area (ac)	CN	Description
* 3.480	72	City of Salem Pre-developed, HSG C
3.480		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
62.0					Direct Entry, TR-55 Worksheet

Subcatchment B4: Existing Conditions

Hydrograph



20220420 Hydrology Master

Prepared by {enter your company name here}

HydroCAD® 10.10-7a s/n 09412 © 2021 HydroCAD Software Solutions LLC

Type IA 24-hr 10-yr Rainfall=3.20"

Printed 4/21/2022

Summary for Subcatchment 4B: Developed Conditions

Runoff = 1.40 cfs @ 8.02 hrs, Volume= 21,252 cf, Depth= 1.68"
Routed to nonexistent node CMH


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-52.00 hrs, dt= 0.02 hrs
Type IA 24-hr 10-yr Rainfall=3.20"

Area (ac)	CN	Description
1.390	98	Paved parking, HSG C
2.090	74	>75% Grass cover, Good, HSG C
3.480	84	Weighted Average
2.090		60.06% Pervious Area
1.390		39.94% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
10.0					Direct Entry, Assumed

Subcatchment 4B: Developed Conditions

Hydrograph



20220420 Hydrology Master

Prepared by {enter your company name here}

HydroCAD® 10.10-7a s/n 09412 © 2021 HydroCAD Software Solutions LLC

Type IA 24-hr 25-yr Rainfall=3.60"

Printed 4/21/2022

Summary for Subcatchment Ex: Existing Conditions

Runoff = 1.79 cfs @ 8.76 hrs, Volume= 54,025 cf, Depth= 1.19"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-52.00 hrs, dt= 0.02 hrs
Type IA 24-hr 25-yr Rainfall=3.60"

Area (ac)	CN	Description
* 12.540	72	City of Salem Pre-developed, HSG C
12.540		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
62.0					Direct Entry, TR-55 Worksheet

Subcatchment Ex: Existing Conditions

Hydrograph



20220420 Hydrology Master

Prepared by {enter your company name here}

HydroCAD® 10.10-7a s/n 09412 © 2021 HydroCAD Software Solutions LLC

Type IA 24-hr 25-yr Rainfall=3.60"

Printed 4/21/2022

Summary for Subcatchment B1: Existing Conditions

Runoff = 0.23 cfs @ 8.76 hrs, Volume= 6,850 cf, Depth= 1.19"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-52.00 hrs, dt= 0.02 hrs
Type IA 24-hr 25-yr Rainfall=3.60"

Area (ac)	CN	Description
* 1.590	72	City of Salem Pre-developed, HSG C
1.590		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
62.0					Direct Entry, TR-55 Worksheet

Subcatchment B1: Existing Conditions

Hydrograph



20220420 Hydrology Master

Prepared by {enter your company name here}

HydroCAD® 10.10-7a s/n 09412 © 2021 HydroCAD Software Solutions LLC

Type IA 24-hr 25-yr Rainfall=3.60"

Printed 4/21/2022

Summary for Subcatchment 1B: Developed Conditions

Runoff = 0.78 cfs @ 8.01 hrs, Volume= 11,673 cf, Depth= 2.02"
Routed to nonexistent node CMH


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-52.00 hrs, dt= 0.02 hrs
Type IA 24-hr 25-yr Rainfall=3.60"

Area (ac)	CN	Description
0.640	98	Paved parking, HSG C
0.950	74	>75% Grass cover, Good, HSG C
1.590	84	Weighted Average
0.950		59.75% Pervious Area
0.640		40.25% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
10.0					Direct Entry, Assumed

Subcatchment 1B: Developed Conditions

Hydrograph



20220420 Hydrology Master

Prepared by {enter your company name here}

HydroCAD® 10.10-7a s/n 09412 © 2021 HydroCAD Software Solutions LLC

Type IA 24-hr 25-yr Rainfall=3.60"

Printed 4/21/2022

Summary for Subcatchment B2: Existing Conditions

Runoff = 0.61 cfs @ 8.76 hrs, Volume= 18,482 cf, Depth= 1.19"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-52.00 hrs, dt= 0.02 hrs
Type IA 24-hr 25-yr Rainfall=3.60"

Area (ac)	CN	Description
* 4.290	72	City of Salem Pre-developed, HSG C
4.290		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
62.0					Direct Entry, TR-55 Worksheet

Subcatchment B2: Existing Conditions

Hydrograph



20220420 Hydrology Master

Prepared by {enter your company name here}

HydroCAD® 10.10-7a s/n 09412 © 2021 HydroCAD Software Solutions LLC

Type IA 24-hr 25-yr Rainfall=3.60"

Printed 4/21/2022

Summary for Subcatchment 2B: Developed Conditions


Runoff = 2.11 cfs @ 8.01 hrs, Volume= 31,494 cf, Depth= 2.02"
Routed to nonexistent node CMH

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-52.00 hrs, dt= 0.02 hrs
Type IA 24-hr 25-yr Rainfall=3.60"

Area (ac)	CN	Description
1.720	98	Paved parking, HSG C
2.570	74	>75% Grass cover, Good, HSG C
4.290	84	Weighted Average
2.570		59.91% Pervious Area
1.720		40.09% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
10.0					Direct Entry, Assumed

Subcatchment 2B: Developed Conditions



20220420 Hydrology Master

Prepared by {enter your company name here}

HydroCAD® 10.10-7a s/n 09412 © 2021 HydroCAD Software Solutions LLC

Type IA 24-hr 25-yr Rainfall=3.60"

Printed 4/21/2022

Summary for Subcatchment B3: Existing Conditions

Runoff = 0.45 cfs @ 8.76 hrs, Volume= 13,700 cf, Depth= 1.19"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-52.00 hrs, dt= 0.02 hrs
Type IA 24-hr 25-yr Rainfall=3.60"

Area (ac)	CN	Description
* 3.180	72	City of Salem Pre-developed, HSG C
3.180		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
62.0					Direct Entry, TR-55 Worksheet

Subcatchment B3: Existing Conditions

Hydrograph



20220420 Hydrology Master

Prepared by {enter your company name here}

HydroCAD® 10.10-7a s/n 09412 © 2021 HydroCAD Software Solutions LLC

Type IA 24-hr 25-yr Rainfall=3.60"

Printed 4/21/2022


Summary for Subcatchment 3B: Developed Conditions

Runoff = 1.57 cfs @ 8.01 hrs, Volume= 23,345 cf, Depth= 2.02"
Routed to nonexistent node CMH

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-52.00 hrs, dt= 0.02 hrs
Type IA 24-hr 25-yr Rainfall=3.60"

Area (ac)	CN	Description
1.270	98	Paved parking, HSG C
1.910	74	>75% Grass cover, Good, HSG C
3.180	84	Weighted Average
1.910		60.06% Pervious Area
1.270		39.94% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
10.0					Direct Entry, Assumed

Subcatchment 3B: Developed Conditions

20220420 Hydrology Master

Prepared by {enter your company name here}

HydroCAD® 10.10-7a s/n 09412 © 2021 HydroCAD Software Solutions LLC

Type IA 24-hr 25-yr Rainfall=3.60"

Printed 4/21/2022

Summary for Subcatchment B4: Existing Conditions

Runoff = 0.50 cfs @ 8.76 hrs, Volume= 14,992 cf, Depth= 1.19"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-52.00 hrs, dt= 0.02 hrs
Type IA 24-hr 25-yr Rainfall=3.60"

Area (ac)	CN	Description
* 3.480	72	City of Salem Pre-developed, HSG C
3.480		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
62.0					Direct Entry, TR-55 Worksheet

Subcatchment B4: Existing Conditions

Hydrograph



20220420 Hydrology Master

Prepared by {enter your company name here}

HydroCAD® 10.10-7a s/n 09412 © 2021 HydroCAD Software Solutions LLC

Type IA 24-hr 25-yr Rainfall=3.60"

Printed 4/21/2022


Summary for Subcatchment 4B: Developed Conditions

Runoff = 1.72 cfs @ 8.01 hrs, Volume= 25,547 cf, Depth= 2.02"
Routed to nonexistent node CMH

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-52.00 hrs, dt= 0.02 hrs
Type IA 24-hr 25-yr Rainfall=3.60"

Area (ac)	CN	Description
1.390	98	Paved parking, HSG C
2.090	74	>75% Grass cover, Good, HSG C
3.480	84	Weighted Average
2.090		60.06% Pervious Area
1.390		39.94% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
10.0					Direct Entry, Assumed

Subcatchment 4B: Developed Conditions

20220420 Hydrology Master

Prepared by {enter your company name here}

HydroCAD® 10.10-7a s/n 09412 © 2021 HydroCAD Software Solutions LLC

Type IA 24-hr 100-yr Rainfall=4.40"

Printed 4/21/2022

Summary for Subcatchment Ex: Existing Conditions

Runoff = 2.99 cfs @ 8.74 hrs, Volume= 79,515 cf, Depth= 1.75"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-52.00 hrs, dt= 0.02 hrs
Type IA 24-hr 100-yr Rainfall=4.40"

Area (ac)	CN	Description
* 12.540	72	City of Salem Pre-developed, HSG C
12.540		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
62.0					Direct Entry, TR-55 Worksheet

Subcatchment Ex: Existing Conditions

Hydrograph



Summary for Subcatchment B1: Existing Conditions

Runoff = 0.38 cfs @ 8.74 hrs, Volume= 10,082 cf, Depth= 1.75"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-52.00 hrs, dt= 0.02 hrs
Type IA 24-hr 100-yr Rainfall=4.40"

Area (ac)	CN	Description
* 1.590	72	City of Salem Pre-developed, HSG C
1.590		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
62.0					Direct Entry, TR-55 Worksheet

Subcatchment B1: Existing Conditions

Hydrograph



20220420 Hydrology Master

Prepared by {enter your company name here}

HydroCAD® 10.10-7a s/n 09412 © 2021 HydroCAD Software Solutions LLC

Type IA 24-hr 100-yr Rainfall=4.40"

Printed 4/21/2022

Summary for Subcatchment 1B: Developed Conditions

Runoff = 1.09 cfs @ 8.00 hrs, Volume= 15,738 cf, Depth= 2.73"
Routed to nonexistent node CMH


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-52.00 hrs, dt= 0.02 hrs
Type IA 24-hr 100-yr Rainfall=4.40"

Area (ac)	CN	Description
0.640	98	Paved parking, HSG C
0.950	74	>75% Grass cover, Good, HSG C
1.590	84	Weighted Average
0.950		59.75% Pervious Area
0.640		40.25% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
10.0					Direct Entry, Assumed

Subcatchment 1B: Developed Conditions

Hydrograph



20220420 Hydrology Master

Prepared by {enter your company name here}

HydroCAD® 10.10-7a s/n 09412 © 2021 HydroCAD Software Solutions LLC

Type IA 24-hr 100-yr Rainfall=4.40"

Printed 4/21/2022

Summary for Subcatchment B2: Existing Conditions

Runoff = 1.02 cfs @ 8.74 hrs, Volume= 27,203 cf, Depth= 1.75"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-52.00 hrs, dt= 0.02 hrs
Type IA 24-hr 100-yr Rainfall=4.40"

Area (ac)	CN	Description
* 4.290	72	City of Salem Pre-developed, HSG C
4.290		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
62.0					Direct Entry, TR-55 Worksheet

Subcatchment B2: Existing Conditions

Hydrograph



20220420 Hydrology Master

Prepared by {enter your company name here}

HydroCAD® 10.10-7a s/n 09412 © 2021 HydroCAD Software Solutions LLC

Type IA 24-hr 100-yr Rainfall=4.40"

Printed 4/21/2022

Summary for Subcatchment 2B: Developed Conditions

Runoff = 2.93 cfs @ 8.00 hrs, Volume= 42,463 cf, Depth= 2.73"
Routed to nonexistent node CMH


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-52.00 hrs, dt= 0.02 hrs
Type IA 24-hr 100-yr Rainfall=4.40"

Area (ac)	CN	Description
1.720	98	Paved parking, HSG C
2.570	74	>75% Grass cover, Good, HSG C
4.290	84	Weighted Average
2.570		59.91% Pervious Area
1.720		40.09% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
10.0					Direct Entry, Assumed

Subcatchment 2B: Developed Conditions

Hydrograph



20220420 Hydrology Master

Prepared by {enter your company name here}

HydroCAD® 10.10-7a s/n 09412 © 2021 HydroCAD Software Solutions LLC

Type IA 24-hr 100-yr Rainfall=4.40"

Printed 4/21/2022

Summary for Subcatchment B3: Existing Conditions

Runoff = 0.76 cfs @ 8.74 hrs, Volume= 20,164 cf, Depth= 1.75"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-52.00 hrs, dt= 0.02 hrs
Type IA 24-hr 100-yr Rainfall=4.40"

Area (ac)	CN	Description
* 3.180	72	City of Salem Pre-developed, HSG C
3.180		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
62.0					Direct Entry, TR-55 Worksheet

Subcatchment B3: Existing Conditions

Hydrograph



20220420 Hydrology Master

Prepared by {enter your company name here}

HydroCAD® 10.10-7a s/n 09412 © 2021 HydroCAD Software Solutions LLC

Type IA 24-hr 100-yr Rainfall=4.40"

Printed 4/21/2022

Summary for Subcatchment 3B: Developed Conditions

Runoff = 2.17 cfs @ 8.00 hrs, Volume= 31,476 cf, Depth= 2.73"
Routed to nonexistent node CMH


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-52.00 hrs, dt= 0.02 hrs
Type IA 24-hr 100-yr Rainfall=4.40"

Area (ac)	CN	Description
1.270	98	Paved parking, HSG C
1.910	74	>75% Grass cover, Good, HSG C
3.180	84	Weighted Average
1.910		60.06% Pervious Area
1.270		39.94% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
10.0					Direct Entry, Assumed

Subcatchment 3B: Developed Conditions

Hydrograph



20220420 Hydrology Master

Prepared by {enter your company name here}

HydroCAD® 10.10-7a s/n 09412 © 2021 HydroCAD Software Solutions LLC

Type IA 24-hr 100-yr Rainfall=4.40"

Printed 4/21/2022

Summary for Subcatchment B4: Existing Conditions

Runoff = 0.83 cfs @ 8.74 hrs, Volume= 22,066 cf, Depth= 1.75"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-52.00 hrs, dt= 0.02 hrs
Type IA 24-hr 100-yr Rainfall=4.40"

Area (ac)	CN	Description
* 3.480	72	City of Salem Pre-developed, HSG C
3.480		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
62.0					Direct Entry, TR-55 Worksheet

Subcatchment B4: Existing Conditions

Hydrograph



Summary for Subcatchment 4B: Developed Conditions

Runoff = 2.38 cfs @ 8.00 hrs, Volume= 34,445 cf, Depth= 2.73"
 Routed to nonexistent node CMH

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-52.00 hrs, dt= 0.02 hrs
 Type IA 24-hr 100-yr Rainfall=4.40"

Area (ac)	CN	Description
1.390	98	Paved parking, HSG C
2.090	74	>75% Grass cover, Good, HSG C
3.480	84	Weighted Average
2.090		60.06% Pervious Area
1.390		39.94% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
10.0					Direct Entry, Assumed

Subcatchment 4B: Developed Conditions

Hydrograph

